

U.S. Department of Housing and Urban Development

Suzanne Harder: suzanne.harder@occr.ocgov.com

451 Seventh Street, SW Washington, DC 20410 www.hud.gov

espanol.hud.gov

Environmental Assessment Determinations and Compliance Findings for HUD-assisted Projects 24 CFR Part 58

This is a suggested format that may be used by Responsible Entities to document completion of an Environmental Assessment.

|--|

Direct Comments to:

Project Name:	The Orion
Responsible Entity:	OC Housing & Community Development 1501 E. Saint Andrew Place, First Floor Santa Ana, California 92705
Grant Recipient (if different than Responsible Entity):	
State/Local Identifier:	CA/059
Preparer:	Suzanne Harder, OC Housing and Community Development
Certifying Officer Name and Title:	Julia Bidwell, Director OC Housing & Community Development
Grant Recipient (if different than Responsible Entity):	
Consultant (if applicable):	Jonathan Rigg, Dudek 605 NE 21st Street, Suite 200 Portland, Oregon 97232 503.956.1444

Project Location:

The Orion (project or proposed project), is located at 1800 E. La Veta, Orange, California 92866 (see **Figure 1**). The project site consists of 3.85 acres on an H-shaped lot and is currently occupied by the former campus of the Rehabilitation Institute of Southern California and associated parking and landscaped areas. A 1,300-square-foot house previously located on the project site was demolished in 2022 due to extensive fire damage. The site is located on Assessor's Parcel Number 390-322-15 and is currently zoned as Residential Multiple Family (R-3) by the City of Orange (City). The proposed project site is bordered by commercial and multifamily housing to the south and by multifamily housing to the north, east, and west. The proposed project site is located near markets, restaurants, healthcare, retail, and other services along South Tustin Avenue to the East and East Chapman Avenue to the North.

Description of the Proposed Project [24 CFR 50.12 & 58.32; 40 CFR 1508.25]:

The proposed project is a partnership between USA Properties Fund, Inc. and Riverside Charitable Corporation (Developers), the City of Orange (City) and the County of Orange (County). The proposed project would demolish the existing Rehabilitation Institute of Southern California campus, which is currently unoccupied, and construct a new affordable housing community with 166 units. The new housing development would be reserved for seniors aged 62 years and older earning between 30 to 70% of the area mean income (AMI). Of the 166 total units, approximately 111 apartments would have a 1bedroom floor plan and 55 apartments would have a 2--bedroom floor plan, with unit sizes ranging from 537 to 700 square feet. Eight 1-bedroom units would be restricted to Mental Health Services Act (MHSA) eligible seniors experiencing homelessness or at-risk of homelessness with rents set at 30% AMI that would be subsidized with Orange County Housing Authority Housing Choice Project-Based Vouchers. Two of the 2--bedroom units would be reserved for property management staff living on site. Residential units and shared community spaces would be split between three separate buildings, two 4-story buildings and one 2-4-story building, totaling approximately 145,716 gross square feet (see Attachment 1). The new buildings would reflect the mid-century architectural style of neighboring properties with a contemporary twist. Clean lines and a nostalgic color palette would blend the project into the existing community. Exterior finishes and materials include painted stucco, a black aluminum storefront system, and metal rail panels and awnings at balconies. Project design would also include sustainable features consistent with the California Green Building Standards Code (CALGreen), including but not limited to supplying equipment to facilitate future installation of electric vehicle (EV) parking spaces and waterefficient landscaping. In addition, the project would utilize energy efficient appliances and low flow plumbing faucets and fixtures.

Site access would be provided from existing driveways located along La Veta Avenue and East Fairway Drive. Neither driveway would be gated. An existing 6 -foot sidewalk wraps around the northern, western, and southern edges of the project site. Proposed pedestrian and bicycle gates would allow resident access to all street frontages as well as to the Santiago Creek Trail and bike path to the north. The project would include 172 parking stalls in a surface lot on site. Approximately 5 parking stalls would be reserved for the leasing area and unloading/loading zones, with the remaining 167 available for resident use. Other on-site amenities include elevators in each building, a 1,318-square-foot club room, computer room, fitness center, food storage lockers, laundry rooms, and bike stalls. The project would also include approximately 17,914 square feet of outdoor courtyard space with several barbeque and outdoor bench and picnic seating areas, a resident-tended garden, and a fenced dog park.

Statement of Purpose and Need for the Proposal [40 CFR 1508.9(b)]:

As demand increases for County services and as the County's population increases, the need for additional housing and access to government services has also increased.

The proposed project's objectives are as follows:

- Create new affordable, safe, attractive, and service-enriched residences for low-income seniors (aged 62 years and older) earning between 30-70% of the area mean income.
- Create 8 supportive housing for seniors experiencing homelessness or at-risk of homelessness who meet MHSA eligibility criteria.
- Create a housing community that fits into and improves the existing neighborhood in style, texture, scale, and relation to the street.

Existing Conditions and Trends [24 CFR 58.40(a)]:

The project site is currently occupied by the vacant Rehabilitation Institute of Southern California building. The building is 2 stories tall and contains approximately 107,586 square feet. The project site also includes an indoor swimming pool, playground, asphalt-paved parking areas, and landscaping. Based on a review of historical resources in the Phase I Environmental Assessment (ESA) for the project site completed by AEI Consultants in September 2023, the project site consisted of a small house and unimproved land in 1896, then was used for agricultural production from 1938 until 1961. The existing commercial building was constructed in 1966, with additions to the initial structure completed in 1979 and 1987. The small house remained on the property until 2022 when it was demolished after fire damaged the structure. Areas adjacent to the project site are developed with commercial and residential uses, as follows:

- North: Residential (multi-family housing); East La Veta Avenue,
- East: Residential (multi-family housing),
- **South:** Residential (multi-family housing) and Commercial (7-Eleven/Tustin 76 Station); East Fairway Drive,
- West: Residential (multi-family housing); South Tustin Street (see Figure 2).

Funding Information

Grant Number	HUD Program	Funding Amount
(No grant number for	8 Orange County Housing	\$2,935,680
vouchers)	Authority Housing Choice	
	Project-Based Vouchers	

Estimated Total HUD Funded Amount: \$2,935,680

Other Funding (non-HUD): City of Orange Low- and Moderate-Income Housing Asset Fund (\$2,200,000)

Estimated Total Project Cost (HUD and non-HUD funds) [24 CFR 58.32(d)]: \$61,630,309

Compliance with 24 CFR 50.4, 58.5, and 58.6 Laws and Authorities

Record below the compliance or conformance determinations for each statute, executive order, or regulation. Provide credible, traceable, and supportive source documentation for each authority. Where applicable, complete the necessary reviews or consultations and obtain or note applicable permits of approvals. Clearly note citations, dates/names/titles of contacts, and page references. Attach additional documentation as appropriate.

Compliance Factors: Statutes, Executive Orders, and Regulations listed at 24 CFR §58.5 and §58.6	Are formal compliance steps or mitigation required?	Compliance determinations
STATUTES, EXECUTIVE OF and 58.6	RDERS, AND R	EGULATIONS LISTED AT 24 CFR 50.4
Airport Hazards 24 CFR Part 51 Subpart D	Yes No	HUD's policy is to apply standards to prevent incompatible development around civil airports or military airfields, consistent with Title 24 of the Code of Federal Regulations (CFR), Part 51, Subpart D. According to the U.S. Environmental Protection Agency's (EPA) NEPAssist tool (https://nepassisttool.epa.gov//.aspx), there are no military airports within 15,000 feet of the subject property, or civilian airports within 2,500 feet of the subject property. The nearest civilian airport is John Wayne Airport (approximately 8.8 miles southwest of the project site) and the closest military airport is Los Alamitos Army Airfield Base Operations (about 12.4 miles west of the project site). Therefore, the project is in compliance with airport hazards requirements (see Attachment 2; see Environmental Review Record [ERR] 1).
Coastal Barrier Resources Coastal Barrier Resources Act, as amended by the Coastal Barrier Improvement Act of 1990 [16 USC 3501]	Yes No	According to Coastal Barrier Resources System (CBRS) information (https://fwsprimary.wim.usgs.gov/v2/), there are no units of the CBRS in California, and the project site is not within a CBRS unit (USFWS 2019). Therefore, the project is in compliance with the Coastal Barrier Resources Act (see Attachment 3; see ERR 2).
Flood Insurance	Yes No	The Flood Disaster Protection Act of 1973 (42 USC 4012a) requires that projects receiving federal assistance and located in an area

Flood Disaster Protection Act of identified by FEMA as being within a Special 1973 and National Flood Flood Hazard Area (SFHA) be covered by flood Insurance Reform Act of 1994 insurance under the National Flood Insurance [42 USC 4001-4128 and 42 USC Program (NFIP). SFHAs are hazard areas that 5154a] are subject to inundation by the base flood (1%annual-chance flood) and are labeled on flood maps as zones starting with the letters A or V. According to the Federal Emergency Management Agency's (FEMA) Flood Insurance Rate Map No. 06059C0164J, effective December 3, 2009 (https://msc.fema.gov/portal/home), the project site is located within unshaded Zone X, in an area outside of the 100- and 500- year flood zones where the flood potential is minimal. The project site is not within a SFHA. According to the NFIP Community Status Book (https://www.fema.gov/flood-insurance/workwith-nfip/community-status-book), the project site is in Community ID 060228# for the City of Orange, which is a participating community in the NFIP in good standing. Therefore, the project is in compliance with flood insurance requirements (see Attachment 4; see ERR 3). STATUTES, EXECUTIVE ORDERS, AND REGULATIONS LISTED AT 24 CFR 50.4 & 58.5 Clean Air The Clean Air Act was implemented to remedy Yes No the damaging effects that bad air quality can \boxtimes П have on human health and the environment and Clean Air Act, as amended, was most recently revised in 1990, when major particularly section 176(c) & (d); changes were enacted. The Clean Air Act is 40 CFR Parts 6, 51, 93 administered by the EPA, which sets National Ambient Air Quality Standards (NAAQS). NAAQS are limits on certain "criteria" air pollutants, including limits on how much of the pollutants can be in the air anywhere in the U.S. Geographic areas that are in compliance with the NAAOS are called "attainment areas," while areas that do not meet the standards are called "nonattainment" areas. Areas that were previously designated as nonattainment areas but have now met the standard (with EPA approval of a suitable air quality plan) are called "maintenance" areas.

The proposed project falls under the jurisdiction of the South Coast Air Quality Management District (SCAQMD) within the South Coast Air Basin. Orange County is currently in a nonattainment zone for federal ozone (8-hour ozone) and particulate matter from greenhouse gases (fine particulate matter [PM_{2.5}]). Federal ozone in Orange County has been classified as extreme, and PM_{2.5} has been classified as serious (EPA 2024). According to NEPAssist, which uses the EPA's Office of Air and Radiation data. Orange County is in a maintenance zone for coarse particulate matter (PM₁₀), carbon monoxide (CO), and nitrogen dioxide (NO₂). Orange County is in attainment for all other criteria pollutants. To meet HUD air quality guidelines, the proposed project must follow the State Implementation Plan, which describes how an area will meet the NAAQS. State Implementation Plan guidelines require the proposed project to keep its criteria pollutant emissions below SCAQMD's significance thresholds (SCAQMD 2023).

The project site's location close to public transportation is consistent with regional efforts to improve transit availability and would reduce the level of emissions (PM_{2.5}) associated with motor vehicle travel. By developing affordable housing consistent with the growth anticipated by the City's Housing Element and existing zoning and land use designations, the proposed project is in compliance with the Regional Air Quality Strategy, State Implementation Plan, and Air Quality Management Plan for this locality.

Air quality at the project site could be negatively impacted by fugitive dust (PM_{10}) and other particulate air pollutants ($PM_{2.5}$) released during construction-related activities, such as land clearing and grading. Exhaust emissions (oxides of nitrogen [NO_x] and CO) released by heavy construction vehicles could also temporarily impact air quality. Adverse impacts to air quality during construction would be managed by implementing mitigation measures for fugitive dust control in compliance with SCQAMD Rule 403. This guideline identifies measures to reduce fugitive dust that are required to be implemented

		at all construction sites within the South Coast Air Basin (SCAQMD 2005) (Mitigation Measure [MM]-AIR-1 ; see section below for all mitigation measures). The California Emissions Estimator Model (CalEEMod) was used to estimate annual criteria air pollutant emissions during the construction and operational phases for the proposed project. Pollutant estimates, including for PM _{2.5} , PM ₁₀ , NOx, volatile organic compounds, and CO, found that all would be below de minimis thresholds during the construction and operational phases. Estimated annual construction emissions for the proposed project, assuming construction would occur in 2024–2025, are approximately 610.08 metric tons (30-year amortized emissions would reduce this to 20.34 metric tons). Estimated annual emissions during the operational phase are approximately 718.89 metric tons. In total, the proposed project is estimated to produce 739.23 metric tons of
		is estimated to produce 739.23 metric tons of emissions per year. Daily emissions from the proposed project would not exceed the SCAQMD's regional construction or operation emissions thresholds (see Attachment 5 ; see ERR 4).
Coastal Zone Management Coastal Zone Management Act, sections 307the & (d)	Yes No	According to the California Coastal Commission's Coastal Zone boundary maps (https://www.coastal.ca.gov//czb/), the project site is not within the Coastal Zone (CCC 2019). Therefore, the project is in compliance with the Coastal Zone Management Act (see Attachment 6; see ERR 5).
Contamination and Toxic Substances 24 CFR Part 50.3(i) & 58.5(i)(2)	Yes No	HUD policy, as described in Section 50.3(i) and Section 58.5(i)(2), states the following: (1) all property proposed for use in HUD programs be free of hazardous materials, contamination, toxic chemicals and gasses, and radioactive substances, where a hazard could affect the health and safety of occupants or conflict with the intended utilization of the property. (2) HUD environmental review of multifamily and non-residential properties shall include evaluation of previous uses of the site and other evidence of contamination on or near the site, to assure that occupants of proposed sites are not adversely affected by the hazards.

- (3) Particular attention should be given to any proposed site on or in the general proximity of such areas as dumps, landfills, industrial sites, or other locations that contain, or may have contained, hazardous wastes.
- (4) The responsible entity shall use current techniques by qualified professionals to undertake investigations determined necessary.

Sites known or suspected to be contaminated by toxic chemicals or radioactive materials include, but are not limited to, sites: (i) listed on an EPA Superfund National Priorities or the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) List, or equivalent State list; (ii) located within 3,000 feet of a toxic or solid waste landfill site; or (iii) with an underground storage tank (UST) (which is not a residential fuel tank).

A Phase I ESA conducted by AEI in September 2023 found no recognized environmental conditions (RECs), historical RECs, or controlled RECs on the project site (Attachment 7). No evidence of aboveground storage tanks or underground storage tanks were observed on site. Small quantities of general cleaning and maintenance supplies and waste oil/hydraulic fluid were observed on site during the site visit. Cleaning supplies and detergents were packaged in consumer quantities and are not expected to represent an environmental concern. Maintenance supplies, including spray paints and laminates, were observed on the first floor. Containers appeared to be properly labeled and stored at the time of the assessment with no signs of leaks, stains, or spills. The storage and use of maintenance supplies would not pose a significant threat to the environmental condition of the proposed project site. Additionally, no spills, stains, or other indications of a leakage were observed on site. Waste oil and hydraulic fluid in a 5-gallon container was observed on site in the elevator equipment room. A second unlabeled 5-gallon container, closed and in good condition, was also observed in the elevator equipment room. Though not labeled, the container was presumed to similarly contain waste oil/hydraulic fluid given its location in the elevator equipment room. Typical pool treatment chemicals, such as muriatic acid and chlorine

were not observed, but were presumed to have previously been on site to maintain the indoor swimming pool on the proposed project site. The prior storage and use of pool cleaning chemicals on site does not represent an environmental concern.

Toxic polychlorinated biphenyls (PCBs) have been historically used in electric equipment, though their use outside of totally enclosed equipment was prohibited in 1977. Transformers installed prior to 1977 may contain PCBs, while transformers installed after 1977 are unlikely to contain PCBs. Three pole-mounted transformers belonging to Southern California Edison were observed on site. Since the building was constructed prior to 1978, the potential exists that hydraulic fluid within the transformers contains PCBs. Federal Regulations (40 CFR 761 Subpart G) requires any release of material containing >50 ppm PCB and occurring after May 4, 1987, to be cleaned up by the transformer owner following the EPA's PCB spill cleanup policy. The transformers appeared to be in good condition, without leaks or stains, and do not represent an environmental concern at this time. Since the existing building on site was constructed prior to 1978, PCBs could also be present in hydraulic fluid used to power two hydraulic elevators and two wheelchair lifts at the proposed project site. No leaks or stains were observed at the base of the equipment during the site reconnaissance. While this equipment does not represent an environmental concern, any oil and associated material should be handled and disposed of in accordance with regulatory guidelines when this equipment is removed as part of the planned project site redevelopment.

Several floor drains were observed in the kitchens, maintenance closets, and indoor pool area on site. Hazardous substances and petroleum products were not observed in the vicinity of the drains and no staining indicative of improper discharge of hazardous substances or petroleum products was apparent near the drains. As a result, the floor drains do not represent an environmental concern. A single gas tank labeled as containing Helium was observed

on site. However, since Helium is not considered a toxic substance or gas according to the Specific Hazardous Substances list (Appendix I to Subpart C of Part 51), the tank does not represent an environmental concern. A dryer-type transformer was also observed on site. Since dry-type transformers do not utilize oils for dielectric fluid, this transformer does not represent an environmental concern. T

Radon is a radioactive gas which has been identified as a human carcinogen. The EPA recommends that homeowners in areas with radon screening levels greater than 4 Picocuries per liter (pCi/L) conduct mitigation of radon gas to reduce exposure. In compliance with HUD's radon policy notice published in January 2024, indoor radon testing at the new affordable housing community will occur after construction is complete and before residents move in. If testing determines that indoor radon levels are or may be above 4pCi/L, then the County must document and implement a mitigation plan. The mitigation plan must identify the radon level onsite, describe the radon reduction system that will be installed, establish an ongoing maintenance plan, establish a reasonable timeframe for system implementation, and require post-installation testing by a licensed radon professional (MM-TOX-1).

The Phase I ESA completed by AEI should not be construed as a mold survey or inspection. However, during the site reconnaissance, AEI observed interior areas of the existing building on site to identify the presence of mold. This activity was not designed to discover all areas which may be affected by mold growth, but intended to provide indication if significant mold growth was present on site. Obvious visible signs of mold growth or conditions conducive for suspect mold growth were observed in the utility closet on the second floor (near the stairs) of the existing building. Additionally, multiple water-stained ceiling tiles were observed throughout the project site. Since the presence of suspect mold may pose a health and safety concern to construction workers during future demolition activities, AEI recommends a mold and water intrusion assessment for the proposed project site if renovation of the existing building

were to occur. However, since the proposed project involves demolition of the existing building and then new construction of the affordable housing community, a mold and water intrusion assessment is not required.

A Pre-Renovation Asbestos and Lead Assessment for the project site was completed by EFI Global in August 2020. The purpose of the assessment was to identify whether asbestoscontaining materials (ACMs) and/or lead-based paint (LBP) were present so that they may be properly managed prior to demolition of the structure. The scope of the ACM assessment included reviewing building and/or previous investigation records, visually identifying homogenous sample areas, collecting bulk samples of building materials suspected to contain asbestos, recording the friability and condition of suspect building materials, interpreting laboratory results, and producing a written report of findings and determinations. ACMs were identified in multiple areas throughout the existing building. All ACMs were found to be in good condition at the time of the assessment. See Tables 2 and 3 in the Pre-Renovation Asbestos and Lead Assessment (Attachment 8) for a list of ACM Homogenous Materials, their locations, and approximate quantities. Materials found to contain asbestos and/or presumed to contain asbestos that could be impacted during demolition activities, by law, must first be abated and properly disposed of by a licensed asbestos abatement contractor prior to such work (MM-TOX-2).

LBP testing at the proposed project site was conducted in accordance with Chapter 7 of the HUD Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing. A total of 500 XRF readings were collected to test painted and coated surfaces on site for LBP. Materials were considered as containing LBP if they exceeded the Los Angeles County threshold of 0.7mg/cm² (Title 11, 11.28.010). Orange County shares the same lead standards as Los Angeles County. LBP was detected in ceramic wall tiles and other ceramic furnishings throughout the existing building on the proposed

		project site. Please refer to the XRF Results Table located in Appendix III of the Pre- Renovation Asbestos and Lead Assessment (Attachment 8) for the individual readings obtained during LBP testing. All lead-laden components identified would be demolished or abated by certified lead trained personnel in accordance with all applicable federal, state, and local regulations. In addition, all suspected lead- laden components need to undergo paint film stabilization before components are removed by manual intact methods. LBP that would be impacted by hot work (welding, torch cutting, etc.) must be removed from the component by lead abatement workers to allow a minimum of 6 inches clearance on either side of the location of the hot work to prevent the volatilization of lead into the air (MM-TOX-2) (see Attachments 7 and 8; see ERR 6).
Endangered Species Endangered Species Act of 1973, particularly section 7; 50 CFR Part 402	Yes No	The Endangered Species Act of 1973, as amended, and its implementing regulations are designed to protect and recover species in danger of extinction and the ecosystems that they depend upon. When passed, the Endangered Species Act spoke specifically to the value—tangible and intangible—of conserving species for future generations. In passing the Endangered Species Act, Congress recognized a key fact that subsequent scientific understanding has only confirmed: the best way to protect species is to conserve their habitat.
		According to HUD guidance, the environmental review of a proposed project must consider potential impacts to endangered and threatened species and critical habitats. A No Effect determination can be made if none of the activities involved in the project have potential to affect species or habitats.
		Due to the urban and commercial setting surrounding the project site, no federally listed special-status plant or wildlife species are expected to be present on site. The USFWS offers consultation on threatened and endangered wildlife and plant species, as well as critical habitats, on a project-by-project basis. According to the USFWS Environmental Conservation Online System (ECOS) Information for Planning and Consultation (IPaC) service

П	T	
		(https://ipac.ecosphere.fws.gov/), six threatened or endangered species potentially occur on the project site, listed as follows (USFWS 2020a): • Birds: Coastal California gnatcatcher (Polioptila californica californica),
		Least Bell's Vireo (Vireo bellii pusillus), Southwestern Willow Flycatcher (Empidonax traillii extimus)
		Fishes: Santa Ana Sucker (Catostomus santaanae) Lead March Lleave Glacier
		• Insects: Monarch butterfly (Danaus plexippus)
		Reptiles: Southwestern Pond Turtle (Actinemys pallida)
Explosive and Flammable	V N-	As stated in the IPaC report and confirmed through NEPAssist mapping of the project site, although the general habitat ranges of these six species overlap with the project location, their critical habitat areas do not intersect with the project site (USFWS 2020a). Given the urbanized nature of the project site and scarcity of on-site native vegetation, it is unlikely that any special-status species would occur on site due to a lack of suitable habitat. As such, the project would not result in potential substantial adverse effects to plant and wildlife species or their habitats protected under the Endangered Species Act. Therefore, the project is in compliance with the Endangered Species Act (see Attachment 9; see ERR 7).
Explosive and Flammable Hazards 24 CFR Part 51 Subpart C	Yes No	Regulations set forth in 24 CFR Part 51 Subpart C require HUD-assisted projects to be separated from hazardous facilities that store, handle, or process hazardous substances by a distance based on the contents and volume of the facilities' aboveground storage tank (AST), or to implement mitigation measures. The requisite distances are necessary, because project sites that are too close to facilities handling, storing, or processing conventional fuels, hazardous gases,
		or chemicals of an explosive or flammable nature may expose occupants or end-users of a

		project to the risk of injury in the event of a fire or an explosion.
		Explosive or flammable hazardous materials would not be present at the project site, which would provide 164 affordable housing units and two manager's units. The Phase I ESA did not identify any hazardous materials on the project site. An EDR Radius Report was obtained for the proposed project site to identify aboveground storage tanks (ASTs) within a 1-mile radius of the project area. The report identified three sites with ASTs but did not provide details on the size and content of all ASTs listed within 1-mile of the project site. The three sites include California Highway Patrol 675 Santa Ana Area (2031 East Santa Clara Avenue, Santa Ana, CA 92705), Selman Chevrolet (1800 East Chapman Avenue, Orange, CA 92867), and Caltrans-Orange (691 South Tustin Street, Orange, CA 92866). The CalEPA Regulated Site Portal website was then used to identify and evaluate the type and amounts of chemicals stored at each site identified as having an AST by the EDR report.
		Chemicals listed for each site were compared to a list of hazardous substances provided in Appendix I to Subpart C of Part 51 (§ 51.201). Chemicals not listed in § 51.201 were considered non-hazardous. HUD's Acceptable Separation Distance (ASD) Assessment Tool was used to calculate the acceptable separation distance between the project site and the CalEPA sites that contained hazardous materials. All sites exceeded HUD's required minimum ASD for the quantities of chemicals present. As such, the proposed project would not expose residents or the surrounding community to the risk of injury in the event of a fire or an explosion. Therefore, the proposed project is in compliance with 24 CFR Part 51 Subpart C (see Attachment 10; see ERR 8).
Farmlands Protection Farmland Protection Policy Act of 1981, particularly sections 1504(b) and 1541; 7 CFR Part 658	Yes No	The importance of farmlands to the national and local economy requires the consideration of the impact of activities on land adjacent to prime or unique farmlands. The purpose of the Farmland Protection Policy Act (7 USC Section 4201 et seq, implementing regulations 7 CFR Part 658, of the Agriculture and Food Act of 1981, as

		amended) is to minimize the effect of federal programs on the unnecessary and irreversible conversion of farmland to nonagricultural uses. According to the California Department of Conservation (DOC) California Important Farmland Finder, the entire project site is designated as "Urban and Built-up Land." The areas adjacent to the project site share the same land type designation. The DOC defines Urban and Built-up Land as land that is "used for residential, industrial, commercial, construction, institutional, public administration, railroad and other transportation yards, cemeteries, airports, golf courses, sanitary landfills, sewage treatment, water control structures, and other developed purposes." As such, the project site does not contain farmland and the proposed project would not facilitate the conversion of farmland to a non-agricultural use. Therefore, the project is in compliance with the Farmland Protection Policy Act (see Attachment 11; see ERR 9).
Floodplain Management Executive Order 11988, particularly section 2(a); 24 CFR Part 55	Yes No	The provisions of Executive Order (EO) 11988, Floodplain Management, require federal activities to avoid impacts to floodplains and to avoid direct and indirect support of floodplain development to the extent practicable. HUD's regulations in 24 CFR Part 55 outline HUD's procedures for complying with EO 11988. As indicated above, the project site is not located within a floodplain. According to the FEMA Flood Insurance Rate Map No. 06059C0164J, effective December 3, 2009 (https://msc.fema.gov/portal/home), the project site is located within unshaded Zone X, in an area outside of the 100- and 500- year flood zones where the flood potential is minimal. Therefore, the project is in compliance with EO 11988 and 24 CFR Part 55 (see Attachment 4; see ERR 10).
Historic Preservation National Historic Preservation Act of 1966, particularly sections 106 and 110; 36 CFR Part 800	Yes No	The National Historic Preservation Act (NHPA) (16 USC 470 et seq.) directs each federal agency, and those tribal, State, and local governments that assume federal agency responsibilities, to protect historic properties and to avoid, minimize, or mitigate possible harm that may result from agency actions. The review process, known as Section 106 review, is detailed in 36

CFR Part 800. Early consideration of historic places in project planning and full consultation with interested parties are key to effective compliance with Section 106. The State Historic Preservation Officer (SHPO) and/or Tribal Historic Preservation Officer (THPO) are primary consulting parties in the process.

Architectural Resources Group conducted an historic resources assessment of the direct APE in 2020. The assessment included a search of California's Built Environment Resource Directory and Historic Resources Inventory and a built environment site visit. The study identified and evaluated two historic-era properties built between 1960 and 1987 within the direct APE. These properties include a single-family residence (585 S. Tustin Street) and a rehabilitation center (1800 E. La Veta Avenue). Both resources were evaluated and recommended ineligible for inclusion in the NRHP and the CRHR (Architectural Resources Group 2020).

ASM Affiliates conducted a cultural resources study of the direct APE in 2021. The study included a Native American Heritage Commission (NAHC) Sacred Lands File (SLF) search, a records search at the South Central Coastal Information Center (SCCIC), a review of historic aerial and topographic imagery, and a pedestrian survey. This cultural resources study did not identify any archaeological resources within the direct APE. No built environmental resources were evaluated (Andrews 2021).

In 2023, Kleinfelder conducted a review of the proposed Project for indirect effects, extending the APE to include an indirect APE that consisted of one parcel in all directions of the undertaking. Two additional historic-era properties were identified. These include the Castilian Park Apartments (1622 and 1625 East Fairway Drive) and the Fairway Park Apartments (1844 E. Fairway Drive). Both resources were evaluated and recommended ineligible for inclusion in the NRHP and the CRHR (Neals and Castells 2023).

Noise Abatement and Control Noise Control Act of 1972, as amended by the Quiet Communities Act of 1978; 24 CFR Part 51 Subpart B	Yes No	Orange County Housing & Community Development reviewed the documentation for the Project and the potential for Project implementation to affect historic properties within the APE and determined that no historic properties will be affected in the APE for the subject undertaking. Therefore, Orange County Housing & Community Development has reached a determination of "No Historic Properties Affected" by the project. Pursuant to 36 CFR Part 800, regulations implementing Section 106, the County has requested SHPO concurrence on their determination of "No Historic Properties Affected." Pursuant to 36 Code of Federal Regulations (CFR) 800.3(c)(4), SHPO did not respond within 30 days of receiving the County's request for a finding or determination. As a result, the County's consultation requirements with the SHPO are complete (see Attachments 12 and 13; see ERR 11). Historic resources are not anticipated to be discovered during construction of the proposed project since no ground-disturbing activities would occur. According to HUD's noise standards set forth in 24 CFR Part 51, Subpart B, all sites whose environmental or community noise exposure exceeds the day night average sound level (DNL) of 65 decibels (dB) are considered noise- impacted areas. HUD guidance includes screening criteria to assist in evaluating a project's consistency with the foregoing standard. Pursuant to HUD guidance, potentially significant noise generators within the vicinity of a project include major roadways, if within 1,000 feet of a project site, railroads, if within 1,000 feet, and military or Federal Aviation Administration-regulated (FAA) airfields, if within 15 miles. Documentation that a project is not within the applicable distances to the foregoing noise generators demonstrates compliance with HUD's noise standard. If within the aforementioned distance, a project may show the noise level is at or below 65 dB to demonstrate consistency with the Noise Control Act of 1972. Dudek completed a Technical Noise Memorandum for the proposed
		-

project site is within the screening threshold distances of noise generators in the vicinity (1,000 feet from a major road, 3,000 feet from a railroad, or 15 miles from an airport). The project site is less than 1,000 feet from the State Route (SR)-22 and SR-55 freeways, and the nearest airport, Santa Ana/John Wayne Airport, is located approximately 6.8 miles away.

The primary noise source in the project vicinity is motor vehicle traffic. The eastern façades of the proposed residential units would face the southbound lanes of the SR-55 freeway, while the southern façades would face the SR-22 freeway. Both the eastern and the southern facades would be separated from these two freeways by several rows of residential homes and an existing noise barrier (i.e., a soundwall) approximately 14 feet in height constructed at the California Department of Transportation (Caltrans) right-of-way (ROW). In addition, the northern façades of the proposed residential units would face La Veta Avenue and the western facades would face South Tustin Street. The other nearby roads are minor "feeder" streets which would have a negligible contribution to the on-site noise environment.

An initial noise analysis of traffic noise from the SR-55, the SR-22, La Veta Avenue and South Tustin Street carried out using HUD's DNL Calculator indicated that worst-case exterior building façade noise levels would be approximately 73 A-weighted decibels (dBA) DNL. However, because the DNL Calculator does not account for site conditions such as the intervening building rows and the existing freeway soundwall, in addition to the proposed upper-floor residential units, this modeled noise level was determined to likely be an overestimate and a more detailed traffic noise model was used.

The Federal Highway Administration's (FHWA) Traffic Noise Model (TNM) version 2.5 (FWHA 2004) was used to conduct a more detailed noise analysis for the project site. The TNM traffic noise prediction model calculates the noise levels based on specific information including traffic volumes, vehicle fleet mix, speed limits, roadway geometrics, receiver elevations,

intervening structures and lateral distances between the noise receivers and the roadways. Exposure from traffic noise would exceed the HUD exterior noise standard of 65 dBA DNL by up to 6 dB at the façade of units closest to the SR-22 freeway and South Tustin Street, putting those units in HUD's "normally unacceptable" noise range. The noise levels at the other modeled building façade receivers on the project site, except for the northern facade of Building 1, also would exceed the HUD exterior noise standard of 65 dBA DNL to varying degrees. At the modeled outdoor use areas, the modeled traffic noise levels would not exceed the HUD exterior noise standard. Detailed results of the noise analysis are summarized in Table 2 of the Noise Memorandum (see Attachment 14).

As described above, 24 CFR Part 51, Subpart B states that sites at which environmental or community noise exposure exceeds the DNL of 65 dBA are considered to be noise-impacted. Approvals in the "normally unacceptable" noise zone require a minimum of 5 dB of additional sound attenuation for buildings having noise-sensitive uses if the day-night average sound level is greater than 65 dBA but does not exceed 70 dBA, or a minimum of 10 dB of additional sound attenuation if the day-night average sound level is greater than 70 dBA but does not exceed 75 dBA.

Typical new construction of multi-family homes with windows closed provides a minimum of 25 dB exterior to interior noise reduction. All residential units will be equipped with a forcedair heating ventilation air conditioning (HVAC) unit that allows for a "windows closed" condition (i.e., windows do not need to be left open for ventilation). As such, the interiors of the proposed habitable rooms with doors or windows facing west, toward South Tustin Street and SR-22 are anticipated to have noise levels of approximately 46 dBA DNL (i.e. 71 dBA exterior -25 dBA attenuation =46 dBAinterior), which exceeds HUD's interior noise standard of 45 dBA DNL. The interiors of the other modeled receivers are anticipated to have noise levels of 43 dBA DNL (i.e. 68 dBA exterior -25 dBA attenuation =43 dBA interior) or less.

		To ensure compliance with 24 CFR Part 51, Subpart B and that the HUD noise standard of 45 dBA DNL is not exceeded, the detailed architectural plans for the proposed project should include the following noise mitigation: All windows and exterior doors in the east-facing residential units on floors 2-4 of Building 1 shall have a Sound Transmission Class (STC) rating of 30 or greater (MM-NOI-1); all windows and exterior doors in the south- and east-facing residential units on floors 2-4 of Building 2 shall have an STC rating of 30 or greater (MM-NOI-2); all windows and exterior doors in the west-facing residential units of
		floors 1-4 of Building 3 shall have an STC rating of 35 or greater (MM-NOI-3); and all windows and exterior doors in the north- and south-facing residential units on floors 1-4 of Building 3 shall have an STC rating of 30 or greater (MM-NOI-4). With implementation of these mitigation measures, ambient noise levels at the proposed project site would not exceed HUD's exterior noise threshold of 65 dBA DNL. Therefore, the proposed project would be in compliance with 24 CFR Part 51, Subpart B (see Attachment 14; see ERR 12).
Sole Source Aquifers Safe Drinking Water Act of 1974, as amended, particularly sectiothe424(e); 40 CFR Part 149	Yes No	Aquifers and surface water are drinking water systems that may be impacted by development. The Safe Drinking Water Act of 1974 requires protection of drinking water systems that are the sole or principal drinking water source for an area and which, if contaminated, would create a significant hazard to public health. The EPA's Map of Sole Source Aquifer Locations (https://www.epa.gov/dwssa/map-sole-source-aquifer-locations) was used to identify sole-source aquifers in the vicinity of the project site (EPA 2023b). There are no sole source aquifers in Orange County and the project site is not located within an area designated by the EPA as being supported by a sole source aquifer. The Campo/Cottonwood Creek Aquifer, approximately 96 miles south of the project site, is the nearest sole source aquifers would occur. Therefore, the project is in compliance with the Safe Drinking Water Act of 1974, as amended (see Attachment 15; see ERR 13).

Wotlands Duotastian		
Executive Order 11990, particularly sections 2 and 5	Yes No	According to the EPA, wetlands are characterized by hydrology, soils, and vegetation. The U.S. Fish and Wildlife Service's National Wetland Inventory (NWI) mapper (https://www.fws.gov/program/national-wetlands-inventory/wetlands-mapper) was used to identify wetlands on or near the project site. According to the NWI Mapper, aquatic resources do not occur on the project site. The nearest wetland feature is Santiago Creek, a riverine feature located approximately 175 feet northwest of the project site. Therefore, the proposed project is in compliance with EO 11990 (see Attachment 16; see ERR 14).
Wild and Scenic Rivers Act of 1968, particularly section 7(b) and (c)	Yes No	The EPA's NEPAssist interactive map (https://nepassisttool.epa.gov/nepassist/nepamap.aspx) was used to determine the location of designated Wild and Scenic Rivers in the vicinity of the project site. There are no designated Wild and Scenic Rivers on or near the project site (EPA 2023b). The closest designated Wild and Scenic River is Bautista Creek, approximately 57.5 miles east of the project site. Therefore, the proposed project is in compliance with the Wild and Scenic Rivers Act (see Attachment 17; see ERR 15).
ENVIRONMENTAL JUSTIC	E	
Executive Order 12898	Yes No	Environmental justice means ensuring that the environment and human health are protected fairly for all people regardless of race, color, national origin, or income. EO 12898, Federal Actions to Address Environmental Justice in Minority Populations and Low-Income Populations, requires certain federal agencies, including HUD, to consider how federally assisted projects may have disproportionately high and adverse human health or environmental effects on minority and low-income populations. The EPA's EJScreen tool was used to evaluate environmental and demographic data for the project site and determine whether the project would have disproportionate adverse environmental impacts on future residents and/or the surrounding community. Environmental factors are measured using 11 environmental indicators (EI), and demographic factors are measured using seven demographic indicators

(DI). An EJScreen report for the subject property was run using a 0.125-mile-radius centered around the project site (study area). According to the demographic data obtained from EJScreen, which reflects American Community Survey statistics collected by the U.S. Census Bureau from 2017 through 2021, the total population within this study area is 722. Approximately 61% of the study area's population is non-white (Hispanic). The remaining 39% of the population is White. Results of the EJScreen assessment further indicate that 52% of the study area population is low-income. The proposed project would not have any aggregate environmental justice issues based on the factors evaluated by the EJScreen tool.

As discussed throughout this EA, substantial adverse effects related to various environmental topic areas would not occur. Thus, the proposed project, which is an infill site surrounded by multi-family and commercial uses, would not introduce new uses that could result in disproportionately high and adverse human health or environmental effects on existing minority and low-income populations in the project vicinity, nor would the project induce population growth in an area subject to health risks due to poor environmental conditions. In addition, the affordable housing project would have a beneficial impact on populations protected by environmental justice by increasing the supply of affordable housing units in the study area. Therefore, the project is in compliance with EO 12898 (see Attachment 18; see ERR 16).

Environmental Assessment Factors [24 CFR 58.40; Ref. 40 CFR 1508.8 &1508.27] Recorded below is the qualitative and quantitative significance of the effects of the proposal on the character, features and resources of the project area. Each factor has been evaluated and documented, as appropriate and in proportion to its relevance to the proposed action. Verifiable source documentation has been provided and described in support of each determination, as appropriate. Credible, traceable and supportive source documentation for each authority has been provided. Where applicable, the necessary reviews or consultations have been completed and applicable permits of approvals have been obtained or noted. Citations, dates/names/titles of contacts, and page references are clear. Additional documentation is attached, as appropriate. **All conditions, attenuation or mitigation measures have been clearly identified.**

Impact Codes: Use an impact code from the following list to make the determination of impact for each factor.

- Minor beneficial impact
 No impact anticipated
 Minor Adverse Impact May require mitigation
 Significant or potentially significant impact requiring avoidance or modification which may require an Environmental Impact Statement

Environmental	Impact			
Assessment Factor	Code	Impact Evaluation		
LAND DEVELO	LAND DEVELOPMENT			
Conformance with Plans / Compatible Land Use and Zoning / Scale and Urban Design	2	The project would include demolition of the former Rehabilitation Institute campus and construction of a new affordable housing community, which would change the existing property use from commercial to residential. The project site currently has a zoning and General Plan Land Use Designation of R-3 for Residential Multiple Family. According to the City's General Plan, Senior Housing Developments are conditionally permitted in the R-3 land use designation. The City's Planning Commission approved the Conditional Use Permit, major Site Plan Review, Design Review, and density bonus for the proposed project on March 7, 2022. State Density Bonus Law allows 100% affordable housing projects to utilize the 80% density bonus increase and up to four concessions/incentives from the City's development standards. Per state law, the density bonus is not a discretionary approval, and the City must grant it, if requested and if the project qualifies. The maximum allowable density within the R-3 zoning district is usually 24 dwelling units per acre; however, the project has received an 80% density bonus from the City, increasing the maximum allowable dwelling units per acre to 43. Therefore, the project would be consistent with local land use plans and regulations and no adverse impacts to existing and future land use would occur.		
Soil Suitability/ Slope/ Erosion/ Drainage/ Storm Water Runoff	2	Soil Suitability. According to the Phase I ESA, which obtained soils data from the U.S. Department of Agriculture's Web Soil Survey tool, the project site consists of three soil types: San Emigdio fine sandy loam on 0 to 2 percent slopes, River wash, which consists of gravelly sand and stratified gravelly coarse sand to sandy loam below depths of six inches, and Soboba gravelly loamy sand on 0 to 5 percent slopes. Slope and Drainage. Slope measurements for the project site were obtained through analysis of the USGS 7.5 Minute Topographic Map for Orange, CA in the Phase I ESA. According to this review, the proposed project site slopes towards the west-southwest. Erosion and Stormwater Runoff. Erosion due to stormwater runoff at the project site would be minimized by the lack of exposed soils. The project would result in an increase of		

impervious surface area onsite since the greenspace at the northwest corner of the project site would be converted into a parking area. Water would flow into stormwater drains located on the project site or on surrounding rights-of-way, which are connected to the municipal owned and maintained stormwater system.

Project construction would include ground disturbance, which could result in increased potential for erosion. The State Water Resources Control Board (SWRCB) has implemented a National Pollutant Discharge Elimination System (NPDES) Construction General Permit for the State of California for projects disturbing 1 or more of acres of soil, requiring dischargers to obtain coverage under the General Permit, file a Notice of Intent (NOI), and prepare a stormwater pollution prevention plan (SWPPP) prior to commencement of construction. Because the project footprint is greater than 1 acre, it would be subject to the NPDES permit requirements for construction site stormwater discharges and would comply with those requirements. A SWPPP is required to be prepared and implemented under these requirements, which includes appropriate erosion-control and water-quality-control best management practices (BMPs) during site preparation, grading, construction, and post-construction. Implementation of the SWPPP for the project would minimize short-term impacts related to erosion and stormwater runoff. Therefore, the project would not have adverse impacts related to erosion and stormwater runoff.

Hazards and Nuisances including Site Safety and Noise 3

Hazardous Materials. Explosive or flammable hazardous materials would not be present at the project site, which would provide approximately 164 affordable housing units and two manager's units. The Phase I ESA conducted by AEI in September 2023 did not identify any hazardous materials or petroleum on the project site.

Site Safety. The proposed project would not create a risk of explosion, release of hazardous substances, or other dangers to public health. The project site is not near any hazardous operations. The project would provide a safe place for employees and residents.

Although no site safety hazards or nuisances are currently present at the project site, it is possible that during construction of the project, construction traffic, noise, dust, and erosion, could be considered a nuisance to the construction crew or immediate neighbors. As discussed in the Air Quality section above, MM-AIR-1 would be implemented to control fugitive dust emissions from project construction, and the project would also include implementation of a SWPPP and BMPs in compliance with the NPDES Construction General Permit to minimize erosion and stormwater runoff. Furthermore, as

discussed in the Contamination and Toxic Materials section above, asbestos containing materials and lead-based paint would be abated and properly disposed of by a licensed asbestos abatement contractor prior to such work prior to demolition activities (MM-TOX-2).

Noise. Construction of the project would generate noise associated with the operation of heavy construction equipment and construction-related activities in the vicinity of the project site. This would result in temporary, intermittent increases in ambient noise levels which would fluctuate depending on the particular construction phase. Pursuant to Chapter 8.24, Noise Control, of the City's Code of Ordinances, noise associated with construction is exempt from the provisions of the noise ordinance, provided that activities take place between the hours of 7:00 a.m. and 8:00 p.m. on any day except for Sunday or a federal holiday. The project would not require nighttime construction or construction on weekends or holidays, and therefore construction noise would not be subject to the City's noise standards identified in Table 8.24.040.

Noise generated from project operation would be required to comply with the City's noise standards. Operation of the project would result in a residential use on the project site. Operational noise would result from project-generated traffic and use of the outdoor areas on site by future project occupants. Operation of the project would not result in substantial generation of noise and would generally be similar to and consistent with existing uses in the project vicinity and would not be distinct from the ambient noise environment created by surrounding uses.

Environmental	Impact	
Assessment Factor	Code	Impact Evaluation
SOCIOECONOM	IIC	
Employment and Income Patterns		Project construction would generate a limited number of temporary construction jobs, and operation would generate a nominal number of permanent jobs (e.g., management, clerical, and janitorial jobs), which could result in a minor increase in percapita income. Construction activities could result in direct economic effects related to increased spending on construction materials, equipment, and services. The magnitude of the economic benefits of construction spending to the City's economy would depend on the proportion of employment, goods, and services procured from local residents and businesses, and would likely have a relatively minor benefit on the City's
Demographic Character Changes, Displacement	2	economy. The proposed project would have an overall beneficial impact on the City of Orange by converting the existing vacant Rehabilitation Institute of Southern California building into

affordable housing for seniors with amenities for residents. Because design of the proposed project would be consistent with the architectural style of neighboring buildings, this new affordable housing community would not adversely affect community character. The new buildings would reflect the midcentury architectural style of neighboring properties with a contemporary twist. Clean lines and a nostalgic color palette would blend the project into the existing community. Exterior finishes and materials include painted stucco, a black aluminum storefront system, and metal rail panels and awnings at balconies.

Residents of the new affordable housing community would likely be transplants from within the City or from neighboring areas within Orange County. The proposed project, which is an infill site converting a commercial facility into multi-family housing, would remain consistent with surrounding multi-family land uses and support infill development goals outlined in the City's Housing Element. Multifamily housing adjacent to the proposed project site, including the Casa Del Rio Apartments (1740 East La Veta Avenue) and the Chestnut Place Senior Apartments (1745) East Fairway Drive), can be viewed in **Figure 2**. The proposed project would increase the availability of affordable housing for seniors aged 62 years and older in the City and County while avoiding the displacement of existing businesses or residences since the project site is currently vacant. Demographics for the study area analyzed in the EJScreen report for the proposed project would change as seniors (aged 62+) moved into the completed affordable housing community. Currently, seniors account for 14% (approximately 101 people) of the study area population of 722 people. Since the proposed development would only allow seniors aged 62 years and older as residents, the percentage of seniors within the study area would increase following completion of the project.

Increasing affordable housing units for seniors supports the housing priorities detailed in the City's Housing Element. The inclusion of 8 units for seniors experiencing homelessness or atrisk of homelessness also supports the regional Housing Funding Strategy to produce 2,396 supportive housing units by 2029 to address homelessness in Orange County. According to 2019 American Community Survey data, approximately 12.2% (17,076 people) of the City's population is composed of seniors (aged 65+). Currently the City has eight affordable housing developments for senior residents. Overall, the proposed project would have a positive impact on community character while remaining compliant with existing land use designations and design.

Environmental Justice

2

According to the City's Housing Element, the senior population tends to have fixed income, experience higher average healthcare costs, have mobility and self-care limitations, be transit dependent, and live alone (City of Orange 2022). The proposed

pro	oject, once complete, would contribute 164 new affordable
hou	using units for seniors, and 2 manager's units, to the City's
hou	using stock including supportive housing units for homeless/
at-1	risk of homeless seniors. Units would be a mixture of 1-
bec	droom and 2-bedroom apartments reserved for seniors (aged
62-	+) and earning between 30-70% AMI. The proposed
dev	velopment would be located near public transit and healthcare,
miı	nimizing the need to independently travel long distances to
obt	tain access to grocery stores, restaurants, healthcare, and other
ser	vices. Increasing affordable housing units for seniors supports
the	housing priorities detailed in the City's Housing Element. The
pro	posed project, which is an infill site converting a commercial
fac	cility into multifamily housing, would not result in any
dis	proportionately high or adverse impacts to minority or low-
inc	come populations.

Environmental	Impact	
Assessment Factor	Code	Impact Evaluation
COMMUNITY F	ACILITIE	ES AND SERVICES
Educational and Cultural Facilities	2	Given the availability of educational institutions in the area, as well as the project's target population of only seniors (aged 62+), adverse impacts to schools near the proposed project are not anticipated because the project is specifically for senior citizens. The project is near multiple educational facilities, as follows: • La Veta Elementary School, approximately 0.8 miles east of the project site • Palmyra Elementary School, about 0.7 miles northwest of the project site • TLC Charter School, approximately 0.9 miles northeast of the project site • The Open School, about 0.6 miles south of the project site • Camelot Academy, approximately 1.9 miles east of the project site
		Cultural facilities include publicly accessible buildings, structures, and establishments that are used primarily for the performance, exhibition, or benefit of arts and heritage activities, including, but not limited to, performing arts, visual arts, heritage and cultural endeavors. Numerous cultural facilities would be accessible to project occupants in the immediate project area and beyond within the City of Orange, including cinemas, galleries, libraries, museums, theaters, and stadiums. Cultural facilities near the project site include the Hilbert Museum of California Art approximately 2 miles to the northwest and the Bowers Museum approximately 3.3 miles to the southwest. The Discovery Cube located at 2500 North Main

		Street in Santa Ana is about 2.8 miles southwest of the project site. The project would result in an incremental increase in demand for cultural facilities. However, as an affordable housing project, the project would be expected to serve existing area residents by addressing existing unmet needs for rental assistance in the project area, rather than result in an influx of new residents. Furthermore, due to the relatively small project size, any incremental increase in demand would not exceed the capacity of existing facilities. There are adequate cultural facilities in the City and surrounding areas of the County to accommodate any potential increased usage generated by the project. Impacts to educational and cultural facilities would be less than significant.
Commercial Facilities	2	No adverse impacts to adjacent commercial facilities are anticipated. The project is primarily bordered by multifamily residential units. According to the Phase I ESA, a 7-Eleven store and 76 gas station along the southwestern border of the project site, across East Fairway Drive, is the closest commercial land use to the proposed project site. Developing housing across the street from the 7-Eleven and 76 gas station could increase business due to an increase in the population with vehicles. Construction of affordable housing could result in an incremental beneficial impact to local businesses since placing residents in more affordable housing provides more disposable income for spending on non-housing related goods and services.
Health Care and Social Services	2	Adverse impacts to healthcare and social services are not anticipated due to the availability of service providers near the project site. The project is near numerous healthcare facilities, including the following: • Sunrise Multispecialist Medical Center, approximately 0.4 miles south of the project site at 867 S Tustin St, Orange, CA 92866 • Nellie Gail Urgent Care- Orange, about 1.1 miles north of the project site at 315 S Tustin St, Orange, CA 92866 • St. Joseph Heritage Medical Group Urgent care, approximately 1.2 miles northeast of the project site at 2501 E Chapman Ave Suite 101, Orange, CA 92869 • Chapman Global Medical Center, about 1.2 miles northeast of the project site at 2601 E Chapman Ave, Orange, CA 92869 • Orange County Global Medical Center, approximately 1.7 miles south of the project site at 1001 N Tustin Ave, Santa Ana, CA 92705 *HealthBridge Orange Pediatric Hospital was not included on this list since residents of the proposed development would not include children.

Solid Waste Disposal / Recycling	2	The City of Orange's trash, recyclables, and organics (green waste and food waste) are collected by CR&R Environmental Services (City of Orange 2024c). Multifamily dwelling units of five or more are required to arrange for recycling services per Mandatory Commercial Recycling Law AB 341. Multifamily dwelling units of five or more are also required to provide recycling containers that are visible, accessible, and adjacent to each trash container (City of Orange 2024b). A construction waste recycling program would be implemented during demolition and construction phases to minimize waste to the extent practicable. All waste generated during the construction and operational phases of the project would be properly disposed of and recycled where possible. The amount of solid waste generated by the proposed project during the construction and operational phases would be a fraction of the throughput taken in by CR&R daily. Adverse impacts from solid waste disposal associated with the proposed project are not anticipated.
Waste Water / Sanitary Sewers	2	The City of Orange supplies wastewater and sewage disposal/treatment services to the proposed project site. The City of Orange maintains over 1.6 million lineal feet or 308 miles of sewer pipeline. Maintenance includes annual cleaning of sewer lines and periodic videotaping to search for trouble spots. Keeping the sewer system clean helps limit potential sewage overflows that threaten public health and water quality (City of Orange 2024a). Sewage is treated by the Orange County Sanitation District, a public agency that provides wastewater collection, treatment, and disposal services for approximately 2.6 million people in central and northwest Orange County (OC Sanitation District, 2024). The project would connect to existing wastewater and sanitary sewer facilities. The project does not include the construction or use of a septic system. The proposed project would not require construction of additional sewage
Water Supply	2	infrastructure. Adverse impacts to wastewater systems and sanitary sewers servicing the project site are not anticipated. The City of Orange supplies potable water to the proposed project site. The Water Division is responsible for providing a clean, safe, potable water supply to the City of Orange. The Division designs, constructs, and maintains wells, water lines, booster pumps, and reservoirs that serve residents and businesses with water for domestic use and fire protection. The City obtains approximately 75% of its water from groundwater sources via 12 active wells managed by the Orange County Water District. The City also imports water from the Colorado River and Northern California from the Metropolitan Water District of Southern California through the Municipal Water District of Orange County (City of Orange, 2024d). The project would connect to existing water infrastructure and would result in an incremental demand for water. Adverse impacts to the City's water supply are not anticipated.

Public Safety - Police, Fire and Emergency Medical	2	The Orange Police Department provides law enforcement services to the City of Orange. The City's Police Department's offices are located at 1107 N Batavia St, Orange, CA 92867, approximately 3.5 miles northwest of the project site. The proposed project site is located near three fire stations in the cities of Santa Ana and Orange in Orange County. Orange City Fire Department Station #1 is the closest fire station to the project site and is at 1176 E Chapman Ave, Orange, CA 92866, approximately 1 mile northwest of the project site. Orange County Fire Authority Station #70, approximately 1.7 miles southwest of the project site at 2301 Old Grand St, Santa Ana, CA 92705, could also provide emergency services. Finally, Orange City Fire Department Station #4, about 2.1 miles east of the proposed project site at 210 S Esplanade St, Orange, CA 92869, could administer emergency services if needed. The proposed project would not create a noticeable increase in demand for police, fire, and emergency medical services from nearby areas since the proposed project would attract residents from the surrounding community. Additionally, the proposed project would be required to comply with all applicable codes for fire safety and emergency access. Therefore, the project would not have adverse impacts on public safety.
Parks, Open Space and Recreation	2	 Public recreational spaces in proximity to the project site include the following: Hart Park, approximately 1.2 miles west of the project site at 701 S Glassell St, Orange, CA 92866 Pitcher Park, about 1.1 miles northwest of the project site at 204 S Cambridge St, Orange, CA 92866 Portola Park, approximately 1.8 miles southwest of the project site at Portola Park, Santa Ana, CA 92705 Grijalva Park, about 1.8 miles northeast of the project site at 368 N Prospect St, Orange, CA 92866 El Modena Park, approximately 2 miles east of the project site at 4343 E Jordan Ave, Orange, CA 92869 The project would result in an incremental increase in demand for public parks that could be absorbed by existing open spaces near the project site. Site plans for the proposed project include three outdoor courtyards with picnic tables, planter boxes, and barbeque areas where residents can enjoy the outdoors without visiting surrounding parks. Therefore, the project would not have adverse impacts on parks, open space, and recreation.
Transportation and Accessibility	2	Crain & Associates completed a preliminary traffic analysis for the proposed project in January 2020 to determine whether an additional transportation analysis is needed. The traffic analysis

determined the proposed project's projected trip generation using trip generation rates from the Institute of Transportation Engineers *Trip Generation manual* (10th Edition) and by collecting empirical driveway counts at the project site's driveways. To determine the trip generation of the rehabilitation center use, comprehensive trip generation surveys of vehicle traffic entering and existing the parking and loading areas of the project site were collected. Trip counts had to be adjusted to remove trips associated with the adjacent senior apartments building since it shares the same driveway accesses with the project site. Results of the trip count survey determined that the proposed project is not anticipated to generate more than 100 net vehicle trips during the morning and evening peak hours and the project would not add 1,600 daily trips to the arterial network or add 51 or more trips to nearby intersections during peak hours. Therefore, per the City of Orange Traffic Impact Analysis Guidelines for Vehicle Miles Traveled and Level of Service Assessment (July 2020), the proposed project does not require further level of service analysis. In addition, since the proposed project consists entirely of affordable housing, the project is expected to result in a less-than-significant vehicle miles traveled (VMT) impact and is screened from conducting further VMT analysis (see **Attachment 19**).

Pre-existing urban development and readily available public transit near the project site would further minimize transportation and accessibility issues associated with the project, such as traffic. The nearest bus stop to the project site is located at the intersection of South Tustin Street and East La Veta Avenue, at the northwest corner of the project site. The proposed project site is located near markets, restaurants, healthcare, retail, and other services along South Tustin Avenue to the East and East Chapman Avenue to the North.

The proposed project would be accessed via two driveways located along La Veta Avenue and East Fairway Drive. Neither driveway would be gated. The existing driveways at the northeast, southwest, and southeast corners of the project site would be removed as part of the new construction plan. Existing pedestrian and bicycle gates would allow resident access to all street frontages as well as to the Santiago Creek Trail and bike path to the north. The project would include 172 parking stalls in a surface lot on site. Approximately 5 parking stalls would be reserved for the leasing area and unloading/loading zones, with the remaining 167 available for resident use.

Environmental	Impact	
Assessment Factor	Code	Impact Evaluation
NATURAL FEATURES		

Unique Natural Features, Water Resources	2	The project site, which is located within a developed area and currently occupied by the former campus of the Rehabilitation Institute of Southern California and associated parking and landscaped areas, does not encompass any unique natural features. Federally protected natural resources, such as rivers, wetlands, coastal zones, and endangered species, are not present on the project site or adjacent properties. Therefore, the proposed project would not result in the alteration of any waterways, unique features, or critical habitat, nor would in result in the loss of any federally listed species.
Vegetation, Wildlife	2	Although the proposed project is within the ranges of six endangered or threatened species, none are likely to occur on site due to a lack of suitable habitat. Results from the U.S. Fish and Wildlife Service's IPaC analysis of the area similarly state that the project site is situated outside of critical habitat areas for the endangered or threatened species that overlap with the project area (USFWS 2020a) (see Attachment 8).
Other Factors		None.

Environmental	Impact	
Assessment Factor	Code	Impact Evaluation
CLIMATE AND EN	ERGY	
Climate Change Impacts	2	Although climate change is driven by global atmospheric conditions, climate change impacts are felt locally. An expanding body of scientific research supports the theory that global climate change is currently causing changes in weather patterns, average sea level, ocean acidification, chemical reaction rates, and precipitation rates, and that it will increasingly do so in the future. Potential effects of global climate change that could adversely affect human health include more extreme heat waves and heat-related stress; an increase in climate-sensitive diseases; more frequent and intense natural disasters such as flooding, hurricanes, and drought; and increased levels of air pollution. As discussed above, the project site is not within a flood zone (see Attachment 4). The project site is not within a coastal community or low-lying area and would not be impacted by sea level rise (see Figure 1). The project site is in an urbanized area that is not subject to wildfire hazards (CAL FIRE, 2024)
		(Attachment 20). As previously discussed, the project site is not in an area that relies on a sole-source aquifer. No substantial
		issues related to air quality, soil suitability, stormwater, wastewater systems, or water supply have been identified in the
		preceding analyses. Thus, the project would not lead to potential

		climate-change-related impacts that would substantially adversely affect residents.
		The Climate Mapping for Resilience and Adaptation (CMRA) tool (https://livingatlas.arcgis.com/assessment-tool/explore/map) provided by the U.S. Climate Resilience Toolkit was used to assess the impact of five common climate-related hazards, extreme heat, drought, wildfires, flooding, and coastal inundation (sea level rise), on the proposed project site. Analysis was conducted for the census tract is located in. Based on the results of the CMRA tool analysis, the project site is most susceptible to climate change impacts related to extreme heat and drought. Currently, this area of the County only receives approximately 14 inches of precipitation annually and experiences approximately 23 days annually where temperatures are greater than 90 degrees Fahrenheit. Though this area currently experiences temperatures greater than 100 degrees Fahrenheit less than five days per year, this number is expected to increase to up to 30 days by the end of this century. Additionally, the project site is not located within a census tract designated as a Disadvantaged Community according to the Climate and Economic Justice Screening Tool (CMRA, 2024) (Attachment 21).
		The project would comply with the California Green Building Standards (CALGreen) Code, which would ensure the project incorporates various measures to reduce greenhouse gas (GHG) emissions. The project is located adjacent to a bus line and approximately 2 miles southeast of the Orange Rail Station, which would serve to reduce the GHG emissions associated with motor vehicle travel. As previously discussed, criteria air pollutant emissions from project construction and operation would be below <i>de minimis</i> thresholds, and daily emissions from the proposed project would not exceed the SCAQMD's regional construction or operation emissions thresholds (see Attachment 5). Therefore, the proposed project would not contribute substantially to climate change impacts.
Energy Efficiency	2	Project design would include sustainable features consistent with CALGreen standards, including but not limited to supplying equipment to facilitate future installation of EV parking spaces and water-efficient landscaping. In addition, the project would utilize energy efficient appliances and low flow plumbing faucets and fixtures. Therefore, the project would not have an adverse impact related to energy efficiency.

Additional Studies Performed:

- Historic Resources Assessment, Prepared by Architectural Resources Group, November 2020.
- Phase I Environmental Site Assessment, Prepared by AEI Consultants, September 2023.
- Pre-Renovation Asbestos and Lead Assessment, Prepared by EFI Global, Inc., August 2020.

• The Orion HUD EA Noise Assessment, Prepared by Dudek, February 2024.

Field Inspection (Date and completed by):

- *Phase I Environmental Site Assessment*, Prepared by AEI Consultants, September 2023. Field Inspection completed on September 6, 2023.
- *Pre-Renovation Asbestos and Lead Assessment*, Prepared by EFI Global, Inc., August 2020. Field Inspection completed on August 7 and August 8, 2020.

List of Sources, Agencies and Persons Consulted [40 CFR 1508.9(b)]:

- AQMD (Air Quality Management District). 2008. "Interim CEQA GHG Significance Threshold for Stationary Sources, Rules, and Plans." http://www.aqmd.gov/docs/default-source/ceqa/handbook/greenhouse-gases-(ghg)-ceqa-significance-thresholds/ghgboardsynopsis.pdf.
- CalEPA (California Environmental Protection Agency). 2024. CalEPA Regulated Site Portal. https://siteportal.calepa.ca.gov/nsite/map/results/filters.
- CalEPA (California Environmental Protection Agency). 2024. CalEPA Regulated Site Portal. https://siteportal.calepa.ca.gov/nsite/map/results/filters.
- CAL FIRE (The Department of Forestry and Fire Protection). 2024. "Fire Hazard Severity Zones." Accessed February 2024. https://osfm.fire.ca.gov/what-we-do/community-wildfire-preparedness-and-mitigation/fire-hazard-severity-zones.
- CCC (California Coastal Commission). 2019. "Maps Coastal Zone Boundary: Orange County." https://coastal.ca.gov/maps/czb/.
- City of Orange. 2022 (Updated October 2023). "6th Cycle Housing Element Update (2021-2029)." Accessed February 2024. https://www.cityoforange.org/home/showpublisheddocument/4968/638351489094930000.
- City of Orange. 2024a. "Development Services." Accessed February 2024. https://www.cityoforange.org/our-city/departments/public-works/engineering-division/development-services.
- City of Orange. 2024b. "Multifamily Trash, Recycling, and Organics." Accessed February 2024. https://www.cityoforange.org/our-city/departments/public-works/field-services-division/trash-recycling-and-organics/multifamily.
- City of Orange. 2024c. "Trash, Recycling, and Organics." Accessed February 2024. https://www.cityoforange.org/residents/trash-recycling-and-organics.
- City of Orange. 2024d. "Water Division." Accessed February 2024. https://www.cityoforange.org/our-city/departments/public-works/water-division.
- CMRA (Climate Mapping for Resilience & Adaptation). 2024. CMRA Assessment Tool. https://livingatlas.arcgis.com/assessment-tool/explore/.
- DOC (California Department of Conservation). 2016. California Important Farmland Finder. https://maps.conservation.ca.gov/DLRP/CIFF/.

- EPA (U.S. Environmental Protection Agency). 2024. "Current Nonattainment Counties for all Criteria Pollutants." Accessed February 2024. https://www3.epa.gov/airquality/greenbook/ancl.html.
- EPA. 2023a. 2023. EPA NEPAssist [interactive online map]. Accessed December 2023. https://nepassisttool.epa.gov/nepassist/nepamap.aspx.
- EPA. 2023b. "Sole Source Aquifers for Drinking Water." Last updated January 2023. Accessed December 2023. https://www.epa.gov/dwssa.
- FEMA (Federal Emergency Management Agency). 2012. "FEMA Flood Map Service Center: Search By Address." Accessed December 2023. https://msc.fema.gov/portal/home. OCSD (Orange County Sanitation District). 2024. "Regional Sewer Service Facts and Key Statistics." Accessed February 2024. https://www.ocsan.gov/services/regional-sewer-service.
- SCAQMD (South Coast Air Quality Management District). 2005. Rule 403: Fugitive Dust. As amended through June 3, 2005. https://www.aqmd.gov/docs/default-source/rule-book/rule-iv/rule-403.pdf?sfvrsn=4.
- SCAQMD. 2023. "South Coast AQMD Air Quality Significance Thresholds." March 2023. Accessed December 2023. https://www.aqmd.gov/docs/default-source/ceqa/handbook/south-coast-aqmd-air-quality-significance-thresholds.pdf?sfvrsn=25.
- USFWS (U.S. Fish and Wildlife Service). 2019. Coastal Barrier Resources System Mapper. Updated July 31, 2019. Accessed December 2023. https://www.fws.gov/program/coastal-barrier-resources-act/maps-and-data.
- USFWS. 2020a. Information for Planning and Consultation (IPaC). Accessed December 2023. https://ipac.ecosphere.fws.gov/location/index.
- USFWS. 2020b. National Wetlands Inventory, Surface Waters and Wetlands Map. Accessed December 2023. https://www.fws.gov/program/national-wetlands-inventory/wetlands-mapper.

List of Permits Obtained:

Public Outreach [24 CFR 50.23 & 58.43]:

The Draft Environmental Assessment will be made available for public review and comment beginning on March 21, 2024 and concluding on April 5, 2024.

Cumulative Impact Analysis [24 CFR 58.32]:

The proposed project would not contribute to a significant cumulative impact under the National Environmental Policy Act because it would consist of an urban development project, consistent with the site's General Plan land use and zoning designations and would be near existing transit services. State and local planning guidelines encourage the development of urban housing in areas served by transit and near commercial and cultural amenities because this type of development contributes less to cumulative effects on the environment in comparison to development of previously undisturbed sites in more remote locations with fewer transit connections, many of which contain native vegetation and wildlife species.

Alternatives [24 CFR 58.40(e); 40 CFR 1508.9]

Site identification has proven to be a major obstacle in providing affordable housing units. Residential sites available at reasonable cost are extremely limited, and sites that do not meet cost and land use criteria are generally eliminated as alternatives. The developer identifies potential properties for affordable housing based on feasibility, location, affordability, and ownership/site control of a potential project site. In addition to the developer's site selection criteria, physical and social constraints are also considered in identifying and rejecting alternatives. Based on the developer's site selection criteria and constraints that limit identification of alternative affordable housing project sites, no other build alternatives are analyzed or included in this environmental document.

No Action Alternative [24 CFR 58.40(e)]:

Under the No Action Alternative, the project would not be constructed, and no new affordable housing would be provided at the project site. The existing vacant commercial building on site would remain. There would be no benefits to the physical or human environment by not taking the federal action associated with this project. Physical impacts to the environment would occur in urban areas whether units are subsidized with federal funds or built at market rates. If an affordable project were not constructed on this site, the social benefits of providing new affordable housing opportunities on an urban infill parcel would not occur.

The proposed project must acquire all required permits and approvals prior to construction; therefore, the proposed project would be consistent with all land use plans, policies, and regulations for the project site. Not building on this infill site could potentially result in more housing constructed outside of the urban area in agricultural and undeveloped areas, contributing to urban sprawl, regional traffic congestion, and regional air quality issues.

Summary of Findings and Conclusions:

USA Properties Fund, Inc., in partnership with the City and County, is proposing the demolition of the existing former campus of the Rehabilitation Institute of Southern California and the new construction of a 166-unit affordable housing community, including two manager's units. The new housing development would be reserved for seniors aged 62 years and older and earning between 30-70% AMI. The proposed project would contribute to the increased density and availability of low-income housing in an area that would encourage multi-modal activity. Furthermore, the proposed project, which is an infill site converting a commercial facility into multi-family housing, would remain consistent with surrounding multi-family land uses and support infill development goals outlined in the City's Housing Element. The proximity of existing transit options to the project site would reduce long-term air pollutant emissions and energy use associated with motor vehicle travel.

Because the project site is within a developed urban area, the project would be adequately served by utilities and public services. The project would conform to all applicable federal, state, and regional regulations associated with land use compatibility, air pollutant emissions, water quality, geologic hazards, and related environmental resources addressed herein. Based on the analyses of environmental issues contained in this document, the proposed project is not expected to have significant environmental impacts.

Mitigation Measures and Conditions [40 CFR 1505.2(c)]

Summarize below all mitigation measures adopted by the Responsible Entity to reduce, avoid, or eliminate adverse environmental impacts and to avoid non-compliance or non-conformance with the above-listed authorities and factors. These measures/conditions must be incorporated into project contracts, development agreements, and other relevant documents. The staff responsible

for implementing and monitoring mitigation measures should be clearly identified in the mitigation plan.

Air Quality – Fugitive Dust

MM-AIR-1

The project shall implement the following, as applicable to the project:

- **Backfilling**: Stabilize backfill material when not actively handling, stabilize backfill material during handling, and stabilize soil at completion of activity.
- Clearing and Grubbing: Maintain stability of soil through prewatering of site prior to clearing and grubbing, stabilize soil during clearing and grubbing activities, and stabilize soil immediately after clearing and grubbing activities.
- **Clearing Forms**: Use water spray, sweeping and water spray, or a vacuum system to clear forms.
- **Crushing**: Stabilize surface soils prior to operation of support equipment and stabilize material after crushing.
- Cut and Fill: Pre-water soils prior to cut and fill activities, and stabilize soil during and after cut and fill activities.
- **Demolition Mechanical/Manual:** Stabilize wind-erodible surfaces to reduce dust, stabilize surface soil where support equipment and vehicles will operate, stabilize loose soil and demolition debris, and comply with Air Quality Management District Rule 1403.
- **Disturbed Soil**: Stabilize disturbed soil throughout the construction site, and stabilize disturbed soil between structures.
- Earth-Moving Activities: Pre-apply water to depth of proposed cuts, re-apply water as necessary to maintain soil in a damp condition and to ensure that visible emissions do not exceed 100 feet in any direction, and stabilize soil once earth-moving activities are complete.
- Importing/Exporting of Bulk Materials: Stabilize material while loading to reduce fugitive dust emissions, maintain at least 6 inches of freeboard on haul vehicles, stabilize material while transporting and unloading to reduce fugitive dust emissions, and comply with California Vehicle Code (CVC) Section 23114.
- Landscaping: Stabilize soils, materials, slopes.
- Road Shoulder Maintenance: Apply water to unpaved shoulders prior to clearing, and apply chemical dust suppressants and/or washed gravel to maintain a stabilized surface after completing road shoulder maintenance.
- **Screening:** Pre-water material prior to screening, limit fugitive dust emissions to opacity and plume length standards, and stabilize material immediately after screening.
- **Staging Areas:** Stabilize staging areas during use, and stabilize staging area soils at project completion.
- Stockpiles/Bulk Material Handling: Stabilize stockpiled materials. Stockpiles within 100 yards of off-site occupied buildings must not be greater than 8 feet in height, or must have a road bladed to the top to

- allow water truck access, or must have an operational water irrigation system that is capable of complete stockpile coverage.
- Traffic Areas for Construction Activities: Stabilize all off-road traffic and parking areas, stabilize all haul routes, and direct construction traffic over established haul routes.
- **Trenching:** Stabilize surface soils where trencher or excavator and support equipment will operate, and stabilize soils at the completion of trenching activities.
- **Truck Loading:** Pre-water material prior to loading and ensure that freeboard exceeds 6 inches (CVC Section 23114).
- **Turf Overseeding:** Apply sufficient water immediately prior to conducting turf vacuuming activities to meet opacity and plume length standards, and cover haul vehicles prior to exiting the site.
- Unpaved Roads/Parking Lots: Stabilize soils to meet the applicable performance standards and limit vehicular travel to established unpaved roads (haul routes) and parking lots.
- Vacant Land: In instances where vacant lots are 0.10 acres or larger and have a cumulative area of 500 square feet or more that are driven over and/or used by motor vehicles and/or off-road vehicles, prevent motor vehicle and off-road-vehicle trespassing, parking, and access by installing barriers, curbs, fences, gates, posts, signs, shrubs, trees, or other effective control measures.

Contamination and Toxic Substances

MM-TOX-1

In compliance with HUD's radon policy notice published in January 2024, indoor radon testing at the new affordable housing community will occur after construction is complete and before residents move in. If testing determines that indoor radon levels are or may be above 4pCi/L, then the County must document and implement a mitigation plan. The mitigation plan must identify the radon level onsite, describe the radon reduction system that will be installed, establish an ongoing maintenance plan, establish a reasonable timeframe for system implementation, and require post-installation testing by a licensed radon professional.

MM-TOX-2

If materials found to contain asbestos and/or presumed to contain asbestos may be impacted during renovation or demolition activities, by law, they must first be abated and properly disposed of by a licensed asbestos abatement contractor prior to such work. Contractors are licensed for asbestos-related work by the California Department of Industrial Relations (DIR) Department of Occupational Safety and Health (DOSH). A list of contractors with current licenses may be found at: https://www.dir.ca.gov/databases/doshacru/acrusearch.html.

Any suspect materials, that are not identified above and may be impacted during work activities, must be presumed to contain asbestos until laboratory analysis of an adequate number of samples proves otherwise. It is highly recommended that abatement monitoring be performed by the asbestos consultant if asbestos abatement is to be performed while non-abatement persons (employees, tenants, other building occupants, or general public) are present in adjacent areas. Abatement monitoring includes the collection of air samples in adjacent areas to demonstrate that asbestos fibers are not migrating out of the regulated areas. In addition to air sampling, the monitoring includes oversight of the abatement contractor to ensure that the work is being conducted in compliance with all applicable regulations and in accordance with the scope of work and abatement specifications. Such abatement monitoring services can reduce risk and limit the legal liabilities of the building owner.

All lead laden components identified in this report shall be demolished or abated by certified lead trained personnel in accordance with all applicable federal, state and local regulations. All suspected lead laden components shall undergo paint film stabilization before components are removed by manual intact methods. LBP that will be impacted by hot work (welding, torch cutting, etc.) must be removed from the component by lead abatement workers to allow a minimum of 6 inches clearance on either side of the location of the hot work to prevent the volatilization of

lead into the air.

Paint / surface coatings that were tested and found to have lead concentrations below the LBP threshold (i.e. 0.7 mg/cm²) may still contain detectable concentrations of lead. Thus, work impacting those surfaces are subject to the Cal/OSHA Lead in Construction Standard 1532.1. This standard requires that respiratory protection and containment is used when performing "trigger tasks" until results of personal air monitoring indicate that workers are not exposed to lead above the action level or permissible exposure level. Additionally, the demolition or removal of lead or components with lead coatings is subject to Title 17, Division 1, Chapter 8 of the California Code of Regulations.

MM-TOX-3

Should the contractor choose not to remove the identified LBP materials and demolish the structure in its entirety with the lead-paint components in place, it is recommended that the contractor stabilize the LBP components prior to demolition and then collect samples representative of the entire mass of the prospective waste stream. These samples should then be analyzed according to the United States Environmental Protection Agency (EPA) and the California Department of Toxic Substances Control (DTSC) prior to disposal facility acceptance.

Historic Preservation (Cultural Resources)

MM-CUL-1

In the event that previously unidentified cultural resources are encountered during ground-disturbing activities associated with project construction, work in the immediate area must halt, and an archaeologist meeting the Secretary of the Interior's Professional Qualifications Standards for archaeology shall be contacted immediately to evaluate the find. If the discovery proves to be significant under the National Environmental Policy Act, additional work, such as data recovery excavation, may be warranted to mitigate potential adverse effects.

Noise Abatement and Control

MM-NOI-1 All windows and exterior doors in the east-facing residential units on

floors 2-4 of Building 1 shall have a Sound Transmission Class (STC)

rating of 30 or greater.

MM-NOI-2 All windows and exterior doors in the south- and east-facing residential

units on floors 2-4 of Building 2 shall have a Sound Transmission Class

(STC) rating of 30 or greater.

MM-NOI-3 All windows and exterior doors in the west-facing residential units on

floors 1-4 of Building 3 shall have a Sound Transmission Class (STC)

rating of 35 or greater.

MM-NOI-4 All windows and exterior doors in the north- and south-facing residential

units on floors 1-4 of Building 3 shall have a Sound Transmission Class

(STC) rating of 30 or greater.

Determination:

\boxtimes	Finding of No Significant Impact [24 CFR 58.40(g)(1); 40 CFR 1508.27]
The	e project will not result in a significant impact on the quality of the human environment.

Finding of Significant Impact [24 CFR 58.40(g)(2); 40 CFR 1508.27]

The project may significantly affect the quality of the human environment.

Preparer Signature: Suzanne Harder	3.14.24 Date:
Name/Title/Organization: Suzanne Harder, Community Developmen	nt Compliance
and Environmental Coordinator, Orange County Housing and Cor	
Certifying Officer Signature: Sig	Date: 3-19-2024
Name/Title: Director, Housing & Community Development	

This original, signed document and related supporting material must be retained on file by the Responsible Entity in an Environmental Review Record (ERR) for the activity/project (ref: 24 CFR Part 58.38) and in accordance with recordkeeping requirements for the HUD program(s).

ENVIRONMENTAL REVIEW RECORDS (ERRS)

ERR No. 1. Airport Hazards



U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

WASHINGTON, DC 20410-1000

This Worksheet was designed to be used by those "Partners" (including Public Housing Authorities, consultants, contractors, and nonprofits) who assist Responsible Entities and HUD in preparing environmental reviews, but legally cannot take full responsibilities for these reviews themselves. Responsible Entities and HUD should use the RE/HUD version of the Worksheet.

Airport Hazards (CEST and EA) - PARTNER

<u>htt</u>	:ps://www	.hudexchange.info/environmental-review/airport-hazards
1.		compatible land use development, you must determine your site's proximity to civil and ports. Is your project within 15,000 feet of a military airport or 2,500 feet of a civilian airport? If the RE/HUD agrees with this recommendation, the review is in compliance with this section. Continue to the Worksheet Summary below. Provide a map showing that the site is not within the applicable distances to a military or civilian airport.
	□Yes →	Continue to Question 2.
2.	Is your pro	oject located within a Runway Potential Zone/Clear Zone (RPZ/CZ) or Accident Potential)?
	□Yes, pro	ject is in an APZ → Continue to Question 3.
	□Yes, pro	ject is an RPZ/CZ → Project cannot proceed at this location.
	□No, proj	ect is not within an APZ or RPZ/CZ
	Cor	ne RE/HUD agrees with this recommendation, the review is in compliance with this section. In the section is not within the site is not with the site is not within the site is not with the site is not with the site is not within t
3.	Is the proj	ect in conformance with DOD guidelines for APZ?
	→If ti	ject is consistent with DOD guidelines without further action. the RE/HUD agrees with this recommendation, the review is in compliance with this tion. Continue to the Worksheet Summary below. Provide any documentation poorting this determination.
		project cannot be brought into conformance with DOD guidelines and has not been approved. iect cannot proceed at this location.

If mitigation measures have been or will be taken, explain in detail the proposed measures that must be implemented to mitigate for the impact or effect, including the timeline for implementation.

Click here to enter text.

→ Work with the RE/HUD to develop mitigation measures. Continue to the Worksheet Summary below. Provide any documentation supporting this determination.

Worksheet Summary

The project site is not within 15,000 feet of a military airport or 2,500 feet of a civilian airport. The nearest municipal airport is the John Wayne Airport, approximately 8.9 miles southeast of the project site.

See Attachment 2.

ERR No. 2. Coastal Barrier Resources



U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

WASHINGTON, DC 20410-1000

This Worksheet was designed to be used by those "Partners" (including Public Housing Authorities, consultants, contractors, and nonprofits) who assist Responsible Entities and HUD in preparing environmental reviews, but legally cannot take full responsibilities for these reviews themselves. Responsible Entities and HUD should use the RE/HUD version of the Worksheet.

Coastal Barrier Resources (CEST and EA) - PARTNER

https://www.hudexchange.info/environmental-review/coastal-barrier-resources

Projects located in the following states must complete this form.

Alabama	Georgia	Massachusetts	New Jersey	Puerto Rico	Virgin Islands
Connecticut	Louisiana	Michigan	New York	Rhode Island	Virginia
Delaware	Maine	Minnesota	North Carolina	South Carolina	Wisconsin
Florida	Maryland	Mississippi	Ohio	Texas	

1. Is the project located in a CBRS Unit?

☑No → If the RE/HUD agrees with this recommendation, the review is in compliance with this section. Continue to the Worksheet Summary below. Provide a map showing that the site is not within a CBRS Unit.

 \square Yes \rightarrow Continue to 2.

<u>Federal assistance for most activities may not be used at this location. You must either choose an alternate site or cancel the project.</u> In very rare cases, federal monies can be spent within CBRS units for certain exempted activities (e.g., a nature trail), after consultation with the Fish and Wildlife Service (FWS) (see <u>16 USC 3505</u> for exceptions to limitations on expenditures).

2. Indicate your recommended course of action for the RE/HUD

\square Consultation with the F	WS
☐ Cancel the project	

Worksheet Summary

According to Coastal Barrier Resources System (CBRS) information accessed at https://fwsprimary.wim.usgs.gov/CBRSMapper-v2/, there are no units of the CBRS in California, and the project site is not located within a CBRS Unit. Therefore, the project is in compliance with HUD's CBRS regulations, and no mitigation is warranted. This project is in compliance with the Coastal Barrier Resources Act.

See Attachment 2.

ERR No. 3. Flood Insurance



U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

WASHINGTON, DC 20410-1000

This Worksheet was designed to be used by those "Partners" (including Public Housing Authorities, consultants, contractors, and nonprofits) who assist Responsible Entities and HUD in preparing environmental reviews, but legally cannot take full responsibilities for these reviews themselves. Responsible Entities and HUD should use the RE/HUD version of the Worksheet.

Flood Insurance (CEST and EA)

General requirements	Legislation	Regulation					
Certain types of federal financial assistance may	Flood Disaster	24 CFR 50.4(b)(1)					
not be used in floodplains unless the community	Protection Act of	and 24 CFR					
participates in National Flood Insurance Program	1973 as amended	58.6(a) and (b);					
and flood insurance is both obtained and	(42 USC 4001-4128)	24 CFR 55.1(b).					
maintained.							
Reference							
https://www.hudexchange.info/environmental-review/flood-insurance							

1. Does this project involve mortgage insurance, refinance, acquisition, repairs, construction, or rehabilitation of a structure, mobile home, or insurable personal property?

□No.	This project	does n	ot require	${\sf flood}$	insurance	or is	excepted	from	flood	insuranc	e
	→ Continue to	the Wo	rksheet Sum	nmary.							

 \boxtimes Yes \rightarrow Continue to Question 2.

2. Provide a FEMA/FIRM map showing the site.

The Federal Emergency Management Agency (FEMA) designates floodplains. The <u>FEMA Map Service Center</u> provides this information in the form of FEMA Flood Insurance Rate Maps (FIRMs). For projects in areas not mapped by FEMA, use the best available information to determine floodplain information. Include documentation, including a discussion of why this is the best available information for the site. Provide FEMA/FIRM floodplain zone designation, panel number, and date within your documentation.

Is the structure, part of the structure, or insurable property located in a FEMA-designated Special Flood Hazard Area?

$oxines$ No $oldsymbol{ o}$ Continue to the Worksheet Summary
\Box Yes \rightarrow Continue to Question 3.

3. Is the community participating in the National Flood Insurance Program or has less than one year passed since FEMA notification of Special Flood Hazards? □Yes, the community is participating in the National Flood Insurance Program. For loans, loan insurance or loan guarantees, flood insurance coverage must be continued for the term of the loan. For grants and other non-loan forms of financial assistance, flood insurance coverage must be continued for the life of the building irrespective of the transfer of ownership. The amount of coverage must equal the total project cost or the maximum coverage limit of the National Flood Insurance Program, whichever is less. Provide a copy of the flood insurance policy declaration or a paid receipt for the current annual flood insurance premium and a copy of the application for flood insurance. → Continue to the Worksheet Summary.	:
 □Yes, less than one year has passed since FEMA notification of Special Flood Hazards. If less than one year has passed since notification of Special Flood Hazards, no flood Insurance is required. → Continue to the Worksheet Summary. □ No. The community is not participating, or its participation has been suspended. 	
Federal assistance may not be used at this location. Cancel the project at this location. Worksheet Summary	2
According to FEMA FIRM # 06059C0164J, both effective on December 3, 2009 and accessed at https://msc.fema.gov/portal/home , the project site is within Zone X - Unshaded (Area of minimal flood hazard) (FEMA 2012). The project site is designated as an area outside the 100-year base flood zone and the 500-year flood zone. According to the National Flood Insurance Program's (NFIP) Community Status Book (https://www.fema.gov/flood-insurance/work-with-nfip/community-status-book), the project site is in Community ID 060228#, which is a participating community in the NFIP. However, because no structures or insurable properties are within a Special Flood Hazard Area, flood insurance is not required under the NFIP. Although flood insurance may not be mandatory in this instance, HUD recommends that all insurable structures maintain flood insurance under the NFIP. The project is in compliance with flood insurance requirements.	
Are formal compliance steps or mitigation required? ☐ Yes ☐ No	

ERR No. 4. Air Quality



U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

WASHINGTON, DC 20410-1000

This Worksheet was designed to be used by those "Partners" (including Public Housing Authorities, consultants, contractors, and nonprofits) who assist Responsible Entities and HUD in preparing environmental reviews, but legally cannot take full responsibilities for these reviews themselves. Responsible Entities and HUD should use the RE/HUD version of the Worksheet.

Air Quality (CEST and EA) - PARTNER

https://www.hudexchange.info/environmental-review/air-quality

1. Does your project include new construction or conversion of land use facilitate development of public, commercial, or industrial facilities OR five or more dwelling unit		
	⊠ Yes	→ Continue to Question 2.
	□No	\Rightarrow If the RE/HUD agrees with this recommendation, the review is in compliance with this section. Provide any documents used to make your determination.
2.	status follow district	project's air quality management district or county in non-attainment or maintenance for any criteria pollutants? the link below to determine compliance status of project county or air quality management: www.epa.gov/oaqps001/greenbk/
	pol →	project's county or air quality management district is in attainment status for all criteria lutants If the RE/HUD agrees with this recommendation, the review is in compliance with this section. Continue to the Worksheet Summary below. Provide any documents used to make your determination.
		, project's management district or county is in non-attainment or maintenance status for e or more criteria pollutants. \Rightarrow Continue to Question 3.

- 3. Determine the <u>estimated emissions levels of your project for each of those criteria pollutants</u> that are in non-attainment or maintenance status on your project area. Will your project exceed any of the *de minimis or threshold* emissions levels of non-attainment and maintenance level pollutants or exceed the screening levels established by the state or air quality management district?
 - ☑ No, the project will not exceed *de minimis* or threshold emissions levels or screening levels
 - → If the RE/HUD agrees with this recommendation, the review is in compliance with this section. Explain how you determined that the project would not exceed de minimis or threshold emissions.

\square Yes, the project exceeds <i>de minimis</i> emissions levels or screening levels.	
--------------------------------------------------------------------------------------------	--

- → Continue to Question 4. Explain how you determined that the project would not exceed de minimis or threshold emissions in the Worksheet Summary.
- 4. For the project to be brought into compliance with this section, all adverse impacts must be mitigated. Explain in detail the exact measures that must be implemented to mitigate for the impact or effect, including the timeline for implementation.

Click here to enter text.

Worksheet Summary

CalEEMod was used to model emissions during the construction and operational phases of the proposed project. Results of the model indicate that the proposed project would not exceed the South Coast Air Quality Management District's emissions thresholds during the construction or operational phases. Estimated annual construction emissions for the proposed project, assuming construction would occur in 2024–2025, are approximately 610.08 metric tons (30-year amortized emissions would reduce this to 20.34 metric tons). Estimated annual emissions during the operational phase are approximately 718.89 metric tons. In total, the proposed project is estimated to produce 739.23 metric tons of emissions per year. Daily emissions from the proposed project would not exceed the SCAQMD's regional construction or operation emissions thresholds.

See Attachment 5.

ERR No. 5. Coastal Zone Management Act



U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT WASHINGTON, DC 20410-1000

This Worksheet was designed to be used by those "Partners" (including Public Housing Authorities, consultants, contractors, and nonprofits) who assist Responsible Entities and HUD in preparing environmental reviews, but legally cannot take full responsibilities for these reviews themselves. Responsible Entities and HUD should use the RE/HUD version of the Worksheet.

Coastal Zone Management Act (CEST and EA)

General requirements	Legislation	Regulation				
Federal assistance to applicant	Coastal Zone Management	15 CFR Part 930				
agencies for activities affecting	Act (16 USC 1451-1464),					
any coastal use or resource is	particularly section 307(c) and					
granted only when such	(d) (16 USC 1456(c) and (d))					
activities are consistent with						
federally approved State Coastal						
Zone Management Act Plans.						
References						
https://www.onecpd.info/environmental-review/coastal-zone-management						

Projects located in the following states must complete this form.

 \square Yes \rightarrow Continue to Question 3.

Alabama	Florida	Louisiana	Mississippi	Ohio	Texas
Alaska	Georgia	Maine	New Hampshire	Oregon	Virgin Islands
American Samona	Guam	Maryland	New Jersey	Pennsylvania	Virginia
California	Hawaii	Massachusetts	New York	Puerto Rico	Washington
Connecticut	Illinois	Michigan	North Carolina	Rhode Island	Wisconsin
Delaware	Indiana	Minnesota	Northern Mariana Islands	South Carolina	

1.	Is the project located in, or does it affect, a Coastal Zone as defined in your state Coasta
	Management Plan?

2.	Does this	project include activities that are subject to state review?
	⊠No →	Based on the response, the review is in compliance with this section. Continue to the Worksheet Summary below. Provide a map showing that the site is not within a Coastal Zone.
	□Yes →	Continue to Question 2.

□ No → Based on the response, the review is in compliance with this section. Continue to the Worksheet Summary below. Provide documentation used to make your determination.

Yes, with mitigation. → Continue to Question 4. Yes, without mitigation. → Based on the response, the review is in compliance with this section. Continue to the Worksheet Summary below. Provide documentation used to make your determination. No, project must be canceled. Project cannot proceed at this location. 4. Explain in detail the proposed measures that must be implemented to mitigate for the impact or effect, including the timeline for implementation. A	3.	Has this project been determined to be consistent with the State Coastal Management Program?
section. Continue to the Worksheet Summary below. Provide documentation used to make your determination. \[\begin{align*} \text{No, project must be canceled.} \\ \text{Project cannot proceed at this location.} \end{align*} \] 4. Explain in detail the proposed measures that must be implemented to mitigate for the impact or effect, including the timeline for implementation. \[\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text{\$\text		\square Yes, with mitigation. \rightarrow Continue to Question 4.
A. Explain in detail the proposed measures that must be implemented to mitigate for the impact or effect, including the timeline for implementation. → Continue to the Worksheet Summary below. Provide documentation of the consultation (including the State Coastal Management Program letter of consistency) and any other documentation used to make your determination. Worksheet Summary The proposed project site is not within the California Coastal Zone. Therefore, the proposed undertaking is in compliance with HUD's Coastal Zone Management Act regulations, and no mitigation is warranted. The project is in compliance with the Coastal Zone Management Act (see Attachment 6). Are formal compliance steps or mitigation required?		section. Continue to the Worksheet Summary below. Provide documentation used to
A. Explain in detail the proposed measures that must be implemented to mitigate for the impact or effect, including the timeline for implementation. → Continue to the Worksheet Summary below. Provide documentation of the consultation (including the State Coastal Management Program letter of consistency) and any other documentation used to make your determination. Worksheet Summary The proposed project site is not within the California Coastal Zone. Therefore, the proposed undertaking is in compliance with HUD's Coastal Zone Management Act regulations, and no mitigation is warranted. The project is in compliance with the Coastal Zone Management Act (see Attachment 6). Are formal compliance steps or mitigation required?		□No, project must be canceled.
→ Continue to the Worksheet Summary below. Provide documentation of the consultation (including the State Coastal Management Program letter of consistency) and any other documentation used to make your determination. Worksheet Summary The proposed project site is not within the California Coastal Zone. Therefore, the proposed undertaking is in compliance with HUD's Coastal Zone Management Act regulations, and no mitigation is warranted. The project is in compliance with the Coastal Zone Management Act (see Attachment 6). Are formal compliance steps or mitigation required?		
consultation (including the State Coastal Management Program letter of consistency) and any other documentation used to make your determination. Worksheet Summary The proposed project site is not within the California Coastal Zone. Therefore, the proposed undertaking is in compliance with HUD's Coastal Zone Management Act regulations, and no mitigation is warranted. The project is in compliance with the Coastal Zone Management Act (see Attachment 6). Are formal compliance steps or mitigation required? Yes	4.	
consultation (including the State Coastal Management Program letter of consistency) and any other documentation used to make your determination. Worksheet Summary The proposed project site is not within the California Coastal Zone. Therefore, the proposed undertaking is in compliance with HUD's Coastal Zone Management Act regulations, and no mitigation is warranted. The project is in compliance with the Coastal Zone Management Act (see Attachment 6). Are formal compliance steps or mitigation required? Yes		
consultation (including the State Coastal Management Program letter of consistency) and any other documentation used to make your determination. Worksheet Summary The proposed project site is not within the California Coastal Zone. Therefore, the proposed undertaking is in compliance with HUD's Coastal Zone Management Act regulations, and no mitigation is warranted. The project is in compliance with the Coastal Zone Management Act (see Attachment 6). Are formal compliance steps or mitigation required? Yes		
The proposed project site is not within the California Coastal Zone. Therefore, the proposed undertaking is in compliance with HUD's Coastal Zone Management Act regulations, and no mitigation is warranted. The project is in compliance with the Coastal Zone Management Act (see Attachment 6). Are formal compliance steps or mitigation required?		consultation (including the State Coastal Management Program letter of
undertaking is in compliance with HUD's Coastal Zone Management Act regulations, and no mitigation is warranted. The project is in compliance with the Coastal Zone Management Act (see Attachment 6). Are formal compliance steps or mitigation required? Yes	W	orksheet Summary
□ Yes	u	ndertaking is in compliance with HUD's Coastal Zone Management Act regulations, and no mitigation
□ Yes		
□ Yes		
□ Yes	Δr	e formal compliance steps or mitigation required?
	ΑI	

ERR No. 6. Contamination and Toxic Substances (Multifamily and Non-Residential Properties)

OMB No. 2506-0177 (exp. 2/28/2025)



U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

WASHINGTON, DC 20410-1000

This Worksheet was designed to be used by those "Partners" (including Public Housing Authorities, consultants, contractors, and nonprofits) who assist Responsible Entities and HUD in preparing environmental reviews, but legally cannot take full responsibilities for these reviews themselves. Responsible Entities and HUD should use the RE/HUD version of the Worksheet.

Contamination and Toxic Substances (Multifamily and Non-Residential Properties) – PARTNER

https://www.hudexchange.info/programs/environmental-review/site-contamination

1.	How was site contamination evaluated? 1 Select all that apply.
	☑ ASTM Phase I ESA
	☐ ASTM Phase II ESA
	☐ Remediation or clean-up plan
	☐ ASTM Vapor Encroachment Screening
	☐ None of the above
	→ Provide documentation and reports and include an explanation of how site contamination
	was evaluated in the Worksheet Summary.
	Continue to Question 2.
2.	Were any on-site or nearby toxic, hazardous, or radioactive substances found that could affect the health and safety of project occupants or conflict with the intended use of the property?
	(Were any recognized environmental conditions or RECs identified in a Phase I ESA and
	confirmed in a Phase II ESA?)
	\boxtimes No \rightarrow Explain below.
	The proposed project site is currently vacant. A Phase I Environmental Site Assessment (ESA) conducted by AEI Consultants (AEI) in September 2023 did not find any recognized environmental conditions (RECs), controlled RECs, or historical RECs on the project site. A Pre-Renovation Asbestos and Lead Assessment for the project site completed by EFI Global in August 2020 identified asbestos containing materials and lead-based paint in the

existing building onsite. Though the Phase I ESA should not be construed as a mold survey and inspection. However, during the site reconnaissance for the Phase I, the obvious visible signs of mold growth or conditions conducive for suspect mold growth were observed.

HUD regulations at 24 CFR § 58.5(i)(2)(ii) require that the environmental review for multifamily housing with five or more dwelling units or non-residential property include the evaluation of previous uses of the site or other evidence of contamination on or near the site. For acquisition and new construction of multifamily and nonresidential properties HUD strongly advises the review include an ASTM Phase I Environmental Site Assessment (ESA) to meet real estate transaction standards of due diligence and to help ensure compliance with HUD's toxic policy at 24 CFR §58.5(i) and 24 CFR §50.3(i). Also note that some HUD programs require an ASTM Phase I ESA.

	ightarrow If the RE/HUD agrees with this recommendation, the review is in compliance with
	this section. Continue to the Worksheet Summary below.
	\square Yes $ o$ Describe the findings, including any recognized environmental conditions
	(RECs), in Worksheet Summary below. Continue to Question 3.
3.	Can adverse environmental impacts be mitigated?
	☐ Adverse environmental impacts cannot feasibly be mitigated → <u>HUD assistance may not be</u> used for the project at this site. Project cannot proceed at this location.
	 ☐ Yes, adverse environmental impacts can be eliminated through mitigation. → Provide all mitigation requirements² and documents. Continue to Question 4.
4.	Describe how compliance was achieved. Include any of the following that apply: State Voluntary Clean-up Program, a No Further Action letter, use of engineering controls ³ , or use of institutional controls ⁴ . Click here to enter text.
	If a remediation plan or clean-up program was necessary, which standard does it follow?
	☐ Complete removal
	\square Risk-based corrective action (RBCA)
	→ Continue to the Worksheet Summary.

Worksheet Summary

A Phase I Environmental Site Assessment (ESA) conducted by Partner Engineering, Inc. (Partner) in September 2023 did not find any recognized environmental conditions (RECs), controlled RECs, or historical RECs on the project site. A Pre-Renovation Asbestos and Lead Assessment for the project site completed by EFI Global in August 2020 identified asbestos containing materials and lead-based paint in the existing building onsite. All asbestos containing materials (ACMs) and lead-based paint (LBP) was found to be in good condition at the time of the assessment. Mitigation for ACMs and LBP has been included in the environmental assessment. Materials found to contain asbestos and/or presumed to contain asbestos that could be impacted during renovation or demolition activities, by law, must first be abated and properly disposed of by a licensed asbestos abatement contractor prior to such work (MM-TOX-1).

Mitigation requirements include all clean-up actions required by applicable federal, state, tribal, or local law. Additionally, provide, as applicable, the long-term operations and maintenance plan, Remedial Action Work Plan, and other equivalent documents.

Engineering controls are any physical mechanism used to contain or stabilize contamination or ensure the effectiveness of a remedial action. Engineering controls may include, without limitation, caps, covers, dikes, trenches, leachate collection systems, signs, fences, physical access controls, ground water monitoring systems and ground water containment systems including, without limitation, slurry walls and ground water pumping systems.

Institutional controls are mechanisms used to limit human activities at or near a contaminated site, or to ensure the effectiveness of the remedial action over time, when contaminants remain at a site at levels above the applicable remediation standard which would allow for unrestricted use of the property. Institutional controls may include structure, land, and natural resource use restrictions, well restriction areas, classification exception areas, deed notices, and declarations of environmental restrictions.

In addition, LBP that would be impacted by hot work (welding, torch cutting, etc.) must be removed from the component by lead abatement workers to allow a minimum of 6 inches clearance on either side of the location of the hot work to prevent the volatilization of lead into the air (MM-TOX-2).

Though the Phase I ESA should not be construed as a mold survey and inspection. However, during the site reconnaissance for the Phase I, the obvious visible signs of mold growth or conditions conducive for suspect mold growth were observed.

See Attachments 7 and 8.

ERR No. 7. Endangered Species Act



U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

WASHINGTON, DC 20410-1000

This Worksheet was designed to be used by those "Partners" (including Public Housing Authorities, consultants, contractors, and nonprofits) who assist Responsible Entities and HUD in preparing environmental reviews, but legally cannot take full responsibilities for these reviews themselves. Responsible Entities and HUD should use the RE/HUD version of the Worksheet.

Endangered Species Act (CEST and EA) – PARTNER

https://www.hudexchange.info/environmental-review/endangered-species

1.	Does the project in	nvolve any activities	that have t	he potential to	affect species or	habitats?
----	---------------------	-----------------------	-------------	-----------------	-------------------	-----------

- □No, the project will have No Effect due to the nature of the activities involved in the project.
 - → If the RE/HUD agrees with this recommendation, the review is in compliance with this section.

 Continue to the Worksheet Summary below. Provide any documents used to make your determination.
- □No, the project will have No Effect based on a letter of understanding, memorandum of agreement, programmatic agreement, or checklist provided by local HUD office.

Explain your determination:

Click here to enter text.

- → If the RE/HUD agrees with this recommendation, the review is in compliance with this section.

 Continue to the Worksheet Summary below. Provide any documents used to make your determination.
- \boxtimes Yes, the activities involved in the project have the potential to affect species and/or habitats. \Rightarrow Continue to Question 2.

2. Are federally listed species or designated critical habitats present in the action area? Obtain a list of protected species from the Services. This information is available on the <u>FWS Website</u>.

⊠No, the project will have No Effect due to the absence of federally listed species and designated critical habitat.

→ If the RE/HUD agrees with this recommendation, the review is in compliance with this section.

Continue to the Worksheet Summary below. Provide any documents used to make your determination. Documentation may include letters from the Services, species lists from the Services' websites, surveys or other documents and analysis showing that there are no species in the action area.

☐Yes, there are federally listed species or designated critical habitats present in the action are	a. →
Continue to Question 3.	

- 3. Recommend one of the following effects that the project will have on federally listed species or designated critical habitat:
 - □No Effect: Based on the specifics of both the project and any federally listed species in the action area, you have determined that the project will have absolutely no effect on listed species or critical habitat.
 - → If the RE/HUD agrees with this recommendation, the review is in compliance with this section.

 Continue to the Worksheet Summary below. Provide any documents used to make your determination. Documentation should include a species list and explanation of your conclusion, and may require maps, photographs, and surveys as appropriate.
 - ☐ May Affect, Not Likely to Adversely Affect: Any effects that the project may have on federally listed species or critical habitats would be beneficial, discountable, or insignificant.
 - → Partner entities should not contact the Services directly. If the RE/HUD agrees with this recommendation, they will have to complete Informal Consultation. Provide the RE/HUD with a biological evaluation or equivalent document. They may request additional information, including surveys and professional analysis, to complete their consultation.
 - □Likely to Adversely Affect: The project may have negative effects on one or more listed species or critical habitat.
 - → Partner entities should not contact the Services directly. If the RE/HUD agrees with this recommendation, they will have to complete Formal Consultation. Provide the RE/HUD with a biological evaluation or equivalent document. They may request additional information, including surveys and professional analysis, to complete their consultation.

Worksheet Summary

The U.S. Fish and Wildlife Service IPaC database was used to identify federally protected species at the project site. Six species classified as endangered or threatened were identified as possibly occurring on the project site. However, given the urban and commercial setting of the site and of the surrounding project area, no federally listed special-status plant or wildlife species are expected to be present due to the lack of suitable habitat.

See Attachment 9.

ERR No. 8. Explosive and Flammable Hazards



U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

WASHINGTON, DC 20410-1000

This Worksheet was designed to be used by those "Partners" (including Public Housing Authorities, consultants, contractors, and nonprofits) who assist Responsible Entities and HUD in preparing environmental reviews, but legally cannot take full responsibilities for these reviews themselves. Responsible Entities and HUD should use the RE/HUD version of the Worksheet.

Explosive and Flammable Hazards (CEST and EA) - PARTNER

https://www.hudexchange.info/environmental-review/explosive-and-flammable-facilities

	boes the proposed HUD-assisted project include a hazardous facility (a facility that mainly stores, handles or processes flammable or combustible chemicals such as bulk fuel storage facilities and refineries)?
	⊠ No
	→ Continue to Question 2.
	□ Yes
	Explain:
	Click here to enter text.
	→ Continue to Question 5.
	Does this project include any of the following activities: development, construction, rehabilitation that will increase residential densities, or conversion?
	\square No $ o$ If the RE/HUD agrees with this recommendation, the review is in compliance with this
	section. Continue to the Worksheet Summary below.
	\boxtimes Yes \rightarrow Continue to Question 3.
	Within 1 mile of the project site, are there any current or planned stationary aboveground storage containers:
	Of more than 100-gallon capacity, containing common liquid industrial fuels OR
	 Of any capacity, containing hazardous liquids or gases that are not common liquid industrial fuels?
	\square No \Rightarrow If the RE/HUD agrees with this recommendation, the review is in compliance with this section. Continue to the Worksheet Summary below. Provide all documents used to make your determination.
	\boxtimes Yes \rightarrow Continue to Question 4.
4	Is the Separation Distance from the project acceptable based on standards in the Regulation? Please visit HUD's website for information on calculating Acceptable Separation Distance.

→ If the RE/HUD agrees with this recommendation, the review is in compliance with this

section. Continue to the Worksheet Summary below.

Provide map(s) showing the location of the project site relative to any tanks and your separation distance calculations. If the map identifies more than one tank, please identify the tank you have chosen as the "assessed tank."

□ No

→ Continue to Question 6.

Provide map(s) showing the location of the project site relative to any tanks and your separation distance calculations. If the map identifies more than one tank, please identify the tank you have chosen as the "assessed tank."

5. Is the hazardous facility located at an acceptable separation distance from residences and any other facility or area where people may congregate or be present?

Please visit HUD's website for information on calculating Acceptable Separation Distance.

☐ Yes

→ If the RE/HUD agrees with this recommendation, the review is in compliance with this section. Continue to the Worksheet Summary below.

Provide map(s) showing the location of the project site relative to residences and any other facility or area where people congregate or are present and your separation distance calculations.

□ No

→ Continue to Question 6.

Provide map(s) showing the location of the project site relative to residences and any other facility or area where people congregate or are present and your separation distance calculations.

6. For the project to be brought into compliance with this section, all adverse impacts must be mitigated. Explain in detail the exact measures that must be implemented to make the Separation Distance acceptable, including the timeline for implementation. If negative effects cannot be mitigated, cancel the project at this location.

Note that only licensed professional engineers should design and implement blast barriers. If a barrier will be used or the project will be modified to compensate for an unacceptable separation distance, provide approval from a licensed professional engineer.

Click here to enter text.

Worksheet Summary

The following resources were reviewed to identify aboveground storage tank (AST) locations, contents, volumes, and distance from subject property:

- EDR Radius Report for the project site with a 1-mile radius buffering the site
- California Environmental Protection Agency (CalEPA) Regulated Site Portal at https://siteportal.calepa.ca.gov/nsite/map/help
- Appendix I to Subpart C of Parts 51- Specific Hazardous Substances at https://www.ecfr.gov/current/title-24/subtitle-A/part-51/subpart-C
- HUD Acceptable Separation Distance (ASD) Electronic Assessment Tool at https://www.hudexchange.info/programs/environmental-review/asd-calculator/

An EDR Radius Report was obtained for the proposed project site to identify aboveground storage tanks (ASTs) within a 1-mile radius of the project area. The report identified three sites with ASTs but did not provide details on the size and content of all ASTs listed within 1-mile of the project site. The CalEPA Regulated Site Portal website was then used to identify and evaluate the type and amounts of chemicals stored at each site identified as having an AST by the EDR report. Chemicals listed for each site were compared to a list of hazardous substances provided in Appendix I to Subpart C of Part 51 (§ 51.201). Chemicals not listed in § 51.201 were considered non-hazardous. HUD's Acceptable Separation Distance (ASD) Assessment Tool was used to calculate the acceptable separation distance between the project site and the CalEPA sites that contained hazardous materials.

All three sites identified as potentially storing hazardous or flammable materials in ASTs were adequately separated from the project site for thermal radiation for people. Maps and ASD calculations for the sites that contain materials listed 24 CFR 51C are provided in **Attachment 10**.

ERR No. 9. Farmlands Protection



U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT WASHINGTON, DC 20410-1000

This Worksheet was designed to be used by those "Partners" (including Public Housing Authorities, consultants, contractors, and nonprofits) who assist Responsible Entities and HUD in preparing environmental reviews, but legally cannot take full responsibilities for these reviews themselves. Responsible Entities and HUD should use the RE/HUD version of the Worksheet.

Farmlands Protection (CEST and EA)

General requirements	Legislation	Regulation			
The Farmland Protection	Farmland Protection Policy	7 CFR Part 658			
Policy Act (FPPA) discourages	Act of 1981 (7 U.S.C. 4201 et				
federal activities that would seq.)					
convert farmland to					
nonagricultural purposes.					
Reference					
https://www.hudexchange.info/environmental-review/farmlands-protection					

1.	Does your pro	oject ir	nclude any	activities	, including	new consti	uction, acc	រុuisitior	n of
	undeveloped	land o	or conversi	on, that	could con	vert agricul	tural land	to a r	on-
	agricultural us	se?							

\square Yes	→ Continue to Question 2
⊠No	

Explain how you determined that agricultural land would not be converted:

The California Department of Conservation's California Important Farmland Finder, accessed at https://maps.conservation.ca.gov/dlrp/ciff/, was used to identify Important Farmlands in the project area.

2. Does "important farmland," including prime farmland, unique farmland, or farmland of statewide or local importance regulated under the Farmland Protection Policy Act, occur on the project site?

You may use the links below to determine important farmland occurs on the project site:

- Utilize USDA Natural Resources Conservation Service's (NRCS) Web Soil Survey http://websoilsurvey.nrcs.usda.gov/app/HomePage.htm
- Check with your city or county's planning department and ask them to document if the project is on land regulated by the FPPA (zoning important farmland as nonagricultural does not exempt it from FPPA requirements)

[→] Based on the response, the review is in compliance with this section. Continue to the Worksheet Summary below. Provide any documentation supporting your determination.

	•	Contact NRCS at the local USDA service center		
		http	o://offices.sc.egov.usda.gov/locator/app?agency=nrcs or your NRCS state soil	
		scie	ntist http://soils.usda.gov/contact/state offices/ for assistance	
	⊠No	\rightarrow	Based on the response, the review is in compliance with this section. Continue to the Worksheet Summary below. Provide any documents used to make your determination.	
	□Yes	\rightarrow	Continue to Question 3.	
3.	Consider alternatives to completing the project on important farmland and means of avoiding impacts to important farmland.			
	Docui Pro	Com http the (NO Con Inte Who NRO info ment ject	nplete form AD-1006, "Farmland Conversion Impact Rating" 1://www.nrcs.usda.gov/Internet/FSE DOCUMENTS/stelprdb1045394.pdf and contact state soil scientist before sending it to the local NRCS District Conservationist. TE: for corridor type projects, use instead form NRCS-CPA-106, "Farmland version Impact Rating for Corridor Type Projects: http://www.nrcs.usda.gov/rrnet/FSE DOCUMENTS/stelprdb1045395.pdf .) Tk with NRCS to minimize the impact of the project on the protected farmland. It is not the project on the protected farmland. It is not the project on the protected farmland. It is not the USDA-NRCS State Soil Scientist or his/her designee that mit is the proposed measures that must be implemented to mitigate for the profession of the proposed measures that must be implemented to mitigate for the profession of the proposed measures that must be implemented to mitigate for the profession of the proposed measures that must be implemented to mitigate for the profession of the proposed measures that must be implemented to mitigate for the profession of the proposed measures that must be implemented to mitigate for the profession of the prof	
	<u></u>		Based on the response, the review is in compliance with this section. Continue to the Worksheet Summary below. Provide form AD-1006 and all other documents used to make your determination.	
	□Pro	ject	will proceed without mitigation.	
	Ex	plaiı	n why mitigation will not be made here:	
	L			

Based on the response, the review is in compliance with this section. Continue to the Worksheet Summary below. Provide form AD-1006 and all other documents used to make your determination.

Worksheet Summary

The California Department of Conservation's California Important Farmland Finder, accessed at https://maps.conservation.ca.gov/dlrp/ciff/, was used to identify Important Farmlands in the project area. The project site is on land designated as Urban and Built-Up Land. Furthermore, the proposed project would be built above an existing garage, and no ground-disturbing activities are required. There are no Important Farmlands on the project site or in adjacent areas (see Attachment 11). The project is in compliance with the Farmland Protection Policy.

ERR No. 10. Floodplain Management



U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT WASHINGTON, DC 20410-1000

This Worksheet was designed to be used by those "Partners" (including Public Housing Authorities, consultants, contractors, and nonprofits) who assist Responsible Entities and HUD in preparing environmental reviews, but legally cannot take full responsibilities for these reviews themselves. Responsible Entities and HUD should use the RE/HUD version of the Worksheet.

Floodplain Management (CEST and EA) – PARTNER https://www.hudexchange.info/environmental-review/floodplain-management

1.	Does 24 CFR 55.12(c) exempt this project from compliance with HUD's floodplain management
	regulations in Part 55?
	□ Yes
	Provide the applicable citation at 24 CFR 55.12(c) here. If project is exempt under 55.12(c)(6) or (8), provide supporting documentation. Click here to enter text.
	→ If the RE/HUD agrees with this recommendation, the review is in compliance with this section. Continue to the Worksheet Summary below. Continue to the Worksheet Summary.
	\boxtimes No \rightarrow Continue to Question 2.
2.	Provide a FEMA/FIRM map showing the site. The Federal Emergency Management Agency (FEMA) designates floodplains. The FEMA Map Service Center provides this information in the form of FEMA Flood Insurance Rate Maps (FIRMs).
	Does your project occur in a floodplain? ⊠ No → Continue to the Worksheet Summary below.
	□ Yes
	Select the applicable floodplain using the FEMA map or the best available information: ☐ Floodway → Continue to Question 3, Floodways
	☐ Coastal High Hazard Area (V Zone) → Continue to Question 4, Coastal High Hazard Areas
	□ 500-year floodplain (B Zone or shaded X Zone) → Continue to Question 5, 500-year Floodplains
	☐ 100-year floodplain (A Zone) → The 8-Step Process is required. Continue to Question 6, 8-Step Process
3.	<u>Floodways</u>
	Is this a functionally dependent use?
	☐ Yes
	The 8-Step Process is required. Work with HUD or the RE to assist with the 8-Step Process.

	→ Continue to Worksheet Summary.
	□ No → Federal assistance may not be used at this location unless an exception in 55.12(c) applies. You must either choose an alternate site or cancel the project.
4.	Coastal High Hazard Area
	Is this a critical action such as a hospital, nursing home, fire station, or police station?
	\square Yes \rightarrow Critical actions are prohibited in coastal high hazard areas unless an exception in 55.12(c)
	applies. You must either choose an alternate site or cancel the project.
	□ No
	Does this action include new construction that is not a functionally dependent use, existing construction (including improvements), or reconstruction following destruction caused by a disaster?
	\square Yes, there is new construction of something that is not a functionally dependent use.
	New construction must be designed to FEMA standards for V Zones at 44 CFR 60.3(e) (24 CFR 55.1(c)(3)(i)).
	→ Continue to Question 6, 8-Step Process
	☐ No, this action concerns only existing construction.
	Existing construction must have met FEMA elevation and construction standards for a
	coastal high hazard area or other standards applicable at the time of construction.
	→ Continue to Question 6, 8-Step Process
5.	500-year Floodplain
	Is this a critical action?
	\square No \rightarrow If the RE/HUD agrees with this recommendation, the review is in compliance with this
	section. Continue to the Worksheet Summary below.
	□Yes → Continue to Question 6, 8-Step Process
6.	8-Step Process.
	Is this 8-Step Process required? Select one of the following options:
	□ 8-Step Process applies.
	This project will require mitigation and may require elevating structure or structures. See the link to the HUD Exchange above for information on HUD's elevation requirements.
	→ Work with the RE/HUD to assist with the 8-Step Process. Continue to Worksheet Summary.
	☐ 5-Step Process is applicable per 55.12(a)(1-3).
	Provide the applicable citation at 24 CFR 55.12(a) here.
	Click here to enter text.
	→ Work with the RE/HUD to assist with the 5-Step Process. Continue to Worksheet Summary.
	☐ 8-Step Process is inapplicable per 55.12(b)(1-4).
	Provide the applicable citation at 24 CFR 55.12(b) here.
	Click here to enter text.

→ If the RE/HUD agrees with this recommendation, the review is in compliance with this section. Continue to the Worksheet Summary below.

Worksheet Summary

According to FEMA FIRM Panel # 06059C0164J, effective on December 3, 2009 and accessed at https://msc.fema.gov/portal/home, the project site is within Zone X - Unshaded (Area of minimal flood hazard) (FEMA 2012). The project site is designated as an area outside the 100-year base flood zone and the 500-year flood zone (see Attachment 4).

ERR No. 11. Historic Preservation

OMB No. 2506-0177 (exp. 2/28/2025)



U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

WASHINGTON, DC 20410-1000

This Worksheet was designed to be used by those "Partners" (including Public Housing Authorities, consultants, contractors, and nonprofits) who assist Responsible Entities and HUD in preparing environmental reviews, but legally cannot take full responsibilities for these reviews themselves. Responsible Entities and HUD should use the RE/HUD version of the Worksheet.

Historic Preservation (CEST and EA) - PARTNER

https://www.hudexchange.info/environmental-review/historic-preservation

Threshold

Is Section 106 review required for your project?

□ No, because a Programmatic Agreement states that all activities included in this project are exempt. (See the <u>PA Database</u> to find applicable PAs.)

Either provide the PA itself or a link to it here. Mark the applicable exemptions or include the text here:

Click here to enter text.

→ Continue to the Worksheet Summary.

□ No, because the project consists solely of activities included in a No Potential to Cause Effects memo or other determination [36 CFR 800.3(a)(1)].

Either provide the memo itself or a link to it here. Explain and justify the other determination here:

Click here to enter text.

→ Continue to the Worksheet Summary.

☑Yes, because the project includes activities with potential to cause effects (direct or indirect). →

Continue to Step 1.

The Section 106 Process

After determining the need to do a Section 106 review, HUD or the RE will initiate consultation with regulatory and other interested parties, identify and evaluate historic properties, assess effects of the project on properties listed on or eligible for the National Register of Historic Places, and resolve any adverse effects through project design modifications or mitigation.

Step 1: Initiate consultation

Step 2: Identify and evaluate historic properties

Step 3: Assess effects of the project on historic properties

Step 4: Resolve any adverse effects

Only RE or HUD staff may initiate the Section 106 consultation process. Partner entities may gather information, including from SHPO records, identify and evaluate historic properties, and make initial assessments of effects of the project on properties listed in or eligible for the National Register of Historic Place. Partners should then provide their RE or HUD with all of their analysis and documentation so that they may initiate consultation.

Step 1 - Initiate Consultation

The following parties are entitled to participate in Section 106 reviews: Advisory Council on Historic Preservation; State Historic Preservation Officers (SHPOs); federally recognized Indian tribes/Tribal Historic Preservation Officers (THPOs); Native Hawaiian Organizations (NHOs); local governments; and project grantees. The general public and individuals and organizations with a demonstrated interest in a project may participate as consulting parties at the discretion of the RE or HUD official. Participation varies with the nature and scope of a project. Refer to HUD's website for guidance on consultation, including the required timeframes for response. Consultation should begin early to enable full consideration of preservation options.

Use the When To Consult With Tribes checklist within Notice CPD-12-006: Process for Tribal Consultation to determine if the RE or HUD should invite tribes to consult on a particular project. Use the Tribal Directory Assessment Tool (TDAT) to identify tribes that may have an interest in the area where the project is located. Note that only HUD or the RE may initiate consultation with Tribes. Partner entities may prepare a draft letter for the RE or HUD to use to initiate consultation with tribes, but may not send the letter themselves.

List all organizations and individuals that you believe may have an interest in the project here: State Historic Preservation Office

→ Continue to Step 2.

Step 2 - Identify and Evaluate Historic Properties

Provide a preliminary definition of the Area of Potential Effect (APE), either by entering the address(es) or providing a map depicting the APE. Attach an additional page if necessary.

1800 E. La Veta Avenue Orange, CA 92866

Gather information about known historic properties in the APE. Historic buildings, districts and archeological sites may have been identified in local, state, and national surveys and registers, local historic districts, municipal plans, town and county histories, and local history websites. If not already listed on the National Register of Historic Places, identified properties are then evaluated to see if they are eligible for the National Register. Refer to HUD's website for guidance on identifying and evaluating historic properties.

In the space below, list historic properties identified and evaluated in the APE.

Every historic property that may be affected by the project should be listed. For each historic property or district, include the National Register status, whether the SHPO has concurred with the finding, and whether information on the site is sensitive. Attach an additional page if necessary.

Click here to enter text.

Provide the documentation (survey forms, Register nominations, concurrence(s) and/or objection(s), notes, and photos) that justify your National Register Status determination.

Was a survey of historic buildings and/or archeological sites done as part of the project?

If the APE contains previously unsurveyed buildings or structures over 50 years old, or there is a likely presence of previously unsurveyed archeological sites, a survey may be necessary. For Archeological surveys, refer to HP Fact Sheet #6, <u>Guidance on Archeological Investigations in HUD Projects</u>.

Click here to enter text.
\square No \rightarrow Continue to Step 3.
Step 3 - Assess Effects of the Project on Historic Properties
Only properties that are listed on or eligible for the National Register of Historic Places receive furthe consideration under Section 106. Assess the effect(s) of the project by applying the Criteria of Adverse Effect. (36 CFR 800.5) Consider direct and indirect effects as applicable as per HUD guidance.
Choose one of the findings below to recommend to the RE or HUD. Please note: this is a recommendation only. It is not the official finding, which will be made by the RE o HUD, but only your suggestion as a Partner entity.
☑ No Historic Properties Affected
Document reason for finding:
⋈ No historic properties present.
☐ Historic properties present, but project will have no effect upon them.
□ <u>No Adverse Effect</u>
Document reason for finding and provide any comments below.
Comments may include recommendations for mitigation, monitoring, a plan for unanticipated discoveries, etc.

☐ <u>Adverse Effect</u>

Document reason for finding:

Copy and paste applicable Criteria into text box with summary and justification.

Criteria of Adverse Effect: 36 CFR 800.5

Click here to enter text.

Provide any comments below:

Comments may include recommendations for avoidance, minimization, and/or mitigation. Click here to enter text.

Remember to provide all documentation that justifies your National Register Status determination and recommendations along with this worksheet.

ERR No. 12. Noise (EA Level Reviews)

OMB No. 2506-0177 (exp. 2/28/2025)



1.

2.

3.

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

WASHINGTON, DC 20410-1000

This Worksheet was designed to be used by those "Partners" (including Public Housing Authorities, consultants, contractors, and nonprofits) who assist Responsible Entities and HUD in preparing environmental reviews, but legally cannot take full responsibilities for these reviews themselves. Responsible Entities and HUD should use the RE/HUD version of the Worksheet.

Noise (EA Level Reviews) – PARTNER

https://www.hudexchange.info/programs/environmental-review/noise-abatement-and-control

/www.nadexchange.imo/programs/environmental-review/noise-abatement-and-control
What activities does your project involve? Check all that apply:
New construction for residential use
NOTE: HUD assistance to new construction projects is generally prohibited if they are located in an Unacceptable zone, and HUD discourages assistance for new construction projects in Normally Unacceptable zones. See 24 CFR 51.101(a)(3) for further details. → Continue to Question 2.
☐ Rehabilitation of an existing residential property
NOTE: For major or substantial rehabilitation in Normally Unacceptable zones, HUD encourages mitigation to reduce levels to acceptable compliance standards. For major rehabilitation in Unacceptable zones, HUD strongly encourages mitigation to reduce levels to acceptable compliance standards. See 24 CFR 51 Subpart B for further details. → Continue to Question 2.
□ None of the above
→ If the RE/HUD agrees with this recommendation, the review is in compliance with this section. Continue to the Worksheet Summary below.
Complete the Preliminary Screening to identify potential noise generators in the vicinity
(1000' from a major road, 3000' from a railroad, or 15 miles from an airport).
Indicate the findings of the Preliminary Screening below:
☐ There are no noise generators found within the threshold distances above.
→ If the RE/HUD agrees with this recommendation, the review is in compliance with this
section. Continue to the Worksheet Summary below. Provide a map showing the location of the project relative to any noise generators.
☑ Noise generators were found within the threshold distances.
→ Continue to Question 3.
Complete the Noise Assessment Guidelines to quantify the noise exposure. Indicate the
findings of the Noise Assessment below:
\square Acceptable (65 decibels or less; the ceiling may be shifted to 70 decibels in circumstances described in §24 CFR 51.105(a))

Indicate noise level here: Click here to enter text.

→ If the RE/HUD agrees with this recommendation, the review is in compliance with this section. Continue to the Worksheet Summary below. Provide noise analysis, including noise level and data used to complete the analysis.

☑ Normally Unacceptable: (Above 65 decibels but not exceeding 75 decibels; the floor may be shifted to 70 decibels in circumstances described in 24 CFR 51.105(a))

Indicate noise level here:

→ Dudek completed a Technical Noise Memorandum for the proposed project in February 2024. The primary noise source in the project vicinity is motor vehicle traffic. The eastern façades of the proposed residential units would face the southbound lanes of the SR-55 freeway, while the southern façades face the SR-22 freeway. Both the eastern and the southern facades are separated from these two freeways by several rows of residential homes and an existing noise barrier (i.e., a soundwall) approximately 14 feet in height constructed at the Caltrans right-of-way (ROW). In addition, the northern façades of the proposed residential units face La Veta Avenue, and the western facades face South Tustin Street. The other nearby roads are minor "feeder" streets which would have a negligible contribution to the on-site noise environment.

The Federal highway Administration's (FHWA) Traffic Noise Model (TNM) version 2.5 (FWHA 2004) was used to run a more detailed noise analysis for the project site. Exposure from traffic noise would exceed the HUD exterior noise standard of 65dBA DNL by up to 6 dB at the façade of units closest to the SR-22 freeway and South Tustin Street, putting those units in HUD's "normally unacceptable" noise range. The noise levels at the other modeled building facade receivers on the project site, except for the northern façade of Building 1, also exceed the HUD exterior noise standard of 65 dBA DNL to varying degrees. At the modeled outdoor use areas, the modeled traffic noise levels would not exceed the HUD exterior noise standard.

If project is rehabilitation:

 \rightarrow Continue to Question 4. Provide noise analysis, including noise level and data used to complete the analysis.

If project is new construction: Is the project in a largely undeveloped area¹? ☑ No ☐ Yes → The project requires completion of an Environmental Impact Statement (EIS) pursuant to 51.104(b)(1)(i).

 \rightarrow Continue to Question 4. Provide noise analysis, including noise level and data used to complete the analysis.

A largely undeveloped area means the area within 2 miles of the project site is less than 50 percent developed with urban uses or does not have water and sewer capacity to serve the project.

Indicate noise level here: Click here to enter text.

If project is rehabilitation:

HUD strongly encourages conversion of noise-exposed sites to land uses compatible with high noise levels. Consider converting this property to a non-residential use compatible with high noise levels.

→ Continue to Question 4. Provide noise analysis, including noise level and data used to complete the analysis, and any other relevant information.

If project is new construction:

The project requires completion of an Environmental Impact Statement (EIS) pursuant to 51.104(b)(1)(i). Work with HUD or the RE to either complete an EIS or obtain a waiver signed by the appropriate authority.

- → Continue to Question 4.
- 4. HUD strongly encourages mitigation be used to eliminate adverse noise impacts. Work with the RE/HUD on the development of the mitigation measures that must be implemented to mitigate for the impact or effect, including the timeline for implementation.
 - ☑ Mitigation as follows will be implemented:

The proposed project would implement mitigation measures at the site to reduce indoor noise levels to within the HUD threshold of 45 dBA DNL. Mitigation would include providing residential units with a forced-air heating, ventilation, and air conditioning (HVAC) system in each unit that provides additional ventilation to keep the indoor air quality high, even with the windows closed. To ensure compliance with 24 CFR Part 51, Subpart B and that the HUD noise standard of 45 dBA DNL is not exceeded, the detailed architectural design plans (when these are prepared) would provide the following specification for upgraded windows: All windows and exterior doors in the east-facing residential units on floors 2-4 of Building 1 shall have a Sound Transmission Class (STC) rating of 30 or greater (MM-NOI-1); all windows and exterior doors in the south- and east-facing residential units on floors 2-4 of Building 2 shall have an STC rating of 30 or greater (MM-NOI-2); all windows and exterior doors in the west-facing residential units of floors 1-4 of Building 3 shall have an STC rating of 35 or greater (MM-NOI-3); and all windows and exterior doors in the north- and south-facing residential units on floors 1-4 of Building 3 shall have an STC rating of 30 or greater (MM-NOI-4).

Noise levels at the outdoor spaces of the proposed project site, including the central courtyard, community garden, entertainment courtyard, and dog park, are within HUD exterior noise thresholds and no mitigation is required.

\rightarrow Provide drawings, specifications, and other materials as needed to describe the project's noise
mitigation measures.
Continue to the Worksheet Summary.
☐ No mitigation is necessary.
Explain why mitigation will not be made here:
Click here to enter text.
→ Continue to the Worksheet Summary.

See attached Technical Noise Memorandum, Dudek, February 2024 (Attachment 14).

ERR No. 13. Sole Source Aquifers



U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

WASHINGTON, DC 20410-1000

This Worksheet was designed to be used by those "Partners" (including Public Housing Authorities, consultants, contractors, and nonprofits) who assist Responsible Entities and HUD in preparing environmental reviews, but legally cannot take full responsibilities for these reviews themselves. Responsible Entities and HUD should use the RE/HUD version of the Worksheet.

Sole Source Aquifers (CEST and EA)

General requirements	Legislation	Regulation				
The Safe Drinking Water Act of 1974	Safe Drinking Water	40 CFR Part 149				
protects drinking water systems	Act of 1974 (42 U.S.C.					
which are the sole or principal	201, 300f et seq., and					
drinking water source for an area and	21 U.S.C. 349)					
which, if contaminated, would create						
a significant hazard to public health.						
Reference						
https://www.hudexchange.info/environmental-review/sole-source-aquifers						

1. Does your project consist solely of acquisition, leasing, or rehabilitation of an existing building(s)?

\square Yes \rightarrow	Based on the response,	the	review	is in	compliance	with	this	section.	Continue	to	the
	Worksheet Summary bel	ow.									

 \boxtimes No \rightarrow Continue to Question 2.

2. Is the project located on a sole source aquifer (SSA)¹?

\boxtimes No \rightarrow	Based on the response, the review is in compliance with this section. Continue to the
	Worksheet Summary below. Provide documentation used to make your determination, such
	as a map of your project (or jurisdiction, if appropriate) in relation to the nearest SSA and its
	source area.

 \square Yes \rightarrow Continue to Question 3.

3. Does your region have a memorandum of understanding (MOU) or other working agreement with EPA for HUD projects impacting a sole source aquifer?


Contact your Field or Regional Environmental Officer or visit the HUD webpage at the link above to determine if an MOU or agreement exists in your area.

A sole source aquifer is defined as an aquifer that supplies at least 50 percent of the drinking water consumed in the area overlying the aquifer. This includes streamflow source areas, which are upstream areas of losing streams that flow into the recharge area.

	□Yes →	Provide the MOU or agreement as part of your supporting documentation. Continue to Question 4.				
	□No→	Continue to Question 5.				
4.	Does your ☐Yes →	MOU or working agreement exclude your project from further review? Based on the response, the review is in compliance with this section. Continue to the Worksheet Summary below. Provide documentation used to make your determination and document where your project fits within the MOU or agreement.				
	□No →	Continue to Question 5.				
5.	=	oposed project contaminate the aquifer and create a significant hazard to				
public health? Consult with your Regional EPA Office. Your consultation request should include detail information about your proposed project and its relationship to the aquifer and associat streamflow source area. EPA will also want to know about water, storm water and was water at the proposed project. Follow your MOU or working agreement or contact you Regional EPA office for specific information you may need to provide. EPA may requestional information if impacts to the aquifer are questionable after this information submitted for review.						
	□No →	Based on the response, the review is in compliance with this section. Continue to the Worksheet Summary below. Provide your correspondence with the EPA and all documents used to make your determination.				
	□Yes →	Work with EPA to develop mitigation measures. If mitigation measures are approved, attach correspondence with EPA and include the mitigation measures in your environmental review documents and project contracts. If EPA determines that the project continues to pose a significant risk to the aquifer, federal financial assistance must be denied. Continue to Question 6.				
6.	be approve	continue with the project, any threat must be mitigated, and all mitigation must ed by the EPA. Explain in detail the proposed measures that can be implemented for the impact or effect, including the timeline for implementation.				

→ Continue to the Worksheet Summary below. Provide documentation of the consultation (including the Managing Agency's concurrence) and any other documentation used to make your determination.

Worksheet Summary



ERR No. 14. Wetlands



U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

WASHINGTON, DC 20410-1000

This Worksheet was designed to be used by those "Partners" (including Public Housing Authorities, consultants, contractors, and nonprofits) who assist Responsible Entities and HUD in preparing environmental reviews, but legally cannot take full responsibilities for these reviews themselves. Responsible Entities and HUD should use the RE/HUD version of the Worksheet.

Wetlands (CEST and EA) - Partner

https://www.hudexchange.info/environmental-review/wetlands-protection

1.	Does this project involve new construction as defined in Executive Order 11990, expansion of a building's footprint, or ground disturbance? The term "new construction" includes draining, dredging, channelizing, filling, diking, impounding, and related activities and construction of any structures or facilities. □ No → If the RE/HUD agrees with this recommendation, the review is in compliance with this section. Continue to the Worksheet Summary below.
	\boxtimes Yes \rightarrow Continue to Question 2.
2.	Will the new construction or other ground disturbance impact a wetland as defined in E.O. 11990? ⊠ No → If the RE/HUD agrees with this recommendation, the review is in compliance with this section. Continue to the Worksheet Summary below. Provide a map or any other relevant documentation to explain your determination.
	\square Yes \rightarrow Work with HUD or the RE to assist with the 8-Step Process. Continue to Question 3.
3.	Does Section 55.12 state that the 8-Step Process is not required?
	 No, the 8-Step Process applies. This project will require mitigation and may require elevating structure or structures. See the link to the HUD Exchange above for information on HUD's elevation requirements. → Work with the RE/HUD to assist with the 8-Step Process. Continue to Worksheet Summary. 5-Step Process is applicable per 55.12(a). Provide the applicable citation at 24 CFR 55.12(a) here. Click here to enter text.
	→ Work with the RE/HUD to assist with the 5-Step Process. This project may require mitigation or alternations. Continue to Worksheet Summary.
	 □ 8-Step Process is inapplicable per 55.12(b). Provide the applicable citation at 24 CFR 55.12(b) here. Click here to enter text. → If the RE/HUD agrees with this recommendation, the review is in compliance with this section. Continue to Worksheet Summary.

☐ 8-Step Process is inapplicable per 55.12(c).	
Provide the applicable citation at 24 CFR 55.12(c) here.	
Click here to enter text.	

→ If the RE/HUD agrees with this recommendation, the review is in compliance with this section. Continue to Worksheet Summary.

Worksheet Summary

According to the National Wetlands Inventory map regulated by the U.S. Fish and Wildlife Service and accessible at https://www.fws.gov/program/national-wetlands-inventory/wetlands-mapper, there are no wetlands on the project site (see Attachment 16). The nearest wetland feature is Santiago Creek, a riverine feature located approximately 175 feet northwest of the project site. As a result, the proposed project is in compliance with Executive Order 11990.

ERR No. 15. Wild and Scenic Rivers



U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT WASHINGTON, DC 20410-1000

This Worksheet was designed to be used by those "Partners" (including Public Housing Authorities, consultants, contractors, and nonprofits) who assist Responsible Entities and HUD in preparing environmental reviews, but legally cannot take full responsibilities for these reviews themselves. Responsible Entities and HUD should use the RE/HUD version of the Worksheet.

Wild and Scenic Rivers (CEST and EA) – PARTNER

https://www.hudexchange.info/environmental-review/wild-and-scenic-rivers

1.	Is your project within proximity of a Wild and Scenic River, Study River, or Nationwide Rivers
	Inventory River?

 \boxtimes No \Rightarrow If the RE/HUD agrees with this recommendation, the review is in compliance with this section. Provide documentation used to make your determination.

 \square Yes \rightarrow Continue to Question 2.

2. Could the project do any of the following?

- Have a direct and adverse effect within Wild and Scenic River Boundaries,
- Invade the area or unreasonably diminish the river outside Wild and Scenic River Boundaries,
 or
- Have an adverse effect on the natural, cultural, and/or recreational values of a NRI segment.

Consult with the appropriate federal/state/local/tribal Managing Agency(s), pursuant to Section 7 of the Act, to determine if the proposed project may have an adverse effect on a Wild & Scenic River or a Study River and, if so, to determine the appropriate avoidance or mitigation measures.

Select one:

- ☐ The Managing Agency has concurred that the proposed project will not alter, directly, or indirectly, any of the characteristics that qualifies or potentially qualifies the river for inclusion in the NWSRS.
- → If the RE/HUD agrees with this recommendation, the review is in compliance with this section. Provide documentation of the consultation (including the Managing Agency's concurrence) and any other documentation used to make your determination.
- ☐ The Managing Agency was consulted and the proposed project may alter, directly, or indirectly, any of the characteristics that qualifies or potentially qualifies the river for inclusion in the NWSRS.
- → The RE/HUD must work with the Managing Agency to identify mitigation measures to mitigate the impact or effect of the project on the river.

Worksheet Summary

According to the EPA's NEPAssist mapping tool, the project site does not contain any rivers protected under the Wild and Scenic Rivers Act. The closest protected waterway is Bautista Creek, approximately

57.3 miles east of the project site. Therefore, the proposed project is in compliance with Executive Order 11990.

See Attachment 17.

ERR No. 16. Environmental Justice



U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

WASHINGTON, DC 20410-1000

This Worksheet was designed to be used by those "Partners" (including Public Housing Authorities, consultants, contractors, and nonprofits) who assist Responsible Entities and HUD in preparing environmental reviews, but legally cannot take full responsibilities for these reviews themselves. Responsible Entities and HUD should use the RE/HUD version of the Worksheet.

Environmental Justice (CEST and EA) – PARTNER

https://www.hudexchange.info/environmental-review/environmental-justice

HUD strongly encourages starting the Environmental Justice analysis only after all other laws and authorities, including Environmental Assessment factors if necessary, have been completed.

- 1. Were any adverse environmental impacts identified in any other compliance review portion of this project's total environmental review?
 - \boxtimes Yes \rightarrow Continue to Question 2.
 - □No → If the RE/HUD agrees with this recommendation, the review is in compliance with this section. Continue to the Worksheet Summary below.
- 2. Were these adverse environmental impacts disproportionately high for low-income and/or minority communities?

□Yes

Explain:

Click here to enter text.

→ The RE/HUD must work with the affected low-income or minority community to decide what mitigation actions, if any, will be taken. Provide any supporting documentation.

 $\boxtimes No$

Explain:

The project site currently occupied by the former campus of the Rehabilitation Institute of Southern California and associated parking and landscaped areas and does not possess any recognized environmental conditions (RECs) or hazardous materials. Though not considered RECs, asbestos-containing materials (ACMs) and lead-based paint (LBP) were identified throughout the existing building onsite. Prior to demolition of the existing building, ACMs and LBPs would be removed by licensed asbestos abatement contractors and certified lead trained personnel in accordance with all applicable federal, state, and local regulations. The noise study for the proposed project indicated that the project site would experience high noise levels due to high traffic volume along the State Route (SR)-55 and SR-22 freeways. However, implementation of mitigation measures would reduce adverse noise impacts at the project site to below HUD thresholds. No disproportionate impacts to low income and/or minority communities would occur as a result of impacts from noise. As a result, potential adverse impacts related to noise would be avoided or reduced for all residents during the operational phase. In addition, with the implementation of best management practices required for the control of fugitive dust, erosion, and storm water at construction sites, no disproportionate impacts to low income and/or

minority communities would occur as a result of impacts to air quality. As a result, potential adverse impacts would be avoided or reduced for all residents during the operational phase.

→ If the RE/HUD agrees with this recommendation, the review is in compliance with this section. Continue to the Worksheet Summary below.

Worksheet Summary


The proposed project would demolish the existing Rehabilitation Institute of Southern California campus, which is currently unoccupied, and construct a new affordable housing community with 166 units. The new housing development would be reserved for seniors aged 62+ and earning between 30-70% of the area mean income (AMI). Increasing affordable housing units for seniors supports the housing priorities detailed in the City's Housing Element. The proposed project, which is an infill site converting a commercial facility into multifamily housing, would not result in any disproportionately high or adverse impacts to minority or low-income populations.

Several studies have been conducted on the potential for environmental impacts related to the project. Some of these studies identified environmental concerns and mitigation measures:

- **Air Quality:** Construction activities such as grading may cause temporary adverse impacts to air quality from fugitive dust during construction of the residential community; however, with the implementation of air quality mitigation measures required for fugitive dust required by SCQAMD Rule 403 (see **MM-AIR-1**), impacts to air quality would be minimized or avoided. Therefore, no disproportionate impacts to low income and/or minority communities would occur as a result of air quality.
- Asbestos and Lead Paint: A Pre-Renovation Asbestos and Lead Assessment for the project site was completed by EFI Global in August 2020. The purpose of the assessment was to identify whether ACMs and/or LBPs were present so that they may be properly managed prior to demolition of the structure. ACMs and LBPs were identified in multiple areas throughout the existing building. All ACMs and LBPs were found to be in good condition at the time of the assessment. Materials found to contain asbestos and/or presumed to contain asbestos that could be impacted during demolition activities, by law, must first be abated and properly disposed of by a licensed asbestos abatement contractor prior to such work (MM-TOX-1). In addition, all lead-laden components identified would be demolished or abated by certified lead trained personnel in accordance with all applicable federal, state, and local regulations prior to demolition activities (MM-TOX-2). Therefore, no disproportionate impacts to low income and/or minority communities would occur as a result of ACMs or LBPs.
- Noise. Construction of the project would generate noise associated with the operation of heavy construction equipment and construction-related activities in the vicinity of the project site. This would result in temporary, intermittent increases in ambient noise levels which would fluctuate depending on the particular construction phase. Pursuant to Chapter 8.24, Noise Control, of the City's Code of Ordinances, noise associated with construction is exempt from the provisions of the noise ordinance, provided that activities take place between the hours of 7:00 a.m. and 8:00 p.m. on any day except for Sunday or a federal holiday. The project would not require nighttime construction or construction on weekends or holidays, and therefore construction noise would not be subject to the City's noise standards identified in Table 8.24.040.

A Technical Noise Memorandum for the proposed project prepared by Dudek in February 2024 determined that exposure from traffic generated by the SR-55 and SR-22 freeways were the primary noise sources for the development. Exposure from traffic noise would exceed the HUD exterior noise standard of 65 dBA DNL by up to 6 dB at the façade of units closest to the SR-22 freeway and South Tustin Street, putting those units in HUD's "normally unacceptable" noise range. The noise levels at the other modeled building façade receivers on the project site, except for the northern façade of Building 1, also would exceed the HUD exterior noise standard of 65 dBA DNL to varying degrees. To reduce noise levels to within HUD thresholds, all residential units would be equipped with a forced air HVAC unit that allows for a "windows closed" condition (i.e., windows do not need to be left open for ventilation). In addition, all windows and exterior doors in the east-facing residential units on floors 2-4 of Building 1 shall have a Sound Transmission Class (STC) rating of 30 or greater (MM-NOI-1); all windows and exterior doors in the south- and east-facing residential units on floors 2-4 of Building 2 shall have an STC ratting of 30 or greater (MM-NOI-2); all windows and exterior doors in the west-facing residential units of floors 1-4 of Building 3 shall have an STC rating of 35 or greater (MM-NOI-3); and all windows and exterior doors in the north- and south-facing residential units on floors 1-4 of Building 3 shall have an STC rating of 30 or greater (MM-NOI-4). Therefore, no disproportionate impacts to low income and/or minority communities would occur as a result of noise.


Figure 1. Project Location



SOURCE: Bing Imagery 2021

FIGURE 1
Project Location

Figure 2. Site Vicinity



SOURCE: AEI, 2024

Attachment 1. Architectural Concept Designs

LEFT ELEVATION 2



FRONT ELEVATION 1

MATERIAL / COLOR LEGEND

VINYL WINDOWS 3 METAL RAILING

В SW 7076 CYBERSPACE C SW 7647 CRUSHED ICE

4 METAL AWINING

2

5 1" METAL SCREED CHANNEL


6 ALUMINUM STOREFRONT

EXTERIOR WALL MOUNTED LIGHT FIXTURE

8 BUILDING NUMBER SIGNAGE

FOR FURTHER INFORMATION NOT SHOWN HERE, REFER TO SHEET A4.0 FOR THE COLOR AND MATERIAL BOARD

KEY MAP



THE ORION

ORANGE, CA

USA PROPERTIES FUND INC.
3200 DOUGLAS BLVD. SUITE 200, ROSEVILLE, CA 95661
(916) 773-6060

RIVERSIDE CHARITABLE CORPORATION
14131 YORBA ST. TUSTIN, CA 92780
(714) 803-7200

AO ARCHITECTS 144 NORTH ORANGE ST., ORANGE, CA 92866 (714) 639-9860

BUILDING 1 ELEVATIONS

DATE: 12-27-21

JOB NO.: 2020-009



A2.2



RIGHT ELEVATION 4



REAR ELEVATION 3

MATERIAL / COLOR LEGEND

В SW 7076 CYBERSPACE

VINYL WINDOWS METAL RAILING

C SW 7647 CRUSHED ICE

4 METAL AWINING

2

3

5 1" METAL SCREED CHANNEL

6 ALUMINUM STOREFRONT

EXTERIOR WALL MOUNTED LIGHT FIXTURE

8 BUILDING NUMBER SIGNAGE

FOR FURTHER INFORMATION NOT SHOWN HERE, REFER TO SHEET A4.0 FOR THE COLOR AND MATERIAL BOARD

3

E. FAIRWAY DR.

KEY MAP

NORTH

DATE: 12-27-21

JOB NO.: 2020-009

BUILDING 1 ELEVATIONS

AO ARCHITECTS 144 NORTH ORANGE ST., ORANGE, CA 92866 (714) 639-9860

A2.3

THE ORION

ORANGE, CA

LEFT ELEVATION 2



FRONT ELEVATION 1

MATERIAL / COLOR LEGEND

VINYL WINDOWS METAL RAILING

В SW 7076 CYBERSPACE C SW 7647 CRUSHED ICE

4 METAL AWINING

2

3

5 1" METAL SCREED CHANNEL


6 ALUMINUM STOREFRONT

EXTERIOR WALL MOUNTED LIGHT FIXTURE

8 BUILDING NUMBER SIGNAGE

FOR FURTHER INFORMATION NOT SHOWN HERE, REFER TO SHEET A4.0 FOR THE COLOR AND MATERIAL BOARD

KEY MAP



THE ORION

ORANGE, CA

RIVERSIDE CHARITABLE CORPORATION

AO ARCHITECTS 144 NORTH ORANGE ST., ORANGE, CA 92866 (714) 639-9860

BUILDING 2 ELEVATIONS

DATE: 12-27-21

JOB NO.: 2020-009

A2.6

RIGHT ELEVATION 4



REAR ELEVATION 3

MATERIAL / COLOR LEGEND

VINYL WINDOWS

В SW 7076 CYBERSPACE

C SW 7647 CRUSHED ICE

3 METAL RAILING 4 METAL AWINING

2

5 1" METAL SCREED CHANNEL


6 ALUMINUM STOREFRONT

EXTERIOR WALL MOUNTED LIGHT FIXTURE

8 BUILDING NUMBER SIGNAGE

FOR FURTHER INFORMATION NOT SHOWN HERE, REFER TO SHEET A4.0 FOR THE COLOR AND MATERIAL BOARD

KEY MAP



THE ORION

ORANGE, CA

USA PROPERTIES FUND INC.
3200 DOUGLAS BLVD. SUITE 200, ROSEVILLE, CA 95661
(916) 773-6060

RIVERSIDE CHARITABLE CORPORATION
14131 YORBA ST. TUSTIN, CA 92780
(714) 803-7200

DATE: 12-27-21 JOB NO.: 2020-009 **AO ARCHITECTS** 144 NORTH ORANGE ST., ORANGE, CA 92866

BUILDING 2 ELEVATIONS

(714) 639-9860

A2.7



LEFT ELEVATION 2



FRONT ELEVATION 1

MATERIAL / COLOR LEGEND

VINYL WINDOWS

В SW 7076 CYBERSPACE

SW 7647 CRUSHED ICE

3 METAL RAILING 4 METAL AWINING

2

5 1" METAL SCREED CHANNEL


6 ALUMINUM STOREFRONT

EXTERIOR WALL MOUNTED LIGHT FIXTURE

8 BUILDING NUMBER SIGNAGE

FOR FURTHER INFORMATION NOT SHOWN HERE, REFER TO SHEET A4.0 FOR THE COLOR AND MATERIAL BOARD

KEY MAP



THE ORION

ORANGE, CA

USA PROPERTIES FUND INC.
3200 DOUGLAS BLVD. SUITE 200, ROSEVILLE, CA 95661
(916) 773-6060

RIVERSIDE CHARITABLE CORPORATION
14131 YORBA ST. TUSTIN, CA 92780
(714) 803-7200

AO ARCHITECTS 144 NORTH ORANGE ST., ORANGE, CA 92866 (714) 639-9860

BUILDING 3 ELEVATIONS

DATE: 12-27-21

JOB NO.: 2020-009

A2.10



RIGHT ELEVATION 4



REAR ELEVATION 3

MATERIAL / COLOR LEGEND

2 VINYL WINDOWS 3 METAL RAILING

В SW 7076 CYBERSPACE C SW 7647 CRUSHED ICE

4 METAL AWINING

5 1" METAL SCREED CHANNEL


6 ALUMINUM STOREFRONT

EXTERIOR WALL MOUNTED LIGHT FIXTURE

8 BUILDING NUMBER SIGNAGE

FOR FURTHER INFORMATION NOT SHOWN HERE, REFER TO SHEET A4.0 FOR THE COLOR AND MATERIAL BOARD

KEY MAP





BUILDING 3 ELEVATIONS


DATE: 12-27-21 JOB NO.: 2020-009


A2.11











UNIT PLANS

A3.0

DATE: 12-27-21 JOB NO.: 2020-009




THE ORION

ORANGE, CA

AO ARCHITECTS 144 NORTH ORANGE ST., ORANGE, CA 92866 (714) 639-9860





BUILDING 1 COMPOSITE PLAN

A2.0


DATE: 12-27-21 JOB NO.: 2020-009


USA PROPERTIES FUND INC.
3200 DOUGLAS BLVD. SUITE 200, ROSEVILLE, CA 95661
(916) 773-6060





09 RCC ORION AFFORDABLE ORANGE\03 DESIGN\SCHEM\AUTOCAD\20-009_A2.0 - A2.1 BUILE





BUILDING 1 COMPOSITE PLAN

A2.1

THE ORION

ORANGE, CA

DATE: 12-27-21 JOB NO.: 2020-009


(714) 639-9860

AO ARCHITECTS

Architecture. Design. Relationships. 144 NORTH ORANGE ST., ORANGE, CA 92866

LEVEL 2





BUILDING 2 COMPOSITE PLAN

A2.4

THE ORION

(916) 773-6060


USA PROPERTIES FUND INC.


DATE: 12-27-21





JOB NO.: 2020-009 AO ARCHITECTS Architecture. Design. Relationships. (714) 639-9860







BUILDING 2 COMPOSITE PLAN

A2.5

THE ORION


(916) 773-6060

ORANGE, CA

DATE: 12-27-21 JOB NO.: 2020-009

Architecture. Design. Relationships. (714) 639-9860





BUILDING 3 COMPOSITE PLAN

A2.8


Architecture. Design. Relationships.


DATE: 12-27-21 JOB NO.: 2020-009

AO ARCHITECTS 144 NORTH ORANGE ST., ORANGE, CA 92866 (714) 639-9860

THE ORION

ORANGE, CA






BUILDING 3 COMPOSITE PLAN

A2.9

THE ORION

ORANGE, CA



DATE: 12-27-21 JOB NO.: 2020-009

(714) 639-9860

AO ARCHITECTS 144 NORTH ORANGE ST., ORANGE, CA 92866





TREE LEGEND

KEE LE	GEND					
<u>MBOL</u>	BOTANICAL NAME	COMMON NAME	W/H	SIZE	QTY. W	UCOL
	Tristania conferta	Brisbane Box	8' x 20'	24"B	30	M
	Magnolia grandiflora 'Little Gem'	Southern Magnolia	8' x 15'	24"B	4	M
	Bauhinia purpurea	Orchid Tree	15' x 18'	36"B	1	M
	Arbutus 'Marina' Lagerstroemia i. "Watermelon"	Marina Strawberry Tree Crape Myrtle (Red)	10' x 12' 10' x 12'	24"B 24"B	17	L M
	Platanus acerifolia Ulmus parvifolia	London Plane Tree Chinese Elm	20' x 25' 25' x 30'	36"B 36"B	16	M M
	Magnolia grandiflora 'D.D. Blanchard'	D.D. Blanchard Magnolia	10' x 25'	24"B	4	M
	Pinus canariensis	Canary Island Pine	15' x 30'	24"B	1	L
	Melaleuca quinquenervia	Paperbark Tea Tree	15' x 25'	24"B	4	L
English States	Chitalpa tashkentensis 'Pink Dawn'	Pink Dawn Chitalpa	8' x 15'	24"B	3	L
	Strelitzia nicolai	Giant Bird Of Paradise	5' x 8'	15 Gal.	14	M
	Cinnamomum camphora	Camphor Tree	30' x 60'	36"B	3	M
	Citrus x sinensis	Orange Tree	6' x 10'	15 Gal.	11	M
	Pyrus calleryana	Ornamental Pear	10' x 15'	24"B	2	M
	Koelreuteria paniculata	Goldenrain Tree	15' x 25'	24"B	5	M
PALMS	<u>S</u>					
	Chamaerops humilis	Mediterranean Fan Palm		24"B	1	L
	Phoenix Dactylifera	Date Palm		18' BTH	5	L
The state of the s	Washingtonia robusta	Mexican Fan Palm		18' BTH	10	L

SHRUB LEGEND

<u>SYMBOL</u>	BOTANICAL NAME	COMMON NAME	$\underline{\text{W/H}}$	SIZE	QTY. W	<u>UCOLS</u>
	Agave 'Blue Flame'	Blue Flame Agave	3' x 3'	5 G	100	\mathbf{L}
	Agave attenuata	Foxtail Agave	3' x 3'	5 G	90	L
	Agave desmettiana 'Variegata'	Variegated Dwarf Century Plant	3' x 3'	5 G	70	\mathbf{L}
	Arbutus unedo 'Elfin King'	Elfin King Strawberry King	3' x 3'	5 G	26	\mathbf{L}
	Buxus microphylla japonica	Japanese Boxwood	2' x 2'	5 G	120	M
	Callistemon viminalis 'LittleJohn'	Dwarf Bottlebrush	2' x 2'	5 G	80	M
	Carex tumulicola	Foothill Sedge	18" x 18"	1 G	100	L
1000	Chondropetalum tectorum	Cape Rush	3' x 3'	5 G	150	\mathbf{M}
	Dianella revoluta 'DR5000'	Little Rev Flax Lily	18" x 18"	1 G	300	M
	Dianella tasmanica 'Silver Streak'	Silver Streak Flax Lily	2' x 3'	5 G	300	\mathbf{M}
	Ilex crenata 'Sky Pencil'	Sky Pencil Ilex	2' x 4'	5 G	18	L
	Ilex vomitoria 'Stokes'	Stokes Holly	2' x 2'	1 G	20	L
	Lantana hybrids 'New Gold'	New Gold Lantana	2' x 4'	5 G	5	L
	Ligustrum japonicum 'Texanum'	Wax Leaf Privet	3' x 4'	5 G	500	\mathbf{M}
	Lomandra longifolia 'LM300'	Breeze Dwarf Mat Rush	2' x 2'	5 G	30	\mathbf{M}
	Moraea bicolor	Fortnight Lily	2' x 4'	5 G	90	M
	Muhlenbergia capillaris 'Regal Mist'	Regal Mist Muhly	3' x 3'	5 G	270	M
	Olea europaea 'Montra'	Little Ollie Dwarf Olive	3' x 2'	5 G	500	\mathbf{L}
	Pennisetum 'Fairy Tails'	Fairy Tails Fountain Grass	2' x 2'	1 G	180	\mathbf{M}
	Pittosporum tobira	Tobira	3' x 3'	5 G	111	\mathbf{M}
	Podocarpus elongatus 'Monmal'	Icee Blue Yellow-Wood	2' x 6'	5 G	38	\mathbf{M}
	Rhaphiolepis indica 'Clara'	Indian Hawthorne	3' x 3'	5 G	500	\mathbf{M}
	Rosa 'Flower Carpet var. Noatraum'	Pink Carpet Rose	4' x 2'	5 G	20	M
	Rosa f. 'Ice Berg'	White Shrub Rose	3' x 3'	5 G	60	M
	Rosmarinus officinalis 'Huntington Carpet'		3' x 18"	1 G	4	\mathbf{L}
		Bird-of-Paradise	3' x 3'	5 G	300	\mathbf{M}
	Stipa tenuissima	Mexican Feather Grass	2' x 2'	1 G	90	M
	Yucca filamentosa 'Golden Sword'	Golden Sword Yucca	3' x 4'	5 G	8	L


EXISTING TREE LEGEND TO REMAIN

<u>TAG</u>	BOTANICAL NAME	COMMON NAME
T-5	Pinus pinea	Italian Stone Pine
T-35	Melaleuca quinquenervia	Paperbark
T-47	Pinus pinea	Italian Stone Pine
T-69	Eucalyptus sideroxylon	Red Ironbark
T-84	Pinus halepensis	Aleppo Pine
T-85	Pinus halepensis	Aleppo Pine
T-86	Pinus halenensis	Alenno Pine

*Spacing distance shown is intended to be maiximum spacing for each plant. Plants may be located closer together if design criteria requires it.

- Landscape/Irrigation plans shall comply with the City of Orange Landscape Standards and Specifications and Water Efficient Landscape Guidelines.
- A fully automated irrigation system shall be provided.
 All parking visible from the streets, including front and side yard areas is to be screened with 5 gallon minimum shrubs at 3 ft. on center.

- Shrub areas at the foundation lines of all building and 4 ft. minimum width planters at all elevations seen from the street, shall be planted with 5 gallon materials at 3 ft. on center.
 All shrubs material in parking areas shall be 30" ht. Max. For ease of visibility into site for



THE ORION

ORANGE, CA






DATE: 02-14-22

JOB NO.: 20-023






THE ORION


ORANGE, CA

DATE: 02-14-22 JOB NO.: 20-023

Design. Relationships.



LEGEND





SITE PLAN - PROPOSED


DATE: 02-17-22 JOB NO.: 2020-009


THE ORION

ORANGE, CA









UNIT PLANS

DATE: 12-27-21 JOB NO.: 2020-009


A3.0

ORANGE, CA

AO ARCHITECTS 144 NORTH ORANGE ST., ORANGE, CA 92866 (714) 639-9860

THE ORION

LEGEND



SITE PLAN - PROPOSED

A1.4


DATE: 02-17-22 JOB NO.: 2020-009





THE ORION

ORANGE, CA


Attachment 2. Airports







Attachment 3. Coastal Barrier Resources



Attachment 4. FEMA FIRM Map


National Flood Hazard Layer FIRMette





Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT



This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards

point selected by the user and does not represent

an authoritative property location.

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on 12/21/2023 at 2:26 PM and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.

Attachment 5. CalEEMod Air Quality Model

Orion Apartments HUD Project Detailed Report

Table of Contents

- 1. Basic Project Information
 - 1.1. Basic Project Information
 - 1.2. Land Use Types
 - 1.3. User-Selected Emission Reduction Measures by Emissions Sector
- 2. Emissions Summary
 - 2.1. Construction Emissions Compared Against Thresholds
 - 2.2. Construction Emissions by Year, Unmitigated
 - 2.3. Construction Emissions by Year, Mitigated
 - 2.4. Operations Emissions Compared Against Thresholds
 - 2.5. Operations Emissions by Sector, Unmitigated
 - 2.6. Operations Emissions by Sector, Mitigated
- 3. Construction Emissions Details
 - 3.1. Demolition (2024) Unmitigated
 - 3.2. Demolition (2024) Mitigated

- 3.3. Site Preparation (2024) Unmitigated
- 3.4. Site Preparation (2024) Mitigated
- 3.5. Grading (2024) Unmitigated
- 3.6. Grading (2024) Mitigated
- 3.7. Building Construction (2024) Unmitigated
- 3.8. Building Construction (2024) Mitigated
- 3.9. Building Construction (2025) Unmitigated
- 3.10. Building Construction (2025) Mitigated
- 3.11. Paving (2025) Unmitigated
- 3.12. Paving (2025) Mitigated
- 3.13. Architectural Coating (2025) Unmitigated
- 3.14. Architectural Coating (2025) Mitigated
- 4. Operations Emissions Details
 - 4.1. Mobile Emissions by Land Use
 - 4.1.1. Unmitigated
 - 4.1.2. Mitigated
 - 4.2. Energy

- 4.2.1. Electricity Emissions By Land Use Unmitigated
- 4.2.2. Electricity Emissions By Land Use Mitigated
- 4.2.3. Natural Gas Emissions By Land Use Unmitigated
- 4.2.4. Natural Gas Emissions By Land Use Mitigated
- 4.3. Area Emissions by Source
 - 4.3.1. Unmitigated
 - 4.3.2. Mitigated
- 4.4. Water Emissions by Land Use
 - 4.4.1. Unmitigated
 - 4.4.2. Mitigated
- 4.5. Waste Emissions by Land Use
 - 4.5.1. Unmitigated
 - 4.5.2. Mitigated
- 4.6. Refrigerant Emissions by Land Use
 - 4.6.1. Unmitigated
 - 4.6.2. Mitigated
- 4.7. Offroad Emissions By Equipment Type

- 4.7.1. Unmitigated
- 4.7.2. Mitigated
- 4.8. Stationary Emissions By Equipment Type
 - 4.8.1. Unmitigated
 - 4.8.2. Mitigated
- 4.9. User Defined Emissions By Equipment Type
 - 4.9.1. Unmitigated
 - 4.9.2. Mitigated
- 4.10. Soil Carbon Accumulation By Vegetation Type
 - 4.10.1. Soil Carbon Accumulation By Vegetation Type Unmitigated
 - 4.10.2. Above and Belowground Carbon Accumulation by Land Use Type Unmitigated
 - 4.10.3. Avoided and Sequestered Emissions by Species Unmitigated
 - 4.10.4. Soil Carbon Accumulation By Vegetation Type Mitigated
 - 4.10.5. Above and Belowground Carbon Accumulation by Land Use Type Mitigated
 - 4.10.6. Avoided and Sequestered Emissions by Species Mitigated
- 5. Activity Data
 - 5.1. Construction Schedule

- 5.2. Off-Road Equipment
 - 5.2.1. Unmitigated
 - 5.2.2. Mitigated
- 5.3. Construction Vehicles
 - 5.3.1. Unmitigated
 - 5.3.2. Mitigated
- 5.4. Vehicles
 - 5.4.1. Construction Vehicle Control Strategies
- 5.5. Architectural Coatings
- 5.6. Dust Mitigation
 - 5.6.1. Construction Earthmoving Activities
 - 5.6.2. Construction Earthmoving Control Strategies
- 5.7. Construction Paving
- 5.8. Construction Electricity Consumption and Emissions Factors
- 5.9. Operational Mobile Sources
 - 5.9.1. Unmitigated
 - 5.9.2. Mitigated

5.10. Operational Area Sources

5.10.1. Hearths

5.10.1.1. Unmitigated

5.10.1.2. Mitigated

5.10.2. Architectural Coatings

5.10.3. Landscape Equipment

5.10.4. Landscape Equipment - Mitigated

5.11. Operational Energy Consumption

5.11.1. Unmitigated

5.11.2. Mitigated

5.12. Operational Water and Wastewater Consumption

5.12.1. Unmitigated

5.12.2. Mitigated

5.13. Operational Waste Generation

5.13.1. Unmitigated

5.13.2. Mitigated

5.14. Operational Refrigeration and Air Conditioning Equipment

- 5.14.1. Unmitigated
- 5.14.2. Mitigated
- 5.15. Operational Off-Road Equipment
 - 5.15.1. Unmitigated
 - 5.15.2. Mitigated
- 5.16. Stationary Sources
 - 5.16.1. Emergency Generators and Fire Pumps
 - 5.16.2. Process Boilers
- 5.17. User Defined
- 5.18. Vegetation
 - 5.18.1. Land Use Change
 - 5.18.1.1. Unmitigated
 - 5.18.1.2. Mitigated
 - 5.18.1. Biomass Cover Type
 - 5.18.1.1. Unmitigated
 - 5.18.1.2. Mitigated
 - 5.18.2. Sequestration

- 5.18.2.1. Unmitigated
- 5.18.2.2. Mitigated
- 6. Climate Risk Detailed Report
 - 6.1. Climate Risk Summary
 - 6.2. Initial Climate Risk Scores
 - 6.3. Adjusted Climate Risk Scores
 - 6.4. Climate Risk Reduction Measures
- 7. Health and Equity Details
 - 7.1. CalEnviroScreen 4.0 Scores
 - 7.2. Healthy Places Index Scores
 - 7.3. Overall Health & Equity Scores
 - 7.4. Health & Equity Measures
 - 7.5. Evaluation Scorecard
 - 7.6. Health & Equity Custom Measures
- 8. User Changes to Default Data

1. Basic Project Information

1.1. Basic Project Information

Data Field	Value
Project Name	Orion Apartments HUD Project
Construction Start Date	8/1/2024
Operational Year	2026
Lead Agency	_
Land Use Scale	Project/site
Analysis Level for Defaults	County
Windspeed (m/s)	2.50
Precipitation (days)	2.20
Location	1800 E La Veta Ave, Orange, CA 92866, USA
County	Orange
City	Orange
Air District	South Coast AQMD
Air Basin	South Coast
TAZ	5744
EDFZ	7
Electric Utility	Southern California Edison
Gas Utility	Southern California Gas
App Version	2022.1.1.21

1.2. Land Use Types

Land Use Subtype	Size	Unit	Lot Acreage	Building Area (sq ft)	Landscape Area (sq	Special Landscape	Population	Description
					ft)	Area (sq ft)		

Apartments Mid Rise	166	Dwelling Unit	2.30	145,716	17,914	_	495	_
Parking Lot	172	Space	1.55	0.00	0.00	_	_	_

1.3. User-Selected Emission Reduction Measures by Emissions Sector

Sector	#	Measure Title
Transportation	T-1	Increase Residential Density
Transportation	T-4	Integrate A ordable and Below Market Rate Housing
Energy	E-2	Require Energy Efficient Appliances
Water	W-4	Require Low-Flow Water Fixtures

2. Emissions Summary

2.1. Construction Emissions Compared Against Thresholds

Un/Mit.	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Unmit.	4.42	51.9	36.1	34.0	0.07	1.60	8.97	10.1	1.47	4.00	5.47	_	9,602	9,602	0.62	0.98	13.3	9,924
Daily, Winter (Max)	_		_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Unmit.	1.99	1.66	12.4	19.7	0.03	0.51	1.72	2.23	0.46	0.41	0.87	_	4,528	4,528	0.15	0.16	0.21	4,580
Average Daily (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Unmit.	0.86	3.28	5.32	8.92	0.01	0.21	1.02	1.22	0.19	0.25	0.44	_	2,033	2,033	0.07	0.09	1.45	2,057
Annual (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

		0.40	0.00	0.07	4.00	. 0 005	0.04	0.40	0.00	0.00	0.05	0.00		227	227	0.04	0.04	0.04	244
U	nmit.	0.16	0.60	0.97	1.63	< 0.005	0.04	0.19	0.22	0.03	0.05	0.08	_	337	337	0.01	0.01	0.24	341

2.2. Construction Emissions by Year, Unmitigated

Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

Year	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily - Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
2024	4.42	3.71	36.1	34.0	0.07	1.60	8.97	10.1	1.47	4.00	5.47	_	9,602	9,602	0.62	0.98	13.3	9,924
2025	1.87	51.9	11.5	20.1	0.03	0.44	1.72	2.16	0.40	0.41	0.81	_	4,565	4,565	0.15	0.16	7.60	4,622
Daily - Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
2024	1.99	1.66	12.4	19.7	0.03	0.51	1.72	2.23	0.46	0.41	0.87	_	4,528	4,528	0.15	0.16	0.21	4,580
2025	1.87	1.57	11.5	19.2	0.03	0.44	1.72	2.16	0.40	0.41	0.81	_	4,488	4,488	0.15	0.16	0.20	4,538
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
2024	0.72	0.58	5.21	6.38	0.01	0.21	1.02	1.22	0.19	0.25	0.44	_	1,599	1,599	0.07	0.09	1.05	1,628
2025	0.86	3.28	5.32	8.92	0.01	0.20	0.77	0.97	0.19	0.18	0.37	_	2,033	2,033	0.07	0.07	1.45	2,057
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
2024	0.13	0.11	0.95	1.16	< 0.005	0.04	0.19	0.22	0.03	0.05	0.08	_	265	265	0.01	0.01	0.17	270
2025	0.16	0.60	0.97	1.63	< 0.005	0.04	0.14	0.18	0.03	0.03	0.07	_	337	337	0.01	0.01	0.24	341

2.3. Construction Emissions by Year, Mitigated

Year	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily -	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Summer																		
(Max)																		

2024	4.42	3.71	36.1	34.0	0.07	1.60	8.97	10.1	1.47	4.00	5.47		9,602	9,602	0.62	0.98	13.3	9,924
2025	1.87	51.9	11.5	20.1	0.03	0.44	1.72	2.16	0.40	0.41	0.81	_	4,565	4,565	0.15	0.16	7.60	4,622
Daily - Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
2024	1.99	1.66	12.4	19.7	0.03	0.51	1.72	2.23	0.46	0.41	0.87	_	4,528	4,528	0.15	0.16	0.21	4,580
2025	1.87	1.57	11.5	19.2	0.03	0.44	1.72	2.16	0.40	0.41	0.81	_	4,488	4,488	0.15	0.16	0.20	4,538
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
2024	0.72	0.58	5.21	6.38	0.01	0.21	1.02	1.22	0.19	0.25	0.44	_	1,599	1,599	0.07	0.09	1.05	1,628
2025	0.86	3.28	5.32	8.92	0.01	0.20	0.77	0.97	0.19	0.18	0.37	_	2,033	2,033	0.07	0.07	1.45	2,057
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
2024	0.13	0.11	0.95	1.16	< 0.005	0.04	0.19	0.22	0.03	0.05	0.08	_	265	265	0.01	0.01	0.17	270
2025	0.16	0.60	0.97	1.63	< 0.005	0.04	0.14	0.18	0.03	0.03	0.07	_	337	337	0.01	0.01	0.24	341

2.4. Operations Emissions Compared Against Thresholds

Un/Mit.	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Unmit.	4.00	7.04	2.55	32.4	0.06	0.08	5.52	5.60	0.07	1.40	1.48	78.1	7,244	7,322	8.23	0.27	21.7	7,629
Mit.	2.48	5.65	1.56	21.1	0.03	0.06	2.78	2.84	0.06	0.71	0.76	77.0	4,252	4,329	7.98	0.15	11.4	4,584
% Reduced	38%	20%	39%	35%	47%	23%	50%	49%	22%	50%	48%	1%	41%	41%	3%	44%	47%	40%
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Unmit.	3.09	6.18	2.63	21.5	0.06	0.07	5.52	5.59	0.07	1.40	1.47	78.1	6,991	7,069	8.24	0.28	1.58	7,359
Mit.	1.59	4.80	1.56	10.9	0.03	0.06	2.78	2.84	0.05	0.71	0.76	77.0	4,111	4,188	7.98	0.16	1.31	4,436

% Reduced	49%	22%	41%	49%	47%	24%	50%	49%	23%	50%	48%	1%	41%	41%	3%	44%	17%	40%
Average Daily (Max)	-	_	_	_	_	_	_	_	_	_	_	_	_	-	_	_	_	-
Unmit.	3.53	6.60	2.60	27.3	0.06	0.07	5.24	5.31	0.07	1.33	1.40	78.1	6,784	6,862	8.22	0.27	9.52	7,156
Mit.	2.10	5.30	1.57	17.1	0.03	0.06	2.64	2.70	0.06	0.67	0.73	77.0	4,016	4,093	7.97	0.15	5.31	4,342
% Reduced	40%	20%	40%	38%	47%	22%	50%	49%	22%	50%	48%	1%	41%	40%	3%	44%	44%	39%
Annual (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Unmit.	0.64	1.20	0.48	4.99	0.01	0.01	0.96	0.97	0.01	0.24	0.26	12.9	1,123	1,136	1.36	0.04	1.58	1,185
Mit.	0.38	0.97	0.29	3.12	0.01	0.01	0.48	0.49	0.01	0.12	0.13	12.8	665	678	1.32	0.02	0.88	719
% Reduced	40%	20%	40%	38%	47%	22%	50%	49%	22%	50%	48%	1%	41%	40%	3%	44%	44%	39%

2.5. Operations Emissions by Sector, Unmitigated

Sector	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Mobile	3.06	2.80	1.99	22.8	0.06	0.04	5.52	5.56	0.03	1.40	1.43	_	5,953	5,953	0.27	0.23	20.7	6,049
Area	0.88	4.21	0.09	9.41	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	0.00	25.2	25.2	< 0.005	< 0.005	_	25.3
Energy	0.05	0.03	0.47	0.20	< 0.005	0.04	_	0.04	0.04	_	0.04	_	1,224	1,224	0.11	0.01	_	1,229
Water	_	_	_	_	_	_	_	_	_	_	_	11.9	41.6	53.6	1.23	0.03	_	93.1
Waste	_	_	_	_	_	_	_	_	_	_	_	66.2	0.00	66.2	6.62	0.00	_	232
Refrig.	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	1.04	1.04
Total	4.00	7.04	2.55	32.4	0.06	0.08	5.52	5.60	0.07	1.40	1.48	78.1	7,244	7,322	8.23	0.27	21.7	7,629

Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Mobile	3.04	2.78	2.16	21.3	0.06	0.04	5.52	5.56	0.03	1.40	1.43	_	5,725	5,725	0.28	0.24	0.54	5,804
Area	0.00	3.38	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00
Energy	0.05	0.03	0.47	0.20	< 0.005	0.04	_	0.04	0.04	_	0.04	_	1,224	1,224	0.11	0.01	_	1,229
Water	_	_	_	_	_	_	_	_	_	_	_	11.9	41.6	53.6	1.23	0.03	_	93.1
Waste	_	_	_	_	_	_	_	_	_	_	_	66.2	0.00	66.2	6.62	0.00	_	232
Refrig.	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	1.04	1.04
Total	3.09	6.18	2.63	21.5	0.06	0.07	5.52	5.59	0.07	1.40	1.47	78.1	6,991	7,069	8.24	0.28	1.58	7,359
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Mobile	2.87	2.62	2.08	20.7	0.05	0.03	5.24	5.27	0.03	1.33	1.36	_	5,501	5,501	0.26	0.23	8.48	5,584
Area	0.60	3.95	0.06	6.45	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	0.00	17.2	17.2	< 0.005	< 0.005	_	17.3
Energy	0.05	0.03	0.47	0.20	< 0.005	0.04	_	0.04	0.04	_	0.04	_	1,224	1,224	0.11	0.01	_	1,229
Water	_	_	_	_	_	_	_	_	_	_	_	11.9	41.6	53.6	1.23	0.03	_	93.1
Waste	_	_	_	_	_	_	_	_	_	_	_	66.2	0.00	66.2	6.62	0.00	_	232
Refrig.	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	1.04	1.04
Total	3.53	6.60	2.60	27.3	0.06	0.07	5.24	5.31	0.07	1.33	1.40	78.1	6,784	6,862	8.22	0.27	9.52	7,156
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Mobile	0.52	0.48	0.38	3.78	0.01	0.01	0.96	0.96	0.01	0.24	0.25	_	911	911	0.04	0.04	1.40	924
Area	0.11	0.72	0.01	1.18	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	0.00	2.86	2.86	< 0.005	< 0.005	_	2.87
Energy	0.01	< 0.005	0.08	0.04	< 0.005	0.01	_	0.01	0.01	_	0.01	_	203	203	0.02	< 0.005	_	204
Water	_	_	_	<u> </u>	_	_	_	_	_	_	_	1.98	6.90	8.87	0.20	< 0.005	_	15.4
Waste	_	_	_	_	_	_	_	_	_	_	_	11.0	0.00	11.0	1.10	0.00	_	38.3
Refrig.	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	0.17	0.17
Total	0.64	1.20	0.48	4.99	0.01	0.01	0.96	0.97	0.01	0.24	0.26	12.9	1,123	1,136	1.36	0.04	1.58	1,185

2.6. Operations Emissions by Sector, Mitigated

Sector	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Mobile	1.54	1.41	1.00	11.5	0.03	0.02	2.78	2.80	0.02	0.71	0.72	_	2,999	2,999	0.14	0.12	10.4	3,047
Area	0.88	4.21	0.09	9.41	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	0.00	25.2	25.2	< 0.005	< 0.005	_	25.3
Energy	0.05	0.03	0.47	0.20	< 0.005	0.04	_	0.04	0.04	_	0.04	_	1,189	1,189	0.11	0.01	_	1,194
Water	_	_	_	_	_	_	_	_	_	_	_	10.8	37.9	48.8	1.11	0.03	_	84.6
Waste	_	_	_	_	_	_	_	_	_	_	_	66.2	0.00	66.2	6.62	0.00	_	232
Refrig.	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	1.04	1.04
Total	2.48	5.65	1.56	21.1	0.03	0.06	2.78	2.84	0.06	0.71	0.76	77.0	4,252	4,329	7.98	0.15	11.4	4,584
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Mobile	1.53	1.40	1.09	10.7	0.03	0.02	2.78	2.80	0.02	0.71	0.72	_	2,884	2,884	0.14	0.12	0.27	2,924
Area	0.00	3.38	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00
Energy	0.05	0.03	0.47	0.20	< 0.005	0.04	_	0.04	0.04	_	0.04	_	1,189	1,189	0.11	0.01	_	1,194
Water	_	_	_	_	_	_	_	_	_	_	_	10.8	37.9	48.8	1.11	0.03	_	84.6
Waste	_	_	_	_	_	_	_	_	_	_	_	66.2	0.00	66.2	6.62	0.00	_	232
Refrig.	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	1.04	1.04
Total	1.59	4.80	1.56	10.9	0.03	0.06	2.78	2.84	0.05	0.71	0.76	77.0	4,111	4,188	7.98	0.16	1.31	4,436
Average Daily	_	_	_	<u> </u>	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Mobile	1.45	1.32	1.05	10.4	0.03	0.02	2.64	2.66	0.02	0.67	0.69	_	2,771	2,771	0.13	0.11	4.27	2,813
Area	0.60	3.95	0.06	6.45	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	0.00	17.2	17.2	< 0.005	< 0.005	_	17.3
Energy	0.05	0.03	0.47	0.20	< 0.005	0.04	_	0.04	0.04	_	0.04	_	1,189	1,189	0.11	0.01	_	1,194
Water	_	_	_	_	_	_	_	_	_	_	_	10.8	37.9	48.8	1.11	0.03	_	84.6

Waste	_	_	_	_	_	_	_	_	_	_	_	66.2	0.00	66.2	6.62	0.00	_	232
Refrig.	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	1.04	1.04
Total	2.10	5.30	1.57	17.1	0.03	0.06	2.64	2.70	0.06	0.67	0.73	77.0	4,016	4,093	7.97	0.15	5.31	4,342
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Mobile	0.26	0.24	0.19	1.90	< 0.005	< 0.005	0.48	0.48	< 0.005	0.12	0.13	_	459	459	0.02	0.02	0.71	466
Area	0.11	0.72	0.01	1.18	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	0.00	2.86	2.86	< 0.005	< 0.005	_	2.87
Energy	0.01	< 0.005	0.08	0.04	< 0.005	0.01	_	0.01	0.01	_	0.01	_	197	197	0.02	< 0.005	_	198
Water	_	_	_	_	_	_	_	_	_	_	_	1.79	6.28	8.07	0.18	< 0.005	_	14.0
Waste	_	_	_	_	_	_	_	_	_	_	_	11.0	0.00	11.0	1.10	0.00	_	38.3
Refrig.	_	_	_	_	_	_	_	_	_	_	_	_	_	_	-	_	0.17	0.17
Total	0.38	0.97	0.29	3.12	0.01	0.01	0.48	0.49	0.01	0.12	0.13	12.8	665	678	1.32	0.02	0.88	719

3. Construction Emissions Details

3.1. Demolition (2024) - Unmitigated

Location		ROG		СО			ì	PM10T			<u> </u>	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		2.62	24.9	21.7	0.03	1.06	_	1.06	0.98	_	0.98	_	3,425	3,425	0.14	0.03	_	3,437
Demolitio n	_	_	_	_	_	_	7.24	7.24	_	1.10	1.10	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.14	1.36	1.19	< 0.005	0.06	-	0.06	0.05	_	0.05	_	188	188	0.01	< 0.005	_	188
Demolitio n	-	_	_	_	-	_	0.40	0.40	-	0.06	0.06	_	_	-	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.03	0.25	0.22	< 0.005	0.01	-	0.01	0.01	_	0.01	_	31.1	31.1	< 0.005	< 0.005	_	31.2
Demolitio n	_	_	_	_	_	_	0.07	0.07	_	0.01	0.01	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.07	0.06	0.06	0.96	0.00	0.00	0.21	0.21	0.00	0.05	0.05	_	217	217	< 0.005	0.01	0.89	220
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.61	0.12	7.39	3.22	0.04	0.07	1.52	1.59	0.07	0.43	0.50	_	5,960	5,960	0.48	0.95	12.4	6,267
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.05	0.00	0.00	0.01	0.01	0.00	< 0.005	< 0.005	_	11.5	11.5	< 0.005	< 0.005	0.02	11.6
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.03	0.01	0.42	0.18	< 0.005	< 0.005	0.08	0.09	< 0.005	0.02	0.03	_	327	327	0.03	0.05	0.29	343
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.01	0.00	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	_	1.90	1.90	< 0.005	< 0.005	< 0.005	1.92

Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.01	< 0.005	0.08	0.03	< 0.005	< 0.005	0.02	0.02	< 0.005	< 0.005	0.01	_	54.1	54.1	< 0.005	0.01	0.05	56.8

3.2. Demolition (2024) - Mitigated

Location	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		2.62	24.9	21.7	0.03	1.06	_	1.06	0.98	_	0.98	_	3,425	3,425	0.14	0.03	_	3,437
Demolitio n	_	_	_	_	_	_	7.24	7.24	_	1.10	1.10	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.14	1.36	1.19	< 0.005	0.06	_	0.06	0.05	_	0.05	_	188	188	0.01	< 0.005	_	188
Demolitio n	_	_	_	_	_	_	0.40	0.40	_	0.06	0.06	_	-	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	-	_	_	_	_	_	_	_	-	_	_
Off-Road Equipmen		0.03	0.25	0.22	< 0.005	0.01	_	0.01	0.01	_	0.01	_	31.1	31.1	< 0.005	< 0.005	_	31.2
Demolitio n	_	_	_	_	_	_	0.07	0.07	_	0.01	0.01	_	_	_	_	_	_	_

Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.07	0.06	0.06	0.96	0.00	0.00	0.21	0.21	0.00	0.05	0.05	_	217	217	< 0.005	0.01	0.89	220
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.61	0.12	7.39	3.22	0.04	0.07	1.52	1.59	0.07	0.43	0.50	_	5,960	5,960	0.48	0.95	12.4	6,267
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	-	_	_	_	_	_	-
Worker	< 0.005	< 0.005	< 0.005	0.05	0.00	0.00	0.01	0.01	0.00	< 0.005	< 0.005	_	11.5	11.5	< 0.005	< 0.005	0.02	11.6
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.03	0.01	0.42	0.18	< 0.005	< 0.005	0.08	0.09	< 0.005	0.02	0.03	_	327	327	0.03	0.05	0.29	343
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.01	0.00	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	_	1.90	1.90	< 0.005	< 0.005	< 0.005	1.92
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.01	< 0.005	0.08	0.03	< 0.005	< 0.005	0.02	0.02	< 0.005	< 0.005	0.01	_	54.1	54.1	< 0.005	0.01	0.05	56.8

3.3. Site Preparation (2024) - Unmitigated

Location	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

Off-Road Equipmen		3.65	36.0	32.9	0.05	1.60	_	1.60	1.47	_	1.47	-	5,296	5,296	0.21	0.04	_	5,314
Dust From Material Movemen	<u>—</u>	_	_	_	_	_	7.67	7.67	_	3.94	3.94	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	-
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.05	0.49	0.45	< 0.005	0.02	_	0.02	0.02	_	0.02	_	72.5	72.5	< 0.005	< 0.005	_	72.8
Dust From Material Movemen	<u> </u>	_	_	_	_	_	0.11	0.11	_	0.05	0.05	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.01	0.09	0.08	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	12.0	12.0	< 0.005	< 0.005	_	12.1
Dust From Material Movemen	<u>—</u>	_	_	_	_	_	0.02	0.02	_	0.01	0.01	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	
Worker	0.08	0.07	0.07	1.08	0.00	0.00	0.24	0.24	0.00	0.06	0.06	_	244	244	< 0.005	0.01	1.00	248

Vendor	0.01	< 0.005	0.07	0.03	< 0.005	< 0.005	0.02	0.02	< 0.005	< 0.005	0.01	_	64.8	64.8	< 0.005	0.01	0.17	67.7
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.01	0.00	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	_	3.22	3.22	< 0.005	< 0.005	0.01	3.27
Vendor	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	_	0.89	0.89	< 0.005	< 0.005	< 0.005	0.93
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	< 0.005	0.00	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	_	0.53	0.53	< 0.005	< 0.005	< 0.005	0.54
Vendor	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	_	0.15	0.15	< 0.005	< 0.005	< 0.005	0.15
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

3.4. Site Preparation (2024) - Mitigated

Location	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		3.65	36.0	32.9	0.05	1.60	_	1.60	1.47	_	1.47	_	5,296	5,296	0.21	0.04	_	5,314
Dust From Material Movemen		_	_	_	_	_	7.67	7.67	_	3.94	3.94	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.05	0.49	0.45	< 0.005	0.02	_	0.02	0.02	_	0.02	_	72.5	72.5	< 0.005	< 0.005	_	72.8
Dust From Material Movemen	_	_	_	-	_	_	0.11	0.11	_	0.05	0.05	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.01	0.09	0.08	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	12.0	12.0	< 0.005	< 0.005	_	12.1
Dust From Material Movemen	<u> </u>	_	_	_	_	_	0.02	0.02	_	0.01	0.01	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.08	0.07	0.07	1.08	0.00	0.00	0.24	0.24	0.00	0.06	0.06	_	244	244	< 0.005	0.01	1.00	248
Vendor	0.01	< 0.005	0.07	0.03	< 0.005	< 0.005	0.02	0.02	< 0.005	< 0.005	0.01	_	64.8	64.8	< 0.005	0.01	0.17	67.7
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)		_	_	_	_	_	_	_	_	_	_	_	_	_	-	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

Worker	< 0.005	< 0.005	< 0.005	0.01	0.00	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	_	3.22	3.22	< 0.005	< 0.005	0.01	3.27
Vendor	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	_	0.89	0.89	< 0.005	< 0.005	< 0.005	0.93
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	< 0.005	0.00	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	_	0.53	0.53	< 0.005	< 0.005	< 0.005	0.54
Vendor	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	_	0.15	0.15	< 0.005	< 0.005	< 0.005	0.15
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

3.5. Grading (2024) - Unmitigated

Location	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T		PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		1.90	18.2	18.8	0.03	0.84	_	0.84	0.77	_	0.77	_	2,958	2,958	0.12	0.02	_	2,969
Dust From Material Movemen	<u> </u>	_	_	_	_	_	2.76	2.76	_	1.34	1.34	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.04	0.40	0.41	< 0.005	0.02	_	0.02	0.02	_	0.02	_	64.8	64.8	< 0.005	< 0.005	_	65.1

Bust From Material Movement	_	—
truck Section Section		
Off-Road 0.01 0.01 0.07 0.08 < 0.005 < 0.005 — < 0.005 — < 0.005 — 10.7 10.7 < 0.005 < 0.005 Equipment Dust From Material Movement Onsite 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.	0.00	0.00
Equipment	_	_
From Material Movemen: Solution State Stat	_	10.8
truck	_	_
Daily, Summer (Max) Worker 0.07 0.06 0.06 0.96 0.00 0.00 0.21 0.21 0.00 0.05 0.05 — 217 217 < 0.005 0.01	0.00	0.00
Summer (Max) Worker 0.07 0.06 0.06 0.96 0.00 0.00 0.21 0.21 0.00 0.05 0.05 — 217 217 < 0.005 0.01	_	_
	_	_
	0.89	220
Vendor 0.01 < 0.005 0.07 0.03 < 0.005 < 0.005 0.02 0.02 < 0.005 < 0.005 0.01 — 64.8 64.8 < 0.005 0.01	0.17	67.7
Hauling 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.	0.00	0.00
Daily, — — — — — — — — — — — — — — — — — — —	_	_
Average — — — — — — — — — — — — — — — — — — —	_	_
Worker < 0.005 < 0.005 < 0.005 0.02 0.00 0.00 < 0.005 < 0.005 0.00 < 0.005 < 0.005 - 4.58 4.58 < 0.005 < 0.005	0.01	4.65
Vendor < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005	< 0.005	1.48
Hauling 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.	0.00	0.00
Annual — — — — — — — — — — — — — — — — — — —	_	_
Worker < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005		0.77
Vendor < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005 < 0.005	< 0.005	0.25

Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00		0.00	0.00	0.00	0.00	0.00	0.00

3.6. Grading (2024) - Mitigated

Location	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	_	_	_	_	_	_	-	_	_	_	_	_	<u> </u>	_	_	_	_	_
Daily, Summer (Max)		_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		1.90	18.2	18.8	0.03	0.84	_	0.84	0.77	_	0.77	_	2,958	2,958	0.12	0.02	_	2,969
Dust From Material Movemen	<u> </u>	_	_	_	_	_	2.76	2.76	_	1.34	1.34		_		_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	-	_	_	_	_	_	_
Off-Road Equipmen		0.04	0.40	0.41	< 0.005	0.02	_	0.02	0.02	_	0.02	-	64.8	64.8	< 0.005	< 0.005	_	65.1
Dust From Material Movemen		-	_	-	_	-	0.06	0.06	-	0.03	0.03	_	_	_	-	-	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.01	0.07	0.08	< 0.005	< 0.005	_	< 0.005	< 0.005	-	< 0.005	_	10.7	10.7	< 0.005	< 0.005	_	10.8

Dust From Material Movemen	 :t	_	_	_	_	_	0.01	0.01	_	0.01	0.01	_	_		_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_		_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.07	0.06	0.06	0.96	0.00	0.00	0.21	0.21	0.00	0.05	0.05	-	217	217	< 0.005	0.01	0.89	220
Vendor	0.01	< 0.005	0.07	0.03	< 0.005	< 0.005	0.02	0.02	< 0.005	< 0.005	0.01	_	64.8	64.8	< 0.005	0.01	0.17	67.7
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.02	0.00	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	_	4.58	4.58	< 0.005	< 0.005	0.01	4.65
Vendor	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	_	1.42	1.42	< 0.005	< 0.005	< 0.005	1.48
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	< 0.005	0.00	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	_	0.76	0.76	< 0.005	< 0.005	< 0.005	0.77
Vendor	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	_	0.24	0.24	< 0.005	< 0.005	< 0.005	0.25
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

3.7. Building Construction (2024) - Unmitigated

Location	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

Daily,													_					
Summer (Max)																		
Off-Road Equipmen		1.20	11.2	13.1	0.02	0.50	_	0.50	0.46	_	0.46	_	2,398	2,398	0.10	0.02	_	2,406
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen	1.44 t	1.20	11.2	13.1	0.02	0.50	_	0.50	0.46	_	0.46	_	2,398	2,398	0.10	0.02	_	2,406
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	_	-	_	_	_	-	_	_	_	-	_	_	_	-	_	_	_
Off-Road Equipmen		0.24	2.28	2.67	< 0.005	0.10	-	0.10	0.09	_	0.09	-	488	488	0.02	< 0.005	_	490
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.04	0.42	0.49	< 0.005	0.02	-	0.02	0.02	_	0.02	-	80.8	80.8	< 0.005	< 0.005	_	81.1
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	<u> </u>	_	_	_	_	_	_	_	_	-	-	_	_	_	_	-
Worker	0.50	0.44	0.47	7.22	0.00	0.00	1.57	1.57	0.00	0.37	0.37	_	1,626	1,626	0.02	0.06	6.67	1,650
Vendor	0.05	0.02	0.62	0.31	< 0.005	0.01	0.15	0.16	< 0.005	0.04	0.05	_	583	583	0.03	0.08	1.57	609
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	
Worker	0.50	0.44	0.53	6.22	0.00	0.00	1.57	1.57	0.00	0.37	0.37	_	1,547	1,547	0.02	0.06	0.17	1,566
Vendor	0.05	0.02	0.65	0.32	< 0.005	0.01	0.15	0.16	< 0.005	0.04	0.05	_	583	583	0.03	0.08	0.04	608
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.10	0.09	0.11	1.33	0.00	0.00	0.32	0.32	0.00	0.07	0.07	_	319	319	< 0.005	0.01	0.59	324
Vendor	0.01	< 0.005	0.13	0.06	< 0.005	< 0.005	0.03	0.03	< 0.005	0.01	0.01	_	119	119	0.01	0.02	0.14	124
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.02	0.02	0.02	0.24	0.00	0.00	0.06	0.06	0.00	0.01	0.01	_	52.9	52.9	< 0.005	< 0.005	0.10	53.6
Vendor	< 0.005	< 0.005	0.02	0.01	< 0.005	< 0.005	0.01	0.01	< 0.005	< 0.005	< 0.005	_	19.7	19.7	< 0.005	< 0.005	0.02	20.5
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

3.8. Building Construction (2024) - Mitigated

		`	,	<i>y</i> ,		July arra			J ,	· J	,							
Location	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		1.20	11.2	13.1	0.02	0.50	_	0.50	0.46	_	0.46	_	2,398	2,398	0.10	0.02	_	2,406
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

Off-Road Equipmen		1.20	11.2	13.1	0.02	0.50	_	0.50	0.46	_	0.46	_	2,398	2,398	0.10	0.02	_	2,406
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	_	-	-	_	_	_	-	-	_	-	-	_	_	-	-	-	_
Off-Road Equipmen		0.24	2.28	2.67	< 0.005	0.10	_	0.10	0.09	_	0.09	_	488	488	0.02	< 0.005	_	490
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.04	0.42	0.49	< 0.005	0.02	_	0.02	0.02	_	0.02	-	80.8	80.8	< 0.005	< 0.005	_	81.1
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	-	_	_	-	_	_	_	_	_	_	_	-	_	_	-
Worker	0.50	0.44	0.47	7.22	0.00	0.00	1.57	1.57	0.00	0.37	0.37	_	1,626	1,626	0.02	0.06	6.67	1,650
Vendor	0.05	0.02	0.62	0.31	< 0.005	0.01	0.15	0.16	< 0.005	0.04	0.05	_	583	583	0.03	0.08	1.57	609
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	-	_	_	-	_	_	_	_	_	_	_	-
Worker	0.50	0.44	0.53	6.22	0.00	0.00	1.57	1.57	0.00	0.37	0.37	_	1,547	1,547	0.02	0.06	0.17	1,566
Vendor	0.05	0.02	0.65	0.32	< 0.005	0.01	0.15	0.16	< 0.005	0.04	0.05	_	583	583	0.03	0.08	0.04	608
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	_	_	_	_	_	_	_		_	_	_	-	_	_	_	_	_
Worker	0.10	0.09	0.11	1.33	0.00	0.00	0.32	0.32	0.00	0.07	0.07	_	319	319	< 0.005	0.01	0.59	324
Vendor	0.01	< 0.005	0.13	0.06	< 0.005	< 0.005	0.03	0.03	< 0.005	0.01	0.01	_	119	119	0.01	0.02	0.14	124

Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.02	0.02	0.02	0.24	0.00	0.00	0.06	0.06	0.00	0.01	0.01	_	52.9	52.9	< 0.005	< 0.005	0.10	53.6
Vendor	< 0.005	< 0.005	0.02	0.01	< 0.005	< 0.005	0.01	0.01	< 0.005	< 0.005	< 0.005	_	19.7	19.7	< 0.005	< 0.005	0.02	20.5
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

3.9. Building Construction (2025) - Unmitigated

	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T		PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		1.13	10.4	13.0	0.02	0.43	_	0.43	0.40	_	0.40	_	2,398	2,398	0.10	0.02	_	2,406
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		1.13	10.4	13.0	0.02	0.43	_	0.43	0.40	_	0.40	_	2,398	2,398	0.10	0.02	_	2,406
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.48	4.48	5.59	0.01	0.19	_	0.19	0.17	_	0.17	_	1,028	1,028	0.04	0.01	_	1,031
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

Off-Road Equipmer		0.09	0.82	1.02	< 0.005	0.03	_	0.03	0.03	_	0.03	_	170	170	0.01	< 0.005	_	171
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	-	_	_	-	_	_	_	_	_	_	_	-	_	_	_	_	_	_
Worker	0.48	0.43	0.42	6.72	0.00	0.00	1.57	1.57	0.00	0.37	0.37	_	1,593	1,593	0.02	0.06	6.03	1,616
Vendor	0.04	0.02	0.60	0.30	< 0.005	< 0.005	0.15	0.16	< 0.005	0.04	0.05	_	574	574	0.03	0.08	1.56	600
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	-	_	_	_	_	_	_	_	_	_	_	-	_	_	_	_	_	_
Worker	0.48	0.42	0.47	5.81	0.00	0.00	1.57	1.57	0.00	0.37	0.37	_	1,516	1,516	0.02	0.06	0.16	1,534
Vendor	0.04	0.02	0.62	0.30	< 0.005	< 0.005	0.15	0.16	< 0.005	0.04	0.05	_	574	574	0.03	0.08	0.04	599
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.20	0.18	0.20	2.60	0.00	0.00	0.67	0.67	0.00	0.16	0.16	_	659	659	0.01	0.02	1.12	667
Vendor	0.02	0.01	0.27	0.13	< 0.005	< 0.005	0.07	0.07	< 0.005	0.02	0.02	_	246	246	0.01	0.03	0.29	257
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.04	0.03	0.04	0.48	0.00	0.00	0.12	0.12	0.00	0.03	0.03	_	109	109	< 0.005	< 0.005	0.18	110
Vendor	< 0.005	< 0.005	0.05	0.02	< 0.005	< 0.005	0.01	0.01	< 0.005	< 0.005	< 0.005	_	40.7	40.7	< 0.005	0.01	0.05	42.5
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

3.10. Building Construction (2025) - Mitigated

Onsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	-	_	_	_	_	_	_	_
Off-Road Equipmen		1.13	10.4	13.0	0.02	0.43	_	0.43	0.40	-	0.40	_	2,398	2,398	0.10	0.02	_	2,406
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	-	_	_	-	_
Off-Road Equipmen		1.13	10.4	13.0	0.02	0.43	_	0.43	0.40	_	0.40	_	2,398	2,398	0.10	0.02	_	2,406
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	-
Off-Road Equipmen		0.48	4.48	5.59	0.01	0.19	_	0.19	0.17	-	0.17	_	1,028	1,028	0.04	0.01	_	1,031
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.09	0.82	1.02	< 0.005	0.03	_	0.03	0.03	_	0.03	_	170	170	0.01	< 0.005	_	171
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	-	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.48	0.43	0.42	6.72	0.00	0.00	1.57	1.57	0.00	0.37	0.37	_	1,593	1,593	0.02	0.06	6.03	1,616
Vendor	0.04	0.02	0.60	0.30	< 0.005	< 0.005	0.15	0.16	< 0.005	0.04	0.05	_	574	574	0.03	0.08	1.56	600
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.48	0.42	0.47	5.81	0.00	0.00	1.57	1.57	0.00	0.37	0.37	-	1,516	1,516	0.02	0.06	0.16	1,534
Vendor	0.04	0.02	0.62	0.30	< 0.005	< 0.005	0.15	0.16	< 0.005	0.04	0.05	_	574	574	0.03	0.08	0.04	599
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.20	0.18	0.20	2.60	0.00	0.00	0.67	0.67	0.00	0.16	0.16	_	659	659	0.01	0.02	1.12	667
Vendor	0.02	0.01	0.27	0.13	< 0.005	< 0.005	0.07	0.07	< 0.005	0.02	0.02	_	246	246	0.01	0.03	0.29	257
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.04	0.03	0.04	0.48	0.00	0.00	0.12	0.12	0.00	0.03	0.03	_	109	109	< 0.005	< 0.005	0.18	110
Vendor	< 0.005	< 0.005	0.05	0.02	< 0.005	< 0.005	0.01	0.01	< 0.005	< 0.005	< 0.005	_	40.7	40.7	< 0.005	0.01	0.05	42.5
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

3.11. Paving (2025) - Unmitigated

Location	TOG	ROG		СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.71	6.52	8.84	0.01	0.29	_	0.29	0.26	_	0.26	_	1,351	1,351	0.05	0.01	_	1,355
Paving	_	0.23	_	_	_	<u> </u>	_	_	_	_	_	_	_	_	_	_	<u> </u>	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

Daily, Winter (Max)	_			_			_		_	_		_		_	_		_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	-	_
Off-Road Equipmen		0.04	0.32	0.44	< 0.005	0.01	_	0.01	0.01	_	0.01	_	66.6	66.6	< 0.005	< 0.005	_	66.8
Paving	_	0.01	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.01	0.06	0.08	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	11.0	11.0	< 0.005	< 0.005	-	11.1
Paving	_	< 0.005	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	-	_	_	_	_	-	_	_	_	_
Worker	0.08	0.07	0.07	1.12	0.00	0.00	0.26	0.26	0.00	0.06	0.06	_	265	265	< 0.005	0.01	1.01	269
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	-	_	-	_	_	_	_	-	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	-	-	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.05	0.00	0.00	0.01	0.01	0.00	< 0.005	< 0.005	_	12.6	12.6	< 0.005	< 0.005	0.02	12.8
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	<u> </u>	_	_	_

Worker	< 0.005	< 0.005	< 0.005	0.01	0.00	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	_	2.09	2.09	< 0.005	< 0.005	< 0.005	2.12
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

3.12. Paving (2025) - Mitigated

	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.71	6.52	8.84	0.01	0.29	_	0.29	0.26	_	0.26	_	1,351	1,351	0.05	0.01	_	1,355
Paving	_	0.23	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	-	_	-	_	-
Off-Road Equipmen		0.04	0.32	0.44	< 0.005	0.01	_	0.01	0.01	_	0.01	_	66.6	66.6	< 0.005	< 0.005	_	66.8
Paving	_	0.01	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.01	0.06	0.08	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	11.0	11.0	< 0.005	< 0.005	_	11.1
Paving	_	< 0.005	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	-	_	-	_	_	_	_	_	_	_
Worker	0.08	0.07	0.07	1.12	0.00	0.00	0.26	0.26	0.00	0.06	0.06	_	265	265	< 0.005	0.01	1.01	269
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	-
Average Daily	_	_	_	_	_	_	_	_	_	_	_	-	_	_	_	_	_	-
Worker	< 0.005	< 0.005	< 0.005	0.05	0.00	0.00	0.01	0.01	0.00	< 0.005	< 0.005	_	12.6	12.6	< 0.005	< 0.005	0.02	12.8
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.01	0.00	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	_	2.09	2.09	< 0.005	< 0.005	< 0.005	2.12
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

3.13. Architectural Coating (2025) - Unmitigated

Location	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

Off-Road Equipmen		0.13	0.88	1.14	< 0.005	0.03	_	0.03	0.03	_	0.03	_	134	134	0.01	< 0.005	_	134
Architect ural Coatings	_	51.7	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	-		_	_	_
Average Daily	_	_	_		_	_	_	_		_	_	_		_		_	_	_
Off-Road Equipmen		0.01	0.04	0.06	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	6.58	6.58	< 0.005	< 0.005	_	6.61
Architect ural Coatings	_	2.55	_	_	_	_	-	_	_	_	_	-	_	_	_	_	_	-
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		< 0.005	0.01	0.01	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	1.09	1.09	< 0.005	< 0.005	_	1.09
Architect ural Coatings	_	0.47	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	-	_	_	_	-	_	_	-
Worker	0.10	0.09	0.08	1.34	0.00	0.00	0.31	0.31	0.00	0.07	0.07	_	319	319	< 0.005	0.01	1.21	323
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.06	0.00	0.00	0.02	0.02	0.00	< 0.005	< 0.005	_	15.2	15.2	< 0.005	< 0.005	0.03	15.4
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.01	0.00	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	_	2.51	2.51	< 0.005	< 0.005	< 0.005	2.54
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

3.14. Architectural Coating (2025) - Mitigated

Location	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	СО2Т	CH4	N2O	R	CO2e
Onsite	_	_	<u> </u>	<u> </u>	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen		0.13	0.88	1.14	< 0.005	0.03	_	0.03	0.03	_	0.03	_	134	134	0.01	< 0.005	_	134
Architect ural Coatings	_	51.7	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	- 38 / 80	_	_	_	_	_	_	_	_	_

Off-Road Equipmen		0.01	0.04	0.06	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	6.58	6.58	< 0.005	< 0.005	_	6.61
Architect ural Coatings	_	2.55	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipmen	< 0.005 t	< 0.005	0.01	0.01	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	1.09	1.09	< 0.005	< 0.005	_	1.09
Architect ural Coatings	_	0.47	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	0.10	0.09	0.08	1.34	0.00	0.00	0.31	0.31	0.00	0.07	0.07	_	319	319	< 0.005	0.01	1.21	323
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.06	0.00	0.00	0.02	0.02	0.00	< 0.005	< 0.005	_	15.2	15.2	< 0.005	< 0.005	0.03	15.4
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.01	0.00	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	_	2.51	2.51	< 0.005	< 0.005	< 0.005	2.54

Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

4. Operations Emissions Details

4.1. Mobile Emissions by Land Use

4.1.1. Unmitigated

Land Use	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	-	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	3.06	2.80	1.99	22.8	0.06	0.04	5.52	5.56	0.03	1.40	1.43	_	5,953	5,953	0.27	0.23	20.7	6,049
Parking Lot	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Total	3.06	2.80	1.99	22.8	0.06	0.04	5.52	5.56	0.03	1.40	1.43	_	5,953	5,953	0.27	0.23	20.7	6,049
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	3.04	2.78	2.16	21.3	0.06	0.04	5.52	5.56	0.03	1.40	1.43	_	5,725	5,725	0.28	0.24	0.54	5,804
Parking Lot	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Total	3.04	2.78	2.16	21.3	0.06	0.04	5.52	5.56	0.03	1.40	1.43	_	5,725	5,725	0.28	0.24	0.54	5,804
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

Apartme nts Mid Rise	0.52	0.48	0.38	3.78	0.01	0.01	0.96	0.96	0.01	0.24	0.25	_	911	911	0.04	0.04	1.40	924
Parking Lot	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Total	0.52	0.48	0.38	3.78	0.01	0.01	0.96	0.96	0.01	0.24	0.25	_	911	911	0.04	0.04	1.40	924

4.1.2. Mitigated

		110 (10, 00	,	J, J		, , , , , ,	000			,	αι							
Land Use	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	1.54	1.41	1.00	11.5	0.03	0.02	2.78	2.80	0.02	0.71	0.72	_	2,999	2,999	0.14	0.12	10.4	3,047
Parking Lot	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Total	1.54	1.41	1.00	11.5	0.03	0.02	2.78	2.80	0.02	0.71	0.72	_	2,999	2,999	0.14	0.12	10.4	3,047
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	1.53	1.40	1.09	10.7	0.03	0.02	2.78	2.80	0.02	0.71	0.72	_	2,884	2,884	0.14	0.12	0.27	2,924
Parking Lot	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Total	1.53	1.40	1.09	10.7	0.03	0.02	2.78	2.80	0.02	0.71	0.72	_	2,884	2,884	0.14	0.12	0.27	2,924
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise		0.24	0.19	1.90	< 0.005	< 0.005	0.48	0.48	< 0.005	0.12	0.13	_	459	459	0.02	0.02	0.71	466

Parking Lot	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Total	0.26	0.24	0.19	1.90	< 0.005	< 0.005	0.48	0.48	< 0.005	0.12	0.13	_	459	459	0.02	0.02	0.71	466

4.2. Energy

4.2.1. Electricity Emissions By Land Use - Unmitigated

Land Use	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	_	_	_	_	_	_	_	_	_	_	_	_	577	577	0.06	0.01	_	581
Parking Lot	_	_	_	_	_	_	_	_	_	_	_	_	56.1	56.1	0.01	< 0.005	_	56.4
Total	_	_	_	_	_	_	_	_	_	_	_	_	633	633	0.06	0.01	_	637
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	_	_	_	_	_	_	_	_	_	_	_	_	577	577	0.06	0.01	_	581
Parking Lot	_	_	_	_	_	_	_	_	_	_	_	_	56.1	56.1	0.01	< 0.005	_	56.4
Total	_	_	_	_	_	_	_	_	_	_	_	_	633	633	0.06	0.01	_	637
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	_	_	_	_	_	_	_	_	_	_	_	_	95.6	95.6	0.01	< 0.005	_	96.1

Parking Lot	_	_	_	_	_	_	_	_	_	_	_	_	9.29	9.29	< 0.005	< 0.005	_	9.34
Total	_	_	_	_	_	_	_	_	_	_	_	_	105	105	0.01	< 0.005	_	105

4.2.2. Electricity Emissions By Land Use - Mitigated

Land Use	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	_	_	_	_	_	_	_	_	_	_	_	_	542	542	0.05	0.01	_	545
Parking Lot	_	_	_	_	_	_	_	_	_	_	_	_	56.1	56.1	0.01	< 0.005	_	56.4
Total	_	_	_	_	_	_	_	_	_	_	_	_	598	598	0.06	0.01	_	602
Daily, Winter (Max)	_	_	_	-	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	_	_	_	_	_	_	_	_	_	_	_	_	542	542	0.05	0.01	_	545
Parking Lot	_	_	_	_	_	_	-	_	-	_	-	_	56.1	56.1	0.01	< 0.005	_	56.4
Total	_	_	_	_	_	_	_	_	_	_	_	_	598	598	0.06	0.01	_	602
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	_	_	_	_	_	_	_	_	_	_	_	-	89.8	89.8	0.01	< 0.005	_	90.3
Parking Lot	_		_	_	_	_	_	_	_	_	_	_	9.29	9.29	< 0.005	< 0.005	_	9.34
Total	_	_	_	_	_	_	_	_	_	_	_	_	99.1	99.1	0.01	< 0.005	_	99.6

4.2.3. Natural Gas Emissions By Land Use - Unmitigated

Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

Land Use	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	-	_	_	-	-	_	-	_	-	_	_	_	-	_	_	-
Apartme nts Mid Rise	0.05	0.03	0.47	0.20	< 0.005	0.04	_	0.04	0.04	_	0.04	_	591	591	0.05	< 0.005	_	593
Parking Lot	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	_	0.00	0.00	0.00	0.00	_	0.00
Total	0.05	0.03	0.47	0.20	< 0.005	0.04	_	0.04	0.04	_	0.04	_	591	591	0.05	< 0.005	_	593
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	-
Apartme nts Mid Rise	0.05	0.03	0.47	0.20	< 0.005	0.04	_	0.04	0.04	_	0.04	_	591	591	0.05	< 0.005	_	593
Parking Lot	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	_	0.00	0.00	0.00	0.00	_	0.00
Total	0.05	0.03	0.47	0.20	< 0.005	0.04	_	0.04	0.04	_	0.04	_	591	591	0.05	< 0.005	_	593
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	0.01	< 0.005	0.08	0.04	< 0.005	0.01	_	0.01	0.01	_	0.01	_	97.8	97.8	0.01	< 0.005	_	98.1
Parking Lot	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	_	0.00	0.00	0.00	0.00	_	0.00
Total	0.01	< 0.005	0.08	0.04	< 0.005	0.01	_	0.01	0.01	_	0.01	_	97.8	97.8	0.01	< 0.005	_	98.1

4.2.4. Natural Gas Emissions By Land Use - Mitigated

Land Use	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	-	_	_	_	_	_	-	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	0.05	0.03	0.47	0.20	< 0.005	0.04	_	0.04	0.04	_	0.04	_	591	591	0.05	< 0.005	_	593
Parking Lot	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	_	0.00	0.00	0.00	0.00	-	0.00
Total	0.05	0.03	0.47	0.20	< 0.005	0.04	_	0.04	0.04	_	0.04	_	591	591	0.05	< 0.005	_	593
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	0.05	0.03	0.47	0.20	< 0.005	0.04	_	0.04	0.04	_	0.04	_	591	591	0.05	< 0.005	_	593
Parking Lot	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	_	0.00	0.00	0.00	0.00	-	0.00
Total	0.05	0.03	0.47	0.20	< 0.005	0.04	_	0.04	0.04	_	0.04	_	591	591	0.05	< 0.005	_	593
Annual	_	_	_	-	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	0.01	< 0.005	0.08	0.04	< 0.005	0.01	_	0.01	0.01	_	0.01	_	97.8	97.8	0.01	< 0.005	_	98.1
Parking Lot	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	_	0.00	0.00	0.00	0.00	-	0.00
Total	0.01	< 0.005	0.08	0.04	< 0.005	0.01	_	0.01	0.01	_	0.01	_	97.8	97.8	0.01	< 0.005	_	98.1

4.3. Area Emissions by Source

4.3.1. Unmitigated

Source	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
--------	-----	-----	-----	----	-----	-------	-------	-------	--------	--------	--------	------	-------	------	-----	-----	---	------

Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Hearths	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00
Consum er Products	_	3.12	_	-	_	_	_	_	_	_	-	_	_	_	_	_	_	_
Architect ural Coatings	_	0.26	_	_	_	_	_	_	_	_		_	_	-	_	_	_	_
Landsca pe Equipme nt	0.88	0.83	0.09	9.41	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	25.2	25.2	< 0.005	< 0.005	_	25.3
Total	0.88	4.21	0.09	9.41	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	0.00	25.2	25.2	< 0.005	< 0.005	_	25.3
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Hearths	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00
Consum er Products	_	3.12	_	-	_	_	_	_	_	_	-	_	_	_	_	_	_	_
Architect ural Coatings	_	0.26	_	_	_	_	_	_	_	_	-	_	_	_	_	_	_	_
Total	0.00	3.38	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Hearths	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00
Consum er Products	_	0.57	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Architect ural Coatings	_	0.05	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

Landsca pe	0.11	0.10	0.01	1.18	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	2.86	2.86	< 0.005	< 0.005	_	2.87
Total	0.11	0.72	0.01	1.18	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	0.00	2.86	2.86	< 0.005	< 0.005	_	2.87

4.3.2. Mitigated

Source	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	-	_	_	_	_	_	_	_	_	_	_	-
Hearths	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00
Consum er Products	_	3.12	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Architect ural Coatings	_	0.26	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Landsca pe Equipme nt	0.88	0.83	0.09	9.41	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	25.2	25.2	< 0.005	< 0.005	_	25.3
Total	0.88	4.21	0.09	9.41	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	0.00	25.2	25.2	< 0.005	< 0.005	_	25.3
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Hearths	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00
Consum er Products	_	3.12	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Architect ural Coatings	_	0.26	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	0.00	3.38	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00

Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Hearths	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00
Consum er Products	_	0.57	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Architect ural Coatings		0.05	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Landsca pe Equipme nt		0.10	0.01	1.18	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	2.86	2.86	< 0.005	< 0.005	_	2.87
Total	0.11	0.72	0.01	1.18	< 0.005	< 0.005	_	< 0.005	< 0.005	_	< 0.005	0.00	2.86	2.86	< 0.005	< 0.005	_	2.87

4.4. Water Emissions by Land Use

4.4.1. Unmitigated

Land Use	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	СО2Т	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	_	_	_	_	_	_	_	_	_	_	_	11.9	41.6	53.6	1.23	0.03	_	93.1
Parking Lot	_	_	_	_	_	_	_	_	_	_	_	0.00	0.00	0.00	0.00	0.00	_	0.00
Total	_	_	_	_	_	_	_	_	_	_	_	11.9	41.6	53.6	1.23	0.03	_	93.1
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

Apartme nts	_	_	_	_	_	_	_	_	_	_	_	11.9	41.6	53.6	1.23	0.03	_	93.1
Parking Lot	_	_	_	-	_	_	_	_	_	_	_	0.00	0.00	0.00	0.00	0.00	_	0.00
Total	_	_	_	_	_	_	_	_	_	_	_	11.9	41.6	53.6	1.23	0.03	_	93.1
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	_	_	_	_	_	_	_	_	_	_	_	1.98	6.90	8.87	0.20	< 0.005	_	15.4
Parking Lot	_	_	_	_	_	_	_	_	_	_	_	0.00	0.00	0.00	0.00	0.00	_	0.00
Total	_	_	_	_	_	_	_	_	_	_	_	1.98	6.90	8.87	0.20	< 0.005	_	15.4

4.4.2. Mitigated

Land Use	TOG			CO					PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	_	_		_	_	_	_	_	_	_	_	10.8	37.9	48.8	1.11	0.03	_	84.6
Parking Lot	_	_		_	_	_	_	_	_	_	_	0.00	0.00	0.00	0.00	0.00	_	0.00
Total	_	_	_	_	_	_	_	_	_	_	_	10.8	37.9	48.8	1.11	0.03	_	84.6
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	_	_	_	_	_	_	_	_	_	_	_	10.8	37.9	48.8	1.11	0.03	_	84.6

Parking Lot	_	_	_	_	_	_	_	_	_	_	_	0.00	0.00	0.00	0.00	0.00	_	0.00
Total	_	_	_	_	_	_	_	_	_	_	_	10.8	37.9	48.8	1.11	0.03	_	84.6
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	_	_	_	_	_	_	_	_	_	_	_	1.79	6.28	8.07	0.18	< 0.005	_	14.0
Parking Lot	_	_	_	_	_	_	_	_	_	_	_	0.00	0.00	0.00	0.00	0.00	_	0.00
Total	_	_	_	_	_	_	_	_	_	_	_	1.79	6.28	8.07	0.18	< 0.005	_	14.0

4.5. Waste Emissions by Land Use

4.5.1. Unmitigated

Land Use	TOG	ROG		СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	_	_	_	_	_	_	_	_	_	_	_	66.2	0.00	66.2	6.62	0.00	_	232
Parking Lot	_	_	_	_	_	_	_	_	_	_	_	0.00	0.00	0.00	0.00	0.00	_	0.00
Total	_	_	_	_	_	_	_	_	_	_	_	66.2	0.00	66.2	6.62	0.00	_	232
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	_	_	_	_	_	_	_	_	_	_	_	66.2	0.00	66.2	6.62	0.00	_	232

Parking Lot	_	_	_	_	_	_		_	_		_	0.00	0.00	0.00	0.00	0.00		0.00
Total	_	_	_	_	_	_	_	_	_	_	_	66.2	0.00	66.2	6.62	0.00	_	232
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	_	_	_	_	_	_	_	_	_	_	_	11.0	0.00	11.0	1.10	0.00	_	38.3
Parking Lot	_	_	_	_	_	_	_	_	_	_	_	0.00	0.00	0.00	0.00	0.00	_	0.00
Total	_	_	_	_	_	_	_	_	_	_	_	11.0	0.00	11.0	1.10	0.00	_	38.3

4.5.2. Mitigated

Ontona		(10, 0.0.	,	<i>J</i> , <i>J</i>		7	(,	J ,	. ,	,							
Land Use	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	СО2Т	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	_	_	_	_	_	_	_	_	_	_	_	66.2	0.00	66.2	6.62	0.00	_	232
Parking Lot	_	_	_	_	_	_	_	_	_	_	_	0.00	0.00	0.00	0.00	0.00	_	0.00
Total	_	_	_	_	_	_	_	_	_	_	_	66.2	0.00	66.2	6.62	0.00	_	232
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	_	_	_	_	_	_	_	_	_	_	_	66.2	0.00	66.2	6.62	0.00	_	232
Parking Lot	_	_	_	_	_	_	_	_	_	_	_	0.00	0.00	0.00	0.00	0.00	_	0.00
Total	_	_	_	_	_	_	_	_	_	_	_	66.2	0.00	66.2	6.62	0.00	_	232

Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	_	_	_	_	_	_	_	_	_	_	_	11.0	0.00	11.0	1.10	0.00	_	38.3
Parking Lot	_	_	_	_	_	_	_	_	_	_	_	0.00	0.00	0.00	0.00	0.00	_	0.00
Total	_	_	_	_	_	_	_	_	_	_	_	11.0	0.00	11.0	1.10	0.00	_	38.3

4.6. Refrigerant Emissions by Land Use

4.6.1. Unmitigated

Land Use	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	-	_	_	_	_	_	_	_	_	_	_	_	_	_	_	-	_
Apartme nts Mid Rise	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	1.04	1.04
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	1.04	1.04
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	1.04	1.04
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	1.04	1.04
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	0.17	0.17
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	0.17	0.17

4.6.2. Mitigated

Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

		(1.07 0.1	.,	any, tony			(.											
Land Use	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	1.04	1.04
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	1.04	1.04
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	_	_	-	_	-	_	_	_	_	_	_	_	_	_	_	_	1.04	1.04
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	1.04	1.04
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Apartme nts Mid Rise	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	0.17	0.17
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	0.17	0.17

4.7. Offroad Emissions By Equipment Type

4.7.1. Unmitigated

Equipme	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
nt																		
Туре																		

Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	<u> </u>	_	_	_	<u> </u>	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

4.7.2. Mitigated

Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

Equipme nt Type	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

4.8. Stationary Emissions By Equipment Type

4.8.1. Unmitigated

Equipme Type	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

4.8.2. Mitigated

Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

Equipme nt Type	TOG	ROG	NOx	СО	SO2	PM10E			PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

4.9. User Defined Emissions By Equipment Type

4.9.1. Unmitigated

Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

		(<i>y</i> , (0, <i>y</i> .		· · · · · · · · · · · · · · · · · · ·		.,,	y ,		,							
Equipme nt Type	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

4.9.2. Mitigated

				, ,														
Equipme nt Type	TOG	ROG	NOx	СО	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

4.10. Soil Carbon Accumulation By Vegetation Type

4.10.1. Soil Carbon Accumulation By Vegetation Type - Unmitigated

Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

Ontona			,	J, J-					,									
Vegetatio n	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	СО2Т	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	<u> </u>	_	_		_	_		_	_	_	_	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

4.10.2. Above and Belowground Carbon Accumulation by Land Use Type - Unmitigated

Land Use	TOG			со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total		_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

4.10.3. Avoided and Sequestered Emissions by Species - Unmitigated

Species	TOG	ROG	NOx	CO CO				D/day for PM10T	PM2.5E			BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
		1100	TVOX		302	TWITOL	TIVITUD	TWITOI	T-1012.3L	T-WZ.3D	T-IVIZ.3T	BCO2	NBCOZ	6021	OI I II	NZO	TX	COZE
Daily, Summer (Max)	_		_	_	_	_		_		_	_	_		_		_		
Avoided	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Subtotal	_	_	_	_		_	_	_	_	_	<u> </u>	_	_	_	_	_	_	_
Sequest ered	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Remove d	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Avoided	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Sequest ered	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Remove d	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Avoided	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

Sequest	_	_	_	-	_	_	_	_	_	_	-	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Remove d	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

4.10.4. Soil Carbon Accumulation By Vegetation Type - Mitigated

Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

Vegetatio	TOG							PM10T				BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Winter (Max)		_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

4.10.5. Above and Belowground Carbon Accumulation by Land Use Type - Mitigated

Land Use	TOG	ROG	NOx	со	SO2	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

4.10.6. Avoided and Sequestered Emissions by Species - Mitigated

	TOG	ROG						PM10T		PM2.5D		BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
	TOG	RUG	IVUX		302	PIVITUE	PIVITUD	PIVITUT	PIVIZ.3E	PIVIZ.3D	FIVIZ.51	BCOZ	NBCO2	CO21	СП4	INZU	IV.	COZE
Daily, Summer	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
(Max)																		
Avoided	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Sequest ered	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Remove d	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Avoided	_	_	_	_	_	_	_	_	_		_	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Sequest ered	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

Remove d	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Subtotal	_	_	_	_		_	_	_	_	_	_	_	_	_	_	_	_	_
_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Avoided	_	_	_	_	_	_	<u> </u>	_	<u> </u>	_	_	_	<u> </u>	_	_	_	<u> </u>	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Sequest ered	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Remove d	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

5. Activity Data

5.1. Construction Schedule

Phase Name	Phase Type	Start Date	End Date	Days Per Week	Work Days per Phase	Phase Description
Demolition	Demolition	8/1/2024	8/29/2024	5.00	20.0	_
Site Preparation	Site Preparation	8/30/2024	9/6/2024	5.00	5.00	_
Grading	Grading	9/7/2024	9/18/2024	5.00	8.00	_
Building Construction	Building Construction	9/19/2024	8/7/2025	5.00	230	_
Paving	Paving	8/8/2025	9/2/2025	5.00	18.0	_
Architectural Coating	Architectural Coating	9/3/2025	9/28/2025	5.00	18.0	_

5.2. Off-Road Equipment

5.2.1. Unmitigated

Phase Name	Equipment Type	Fuel Type	Engine Tier	Number per Day	Hours Per Day	Horsepower	Load Factor
Demolition	Rubber Tired Dozers	Diesel	Average	2.00	8.00	367	0.40
Demolition	Concrete/Industrial Saws	Diesel	Average	1.00	8.00	33.0	0.73
Demolition	Excavators	Diesel	Average	3.00	8.00	36.0	0.38
Site Preparation	Rubber Tired Dozers	Diesel	Average	3.00	8.00	367	0.40
Site Preparation	Tractors/Loaders/Backh oes	Diesel	Average	4.00	8.00	84.0	0.37
Grading	Graders	Diesel	Average	1.00	8.00	148	0.41
Grading	Excavators	Diesel	Average	1.00	8.00	36.0	0.38
Grading	Tractors/Loaders/Backh oes	Diesel	Average	3.00	8.00	84.0	0.37
Grading	Rubber Tired Dozers	Diesel	Average	1.00	8.00	367	0.40
Building Construction	Cranes	Diesel	Average	1.00	7.00	367	0.29
Building Construction	Forklifts	Diesel	Average	3.00	8.00	82.0	0.20
Building Construction	Generator Sets	Diesel	Average	1.00	8.00	14.0	0.74
Building Construction	Welders	Diesel	Average	1.00	8.00	46.0	0.45
Building Construction	Tractors/Loaders/Backh oes	Diesel	Average	3.00	7.00	84.0	0.37
Paving	Tractors/Loaders/Backh oes	Diesel	Average	1.00	8.00	84.0	0.37
Paving	Cement and Mortar Mixers	Diesel	Average	2.00	6.00	10.0	0.56
Paving	Pavers	Diesel	Average	1.00	8.00	81.0	0.42
Paving	Paving Equipment	Diesel	Average	2.00	6.00	89.0	0.36
Paving	Rollers	Diesel	Average	2.00	6.00	36.0	0.38
Architectural Coating	Air Compressors	Diesel	Average	1.00	6.00	37.0	0.48

5.2.2. Mitigated

Phase Name	Equipment Type	Fuel Type	Engine Tier	Number per Day	Hours Per Day	Horsepower	Load Factor
Demolition	Rubber Tired Dozers	Diesel	Average	2.00	8.00	367	0.40
Demolition	Concrete/Industrial Saws	Diesel	Average	1.00	8.00	33.0	0.73
Demolition	Excavators	Diesel	Average	3.00	8.00	36.0	0.38
Site Preparation	Rubber Tired Dozers	Diesel	Average	3.00	8.00	367	0.40
Site Preparation	Tractors/Loaders/Backh oes	Diesel	Average	4.00	8.00	84.0	0.37
Grading	Graders	Diesel	Average	1.00	8.00	148	0.41
Grading	Excavators	Diesel	Average	1.00	8.00	36.0	0.38
Grading	Tractors/Loaders/Backh oes	Diesel	Average	3.00	8.00	84.0	0.37
Grading	Rubber Tired Dozers	Diesel	Average	1.00	8.00	367	0.40
Building Construction	Cranes	Diesel	Average	1.00	7.00	367	0.29
Building Construction	Forklifts	Diesel	Average	3.00	8.00	82.0	0.20
Building Construction	Generator Sets	Diesel	Average	1.00	8.00	14.0	0.74
Building Construction	Welders	Diesel	Average	1.00	8.00	46.0	0.45
Building Construction	Tractors/Loaders/Backh oes	Diesel	Average	3.00	7.00	84.0	0.37
Paving	Tractors/Loaders/Backh oes	Diesel	Average	1.00	8.00	84.0	0.37
Paving	Cement and Mortar Mixers	Diesel	Average	2.00	6.00	10.0	0.56
Paving	Pavers	Diesel	Average	1.00	8.00	81.0	0.42
Paving	Paving Equipment	Diesel	Average	2.00	6.00	89.0	0.36
Paving	Rollers	Diesel	Average	2.00	6.00	36.0	0.38
Architectural Coating	Air Compressors	Diesel	Average	1.00	6.00	37.0	0.48

5.3. Construction Vehicles

5.3.1. Unmitigated

Phase Name	Trip Type	One-Way Trips per Day	Miles per Trip	Vehicle Mix
Demolition	—	—	—	—
Demolition	Worker	16.0	18.5	LDA,LDT1,LDT2
Demolition	Vendor	_	10.2	HHDT,MHDT
Demolition				HHDT
	Hauling	84.0	20.0	
Demolition	Onsite truck	_	_	HHDT
Site Preparation	_	_	_	_
Site Preparation	Worker	18.0	18.5	LDA,LDT1,LDT2
Site Preparation	Vendor	2.00	10.2	HHDT,MHDT
Site Preparation	Hauling	0.00	20.0	HHDT
Site Preparation	Onsite truck	_	_	HHDT
Grading	_	_	_	_
Grading	Worker	16.0	18.5	LDA,LDT1,LDT2
Grading	Vendor	2.00	10.2	HHDT,MHDT
Grading	Hauling	0.00	20.0	HHDT
Grading	Onsite truck	_	_	HHDT
Building Construction	_	_	_	_
Building Construction	Worker	120	18.5	LDA,LDT1,LDT2
Building Construction	Vendor	18.0	10.2	HHDT,MHDT
Building Construction	Hauling	0.00	20.0	HHDT
Building Construction	Onsite truck	_	_	HHDT
Paving	_	_	_	_
Paving	Worker	20.0	18.5	LDA,LDT1,LDT2
Paving	Vendor	_	10.2	HHDT,MHDT

Paving	Hauling	0.00	20.0	HHDT
Paving	Onsite truck	_	_	HHDT
Architectural Coating	_	_	_	_
Architectural Coating	Worker	24.0	18.5	LDA,LDT1,LDT2
Architectural Coating	Vendor	_	10.2	HHDT,MHDT
Architectural Coating	Hauling	0.00	20.0	HHDT
Architectural Coating	Onsite truck	_	_	HHDT

5.3.2. Mitigated

Phase Name	Trip Type	One-Way Trips per Day	Miles per Trip	Vehicle Mix
Demolition	_	_	_	_
Demolition	Worker	16.0	18.5	LDA,LDT1,LDT2
Demolition	Vendor	_	10.2	HHDT,MHDT
Demolition	Hauling	84.0	20.0	HHDT
Demolition	Onsite truck	_	_	HHDT
Site Preparation	_	_	_	_
Site Preparation	Worker	18.0	18.5	LDA,LDT1,LDT2
Site Preparation	Vendor	2.00	10.2	HHDT,MHDT
Site Preparation	Hauling	0.00	20.0	HHDT
Site Preparation	Onsite truck	_	_	HHDT
Grading	_	_	_	_
Grading	Worker	16.0	18.5	LDA,LDT1,LDT2
Grading	Vendor	2.00	10.2	HHDT,MHDT
Grading	Hauling	0.00	20.0	HHDT
Grading	Onsite truck	_	_	HHDT
Building Construction	_	_	_	_
Building Construction	Worker	120	18.5	LDA,LDT1,LDT2

Building Construction	Vendor	18.0	10.2	HHDT,MHDT
Building Construction	Hauling	0.00	20.0	HHDT
Building Construction	Onsite truck	_	_	HHDT
Paving	_	_	_	_
Paving	Worker	20.0	18.5	LDA,LDT1,LDT2
Paving	Vendor	_	10.2	HHDT,MHDT
Paving	Hauling	0.00	20.0	HHDT
Paving	Onsite truck	_	_	HHDT
Architectural Coating	_	_	_	_
Architectural Coating	Worker	24.0	18.5	LDA,LDT1,LDT2
Architectural Coating	Vendor	_	10.2	HHDT,MHDT
Architectural Coating	Hauling	0.00	20.0	HHDT
Architectural Coating	Onsite truck	_	_	HHDT

5.4. Vehicles

5.4.1. Construction Vehicle Control Strategies

Non-applicable. No control strategies activated by user.

5.5. Architectural Coatings

Phase Name	Residential Interior Area Coated (sq ft)	Residential Exterior Area Coated (sq ft)	Non-Residential Interior Area Coated (sq ft)	Non-Residential Exterior Area Coated (sq ft)	Parking Area Coated (sq ft)
Architectural Coating	295,075	98,358	0.00	0.00	4,051

5.6. Dust Mitigation

5.6.1. Construction Earthmoving Activities

Phase Name	Material Imported (cy)	Material Exported (cy)	Material Demolished (Ton of	Acres Paved (acres)
			Debris)	

Demolition	0.00	0.00	0.00	6,706	_
Site Preparation	_	_	7.50	0.00	_
Grading	_	_	8.00	0.00	_
Paving	0.00	0.00	0.00	0.00	1.55

5.6.2. Construction Earthmoving Control Strategies

Control Strategies Applied	Frequency (per day)	PM10 Reduction	PM2.5 Reduction
Water Exposed Area	2	61%	61%

5.7. Construction Paving

Land Use	Area Paved (acres)	% Asphalt
Apartments Mid Rise	_	0%
Parking Lot	1.55	100%

5.8. Construction Electricity Consumption and Emissions Factors

kWh per Year and Emission Factor (lb/MWh)

Year	kWh per Year	CO2	CH4	N2O
2024	0.00	532	0.03	< 0.005
2025	0.00	532	0.03	< 0.005

5.9. Operational Mobile Sources

5.9.1. Unmitigated

Land Use Type	Trips/Weekday	Trips/Saturday	Trips/Sunday	Trips/Year	VMT/Weekday	VMT/Saturday	VMT/Sunday	VMT/Year
Apartments Mid Rise	903	815	679	313,337	7,800	7,040	5,865	2,706,598
Parking Lot	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

5.9.2. Mitigated

Land Use Type	Trips/Weekday	Trips/Saturday	Trips/Sunday	Trips/Year	VMT/Weekday	VMT/Saturday	VMT/Sunday	VMT/Year
Apartments Mid Rise	455	411	342	157,860	3,930	3,547	2,955	1,363,595
Parking Lot	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

5.10. Operational Area Sources

5.10.1. Hearths

5.10.1.1. Unmitigated

Hearth Type	Unmitigated (number)
Apartments Mid Rise	_
Wood Fireplaces	0
Gas Fireplaces	0
Propane Fireplaces	0
Electric Fireplaces	0
No Fireplaces	166
Conventional Wood Stoves	0
Catalytic Wood Stoves	0
Non-Catalytic Wood Stoves	0
Pellet Wood Stoves	0

5.10.1.2. Mitigated

Hearth Type	Unmitigated (number)
Apartments Mid Rise	_
Wood Fireplaces	0
Gas Fireplaces	0

Propane Fireplaces	0
Electric Fireplaces	0
No Fireplaces	166
Conventional Wood Stoves	0
Catalytic Wood Stoves	0
Non-Catalytic Wood Stoves	0
Pellet Wood Stoves	0

5.10.2. Architectural Coatings

Residential Interior Area Coated (sq ft)	Residential Exterior Area Coated (sq ft)	Non-Residential Interior Area Coated (sq ft)	Non-Residential Exterior Area Coated (sq ft)	Parking Area Coated (sq ft)
295074.8999999997	98,358	0.00	0.00	4,051

5.10.3. Landscape Equipment

Season	Unit	Value
Snow Days	day/yr	0.00
Summer Days	day/yr	250

5.10.4. Landscape Equipment - Mitigated

Season	Unit	Value
Snow Days	day/yr	0.00
Summer Days	day/yr	250

5.11. Operational Energy Consumption

5.11.1. Unmitigated

Electricity (kWh/yr) and CO2 and CH4 and N2O and Natural Gas (kBTU/yr)

Land Use	Electricity (kWh/yr)	CO2	CH4	N2O	Natural Gas (kBTU/yr)
Apartments Mid Rise	608,528	346	0.0330	0.0040	1,843,736
Parking Lot	59,146	346	0.0330	0.0040	0.00

5.11.2. Mitigated

Electricity (kWh/yr) and CO2 and CH4 and N2O and Natural Gas (kBTU/yr)

Land Use	Electricity (kWh/yr)	CO2	CH4	N2O	Natural Gas (kBTU/yr)
Apartments Mid Rise	571,722	346	0.0330	0.0040	1,843,736
Parking Lot	59,146	346	0.0330	0.0040	0.00

5.12. Operational Water and Wastewater Consumption

5.12.1. Unmitigated

Land Use	Indoor Water (gal/year)	Outdoor Water (gal/year)
Apartments Mid Rise	6,229,258	283,766
Parking Lot	0.00	0.00

5.12.2. Mitigated

Land Use	Indoor Water (gal/year)	Outdoor Water (gal/year)
Apartments Mid Rise	5,651,806	283,766
Parking Lot	0.00	0.00

5.13. Operational Waste Generation

5.13.1. Unmitigated

· · · · · ·	And the second s	
Land Use	Waste (ton/year)	Cogeneration (kWh/year)
Zana ecc	reacto (torn your)	ought and (attriffed)

Apartments Mid Rise	123	_
Parking Lot	0.00	_

5.13.2. Mitigated

Land Use	Waste (ton/year)	Cogeneration (kWh/year)
Apartments Mid Rise	123	_
Parking Lot	0.00	_

5.14. Operational Refrigeration and Air Conditioning Equipment

5.14.1. Unmitigated

Land Use Type	Equipment Type	Refrigerant	GWP	Quantity (kg)	Operations Leak Rate	Service Leak Rate	Times Serviced
Apartments Mid Rise	Average room A/C & Other residential A/C and heat pumps	R-410A	2,088	< 0.005	2.50	2.50	10.0
Apartments Mid Rise	Household refrigerators and/or freezers	R-134a	1,430	0.12	0.60	0.00	1.00

5.14.2. Mitigated

Land Use Type	Equipment Type	Refrigerant	GWP	Quantity (kg)	Operations Leak Rate	Service Leak Rate	Times Serviced
Apartments Mid Rise	Average room A/C & Other residential A/C and heat pumps	R-410A	2,088	< 0.005	2.50	2.50	10.0
Apartments Mid Rise	Household refrigerators and/or freezers	R-134a	1,430	0.12	0.60	0.00	1.00

5.15. Operational Off-Road Equipment

5.15.1. Unmitigated

Final Acres

Equipment Type	Fuel Type	Engine Tier	Number per Day	Hours Per Day	Horsepower	Load Factor
5.15.2. Mitigated						
Equipment Type	Fuel Type	Engine Tier	Number per Day	Hours Per Day	Horsepower	Load Factor
5.16. Stationary	/ Sources					
5.16.1. Emergenc	y Generators and Fire	e Pumps				
Equipment Type	Fuel Type	Number per Day	Hours per Day	Hours per Year	Horsepower	Load Factor
5.16.2. Process Boilers						
Equipment Type	Fuel Type	Number	Boiler Rat	ing (MMBtu/hr)	Daily Heat Input (MMBtu/day)	Annual Heat Input (MMBtu/yr)
5.17. User Defii	ned					
Equipment Type			Fuel Type			
5.18. Vegetation	n					
5.18.1. Land Use	Change					
5.18.1.1. Unmitiga	ated					
Vegetation Land Use Ty	ype	Vegetation Soil Type	Initial Acre	es	Final Acres	
5.18.1.2. Mitigated	d					

Initial Acres

Vegetation Soil Type

Vegetation Land Use Type

5.18.1. Biomass Cover Type

5.18.1.1. Unmitigated

Biomass Cover Type Initial Acres Final Acres

5.18.1.2. Mitigated

Biomass Cover Type	Initial Acres	Final Acres
Biomass Cover Type	Initial Acres	Trinai Acres

5.18.2. Sequestration

5.18.2.1. Unmitigated

Tree Type	Number	Electricity Saved (kWh/year)	Natural Gas Saved (btu/year)

5.18.2.2. Mitigated

_				
	Tree Type	Number	Electricity Saved (kWh/year)	Natural Gas Saved (btu/year)
	nee type	Number	Liectricity Saved (KWII/year)	Natural Gas Saveu (blu/year)

6. Climate Risk Detailed Report

6.1. Climate Risk Summary

Cal-Adapt midcentury 2040–2059 average projections for four hazards are reported below for your project location. These are under Representation Concentration Pathway (RCP) 8.5 which assumes GHG emissions will continue to rise strongly through 2050 and then plateau around 2100.

Climate Hazard	Result for Project Location	Unit		
Temperature and Extreme Heat	10.5	annual days of extreme heat		
Extreme Precipitation	4.00	annual days with precipitation above 20 mm		
Sea Level Rise	_	meters of inundation depth		
Wildfire	0.00	annual hectares burned		

Temperature and Extreme Heat data are for grid cell in which your project are located. The projection is based on the 98th historical percentile of daily maximum/minimum temperatures from observed historical data (32 climate model ensemble from Cal-Adapt, 2040–2059 average under RCP 8.5). Each grid cell is 6 kilometers (km) by 6 km, or 3.7 miles (mi) by 3.7 mi.

Extreme Precipitation data are for the grid cell in which your project are located. The threshold of 20 mm is equivalent to about ¾ an inch of rain, which would be light to moderate rainfall if received over a full day or heavy rain if received over a period of 2 to 4 hours. Each grid cell is 6 kilometers (km) by 6 km, or 3.7 miles (mi) by 3.7 mi.

Sea Level Rise data are for the grid cell in which your project are located. The projections are from Radke et al. (2017), as reported in Cal-Adapt (Radke et al., 2017, CEC-500-2017-008), and consider inundation location and depth for the San Francisco Bay, the Sacramento-San Joaquin River Delta and California coast resulting different increments of sea level rise coupled with extreme storm events. Users may select from four scenarios to view the range in potential inundation depth for the grid cell. The four scenarios are: No rise, 0.5 meter, 1.41 meters

Wildfire data are for the grid cell in which your project are located. The projections are from UC Davis, as reported in Cal-Adapt (2040–2059 average under RCP 8.5), and consider historical data of climate, vegetation, population density, and large (> 400 ha) fire history. Users may select from four model simulations to view the range in potential wildfire probabilities for the grid cell. The four simulations make different assumptions about expected rainfall and temperature are: Warmer/drier (HadGEM2-ES), Cooler/wetter (CNRM-CM5), Average conditions (CanESM2), Range of different rainfall and temperature possibilities (MIROC5). Each grid cell is 6 kilometers (km) by 6 km, or 3.7 miles (mi) by 3.7 mi.

6.2. Initial Climate Risk Scores

Climate Hazard	Exposure Score	Sensitivity Score	Adaptive Capacity Score	Vulnerability Score
Temperature and Extreme Heat	1	0	0	N/A
Extreme Precipitation	N/A	N/A	N/A	N/A
Sea Level Rise	1	0	0	N/A
Wildfire	1	0	0	N/A
Flooding	N/A	N/A	N/A	N/A
Drought	N/A	N/A	N/A	N/A
Snowpack Reduction	N/A	N/A	N/A	N/A
Air Quality Degradation	0	0	0	N/A

The sensitivity score reflects the extent to which a project would be adversely affected by exposure to a climate hazard. Exposure is rated on a scale of 1 to 5, with a score of 5 representing the greatest exposure.

The adaptive capacity of a project refers to its ability to manage and reduce vulnerabilities from projected climate hazards. Adaptive capacity is rated on a scale of 1 to 5, with a score of 5 representing the greatest ability to adapt.

The overall vulnerability scores are calculated based on the potential impacts and adaptive capacity assessments for each hazard. Scores do not include implementation of climate risk reduction measures.

6.3. Adjusted Climate Risk Scores

Climate Hazard	Exposure Score	Sensitivity Score	Adaptive Capacity Score	Vulnerability Score
Temperature and Extreme Heat	1	1	1	2
Extreme Precipitation	N/A	N/A	N/A	N/A
Sea Level Rise	1	1	1	2

Wildfire	1	1	1	2
Flooding	N/A	N/A	N/A	N/A
Drought	N/A	N/A	N/A	N/A
Snowpack Reduction	N/A	N/A	N/A	N/A
Air Quality Degradation	1	1	1	2

The sensitivity score reflects the extent to which a project would be adversely affected by exposure to a climate hazard. Exposure is rated on a scale of 1 to 5, with a score of 5 representing the greatest exposure.

The adaptive capacity of a project refers to its ability to manage and reduce vulnerabilities from projected climate hazards. Adaptive capacity is rated on a scale of 1 to 5, with a score of 5 representing the greatest ability to adapt.

The overall vulnerability scores are calculated based on the potential impacts and adaptive capacity assessments for each hazard. Scores include implementation of climate risk reduction measures.

6.4. Climate Risk Reduction Measures

7. Health and Equity Details

7.1. CalEnviroScreen 4.0 Scores

The maximum CalEnviroScreen score is 100. A high score (i.e., greater than 50) reflects a higher pollution burden compared to other census tracts in the state.

Indicator	Result for Project Census Tract
Exposure Indicators	
AQ-Ozone	57.0
AQ-PM	71.8
AQ-DPM	71.9
Drinking Water	63.5
Lead Risk Housing	53.7
Pesticides	6.34
Toxic Releases	90.4
Traffic	95.9
Effect Indicators	_
CleanUp Sites	58.2

Groundwater	14.3
Haz Waste Facilities/Generators	46.4
Impaired Water Bodies	0.00
Solid Waste	89.3
Sensitive Population	_
Asthma	30.2
Cardio-vascular	24.4
Low Birth Weights	16.4
Socioeconomic Factor Indicators	_
Education	61.2
Housing	60.9
Linguistic	52.0
Poverty	44.9
Unemployment	22.6

7.2. Healthy Places Index Scores

The maximum Health Places Index score is 100. A high score (i.e., greater than 50) reflects healthier community conditions compared to other census tracts in the state.

Indicator	Result for Project Census Tract
Economic	_
Above Poverty	40.39522649
Employed	80.26433979
Median HI	43.7058899
Education	_
Bachelor's or higher	39.70229693
High school enrollment	100
Preschool enrollment	22.41755422
Transportation	_

Auto Access	49.51879892
Active commuting	54.04850507
Social	_
2-parent households	46.6059284
Voting	49.15950212
Neighborhood	_
Alcohol availability	27.11407674
Park access	27.44770948
Retail density	57.44899269
Supermarket access	53.70204029
Tree canopy	19.79982035
Housing	_
Homeownership	39.93327345
Housing habitability	34.03054023
Low-inc homeowner severe housing cost burden	45.10458103
Low-inc renter severe housing cost burden	60.47735147
Uncrowded housing	15.62941101
Health Outcomes	_
Insured adults	4.953163095
Arthritis	36.0
Asthma ER Admissions	74.4
High Blood Pressure	53.6
Cancer (excluding skin)	34.5
Asthma	34.7
Coronary Heart Disease	31.2
Chronic Obstructive Pulmonary Disease	25.1
Diagnosed Diabetes	50.0

Life Expectancy at Birth	41.0
Cognitively Disabled	91.4
Physically Disabled	65.4
Heart Attack ER Admissions	88.7
Mental Health Not Good	37.4
Chronic Kidney Disease	35.4
Obesity	53.5
Pedestrian Injuries	77.8
Physical Health Not Good	37.9
Stroke	34.3
Health Risk Behaviors	_
Binge Drinking	25.3
Current Smoker	36.3
No Leisure Time for Physical Activity	38.1
Climate Change Exposures	_
Wildfire Risk	0.0
SLR Inundation Area	0.0
Children	26.6
Elderly	44.5
English Speaking	15.5
Foreign-born	77.6
Outdoor Workers	12.2
Climate Change Adaptive Capacity	_
Impervious Surface Cover	22.4
Traffic Density	97.7
Traffic Access	23.0
Other Indices	

Hardship	68.8
Other Decision Support	_
2016 Voting	77.0

7.3. Overall Health & Equity Scores

Metric	Result for Project Census Tract
CalEnviroScreen 4.0 Score for Project Location (a)	50.0
Healthy Places Index Score for Project Location (b)	40.0
Project Located in a Designated Disadvantaged Community (Senate Bill 535)	No
Project Located in a Low-Income Community (Assembly Bill 1550)	Yes
Project Located in a Community Air Protection Program Community (Assembly Bill 617)	No

a: The maximum CalEnviroScreen score is 100. A high score (i.e., greater than 50) reflects a higher pollution burden compared to other census tracts in the state.

7.4. Health & Equity Measures

No Health & Equity Measures selected.

7.5. Evaluation Scorecard

Health & Equity Evaluation Scorecard not completed.

7.6. Health & Equity Custom Measures

No Health & Equity Custom Measures created.

8. User Changes to Default Data


Screen	Justification
Land Use	Land uses based on proposed project: 166 dwelling units (164 of which are affordable senior) and 172 parking spaces on 3.85 acres
Construction: Trips and VMT	Rounded default trips up to nearest even number. Added vendor trips to site preparation and grading phases to account for water trucks

b: The maximum Health Places Index score is 100. A high score (i.e., greater than 50) reflects healthier community conditions compared to other census tracts in the state.

Operations: Hearths

No fireplaces or wood stoves assumed

Attachment 6. Coastal Zone Management Map



Attachment 7. Phase I Environmental Site Assessment

Attachment 8. Lead Based Paint & Asbestos Survey

5261 West Imperial Highway Los Angeles, California 90045 T (310) 854 - 6300 F (310) 854 - 0199 efiglobal.com

efi global

August 31, 2020

Leatha Clark USA Properties Fund, Inc. 3200 Douglas Boulevard, Suite 200 Roseville, CA 95661

Subject: Pre-Renovation Asbestos and Lead Assessment

1800 E. La Veta Avenue, Orange, CA 92866

EFI Job Number: 045.04081

1. Introduction

USA Properties Fund, Inc., (referred to hereunder as the client) retained EFI Global to perform pre-renovation sampling of building materials suspected to contain asbestos and surface coatings suspected to contain lead (i.e., suspect materials) within the subject property. The purpose of the assessment was to identify whether asbestos-containing materials (ACM) and/or lead-based paint (LBP) were present so they may be properly managed prior to renovation of the structure. The subject property is approximately 2.6 total acres in size with one single-story commercial building (i.e., Building 1) and one unoccupied residential structure (i.e., Building 2), which total approximately 37,500 square feet (ft²). Building 1 is a physical rehabilitation center and building 2 consists a vacant residential house; both structures were included in this assessment.

The pre-demolition assessment was performed on August 7 and 8, 2020, by Heriberto Romero, a Cal/OSHA Certified Site Surveillance Technician (CSST, DOSH Cert No. 15-5572) and Jacob Pulliam, a California Department of Health (CDPH) Lead Sampling Technician (LST, Cert. No. LRC-00001469). The work was performed under the supervision of Benjamin Curry, a DOSH Certified Asbestos Consultant (CAC, DOSH Cert No. 09-4549) and CDPH Lead Inspector / Assessor (LIA, Cert. No. LRC-00000208).

2. Asbestos Assessment

The purpose of this assessment was to conduct bulk sampling in order to determine the presence of ACM and/or regulated asbestos containing materials (RACM) at the subject property so they may be properly abated prior to demolition. The scope of this assessment included reviewing building and/or previous investigation records, visually identifying homogeneous sample areas, collecting bulk samples of building materials suspected to contain asbestos, recording the friability and condition of suspect building materials, interpreting the laboratory results, and producing a written report of findings and recommendations. EFI requested but was not provided copies of previous investigation reports; it is assumed there are no such documents.

The sampling was performed in accordance with requirements of the following regulations:

- Asbestos Hazard Emergency Response Act (AHERA); 40 CFR 763 Subpart E
- Asbestos School Hazard Abatement Reauthorization Act (ASHARA); Section 206 of the Toxic Substance Control Act
- National Emissions Standards for Hazardous Air Pollutants (NESHAPS); 40 CFR 61 Subpart M.
- South Coast Air Quality Management District (SCAQMD) Rule 1403

This report is a record of activities performed, observations made, analytical results obtained, and recommendations to date.

2.1 Asbestos Results Summary

The laboratory results indicate that the following materials contain asbestos above the threshold limit of 1%, and are to be treated and disposed of as ACM:

Building 1: Main Structure -

- Drywall Joint Compound Interior Throughout (2 -3% Chrysotile), samples 14A-14I & 40A-40B
- Sink Undercoating Room 149 (3% Chrysotile), samples, 19A-19B
- Tan Carpet Adhesive Changing Room 1 (4% Chrysotile), samples; 23A-23B
- Gray Pebble VSF See Table (15% Chrysotile), samples; 26A-26C
- 12" Gray w/ White VFT Utility Room 2 (6% Chrysotile), samples 30A-30B
- Black Roofing Mastic North Roof (4% Chrysotile), samples, 46A-46C
- Gray HVAC Coating Center Roof HVAC Ducting (4% Chrysotile), samples; 49A-49C
- White Vent Coating Center Roof HVAC Ducting (5% Chrysotile), samples; 50A-50C
- Penetration Mastic Center Roof (5% Chrysotile), samples 51A-51C

Building 2: Small House Structure -

- Beige VFT Closet 1 (20 30% Chrysotile), samples 9A-9B
- Tan VFT & Mastic Kitchen (2 3% Chrysotile), samples; 11A-11B

The following materials were further analyzed via the 1,000-Point Count method. The laboratory results indicate that the following materials contain between 0.10 and 1.0% asbestos and should be treated and disposed of as ACCM:

Main Structure -

Stucco – Exterior (0.2% Chrysotile), samples 22A-22G

Each of the above materials were found to be in good condition at the time of the assessment. All other building materials sampled during this assessment were found to be none detected for asbestos.

Please refer to Tables 2 and 3 for a list of ACM Homogenous Materials, their locations and approximate quantities. Analytical data can be found in Appendix II.

2.2 Methodology

All samples were collected using a clean knife, chisel or the appropriate sampling tool(s). Each sample was extracted carefully so as not to disturb adjacent materials while still penetrating through all layers of the material sampled. Each sample was sealed in the appropriately sized plastic baggie and the bag then labeled with a unique identification number. The sample number, description, and location were then recorded on a log and plotted on a floor plan of the structure or area. Sampling tools were cleaned after collecting each sample. Any excess dust or debris from the sample location was cleaned using a moistened cloth. Whenever possible, samples were collected from previously damaged portions of the material in order to minimize damage to the material.



A total of 147 samples were submitted to EMSL Analytical in Cinnaminson, New Jersey. EMSL is accredited under the NIST/NVLAP program for asbestos in bulk material by polarized light microscopy (PLM) and the State of California for asbestos analysis. NIST/NVLAP lab code 101048-0, California ELAP Certificate No. 1406.

The analyses of the samples in this report were performed using PLM in accordance with EPA method 600/R-93/116. The phase abundances provided are visually estimated and expressed as percent area. Total percentage of sample constituents may total greater than 100 due to trace amounts. The limit of detection for this analytical method is less than one percent (< 1%). In multilayer samples, unless otherwise specified, the asbestos concentration is reported for the layer where asbestos is found. These results lie within the statistical limits of variability calculated for standard reference samples routinely analyzed in the laboratory. On a per sample basis, the accuracy and precision of the results depend on the type of sample and its asbestos content.

Some of the samples in this report were further analyzed using the point count method. These analyses were performed using gravimetric matrix reduction and PLM in accordance with the EPA method 600/R-93/116 July 1993. The asbestos concentration was determined using the semi-quantitative point count method. On a per sample basis, the accuracy and precision of point count results are not known. The result should lie within the statistical limits of variability calculated for standard reference samples routinely analyzed in the laboratory using the point count method. The limit of detection for this analytical method is 0.25 percent using 400 points and 0.10 percent using 1000 points (visual area estimates).

2.3 Regulatory Limits

Government agencies have promulgated different regulatory threshold levels to classify materials containing asbestos. The levels of asbestos content and the terms used to classify them differ. Listed below are the current regulatory agencies that have defined materials containing asbestos, along with the respective action levels, regulatory terminology and applicability:

Table 1: Applicable Regulations

Agency / Regulation	Regulatory Code	Action Level (% Weight)	Terminology	Applicability
CAL OSHA	8 CCR Section 341.6(c)	> 0.1%	Asbestos-Containing Construction Material (ACCM)	Removal Work in California
Fed OSHA	29 CFR Section 1926.1101(b)	> 1.0%	Asbestos-Containing Material (ACM)	Removal Work in United States
NESHAP	40 CFR Part 61, Subpart M	> 1.0% and Friable	Regulated Asbestos- Containing Material (RACM)	Transport and Disposal of Waste in United States
SCAQMD	RULE 1403	>1.0%	Asbestos-Containing Material (ACM)	Removal Work, Transport and Disposal of Waste in SCAQMD District



2.4 Homogeneous Sample Materials Table

Homogeneous materials are defined as surfacing materials, thermal system insulation (TSI), or miscellaneous materials that are uniform in color and texture. Homogeneous sample areas are the areas where homogeneous materials are located. Multiple sample locations are selected within each homogeneous sample area to be a true representation of each homogeneous material. Typically, a minimum of three (3) samples must be collected from each homogeneous area when sampling materials that may have variable asbestos content because it was batch mixed or applied by different contractors. High asbestos content variability is especially true of surfacing materials (i.e., sprayed-on and/or troweled-on materials like plaster, fireproofing, and acoustic ceiling plaster) and TSI used to insulate pipes, boilers, tanks or ducts to prevent heat loss. As many as 9 samples may be collected of surfacing materials when they cover large surface areas.

Materials that appear to be homogeneous may in fact be different materials, installed at different times and have different material content in terms of asbestos; only laboratory testing can determine whether they are really the same homogeneous area. The below table presents the homogeneous materials identified during the assessment and the asbestos content of those identified materials. The homogeneous materials found to contain asbestos are listed in **bold** type with ACM highlighted in **yellow**.

Table 2: Homogenous Building Materials & Asbestos Content: Building 2 (Small House Structure)

Homogenous Material Number	Material Description	Location	Asbestos Content (% Weight)	Material Quantity *	Friability **	Condition
1	Drywall & Joint Compound	Interior	None Detected			
2	Wallpaper	Bedroom 1	None Detected			
3	Window Putty	Exterior	None Detected			
4	Sink Undercoating	Kitchen	None Detected			
5	Mastic for FRP	Restroom 2	None Detected			
6	4" White Ceramic Tiles & Mastic	Living Room Countertop	None Detected			
7	White Ceramic Floor Tile, Mortar & Grout	Restroom 1 Restroom 2	None Detected			
8	Tan VFT & Mastic	Bedroom 1 Under Wood Flooring)	None Detected			
9	Beige VFT	Closet 1	20-30% Chrysotile	36 SF	Non- Friable	Good
3	Mastic for Beige VFT	Closet 1	None Detected			
10	Brown VSF & Mastic	Closet 3	None Detected			



Homogenous Material Number	Material Description	Location	Asbestos Content (% Weight)	Material Quantity *	Friability **	Condition
11	Tan VFT & Mastic	Kitchen	2-3% Chrysotile	155 SF	Non- Friable	Good
12	Roof Core	Roof	None Detected			
13	Roofing Mastic	Roof	None Detected			

^{*} All quantities are approximations and should be verified by an abatement contractor.

- Table 3: Homogenous Building Materials & Asbestos Content: Building 1 (Main Building)

Homogenous Material Number	Material Description	Location	Asbestos Content (% Weight)	Material Quantity *	Friability **	Condition
14	Drywall & Skim Coat	2 nd Floor 1 st Floor	None Detected			
14	Drywall Joint 2 nd Flo		2-3% Chrysotile	126,000 SF	Non- Friable	Good
15	Acoustic Texture Ceiling	1 st Floor	None Detected			
16	Brown Covebase & Mastic	Utility Room 6 Utility Room 7 Room 106 Room 110 Room 159	None Detected			
17	1'x1' Ceiling Tiles	Room 158 Room 106	None Detected			
18	2'x4' Ceiling Tiles	Room 202 Room 226	None Detected			
19	Sink Undercoating	Room 149	3% Chrysotile	9 SF	Non- Friable	Good
20	White Sink Caulking	Restroom 13 Restroom 2	None Detected			
21	Gray Stone Grout	Lobby Exterior	None Detected			
22	Stucco	Exterior	0.2% Chrysotile	16,000 SF	Non- Friable	Good
23	Tan Carpet Adhesive	Changing Room 1	4% Chrysotile	72 SF	Non- Friable	Good
24	White Speckled VSF & Mastic	Room 126	None Detected			
25	Green Speckled VSF & Mastic	Restroom 3	None Detected			



^{**} Non-friable materials may be rendered friable during removal by mechanical or other aggressive methods.

Homogenous Material Number	Material Description	Location	Asbestos Content (% Weight)	Material Quantity *	Friability **	Condition
26	Gray Pebble VSF	Utility Room 7 Room 149	15% Chrysotile	750	Non- Friable	Good
20	Mastic for Gray Pebble VSF	Utility Room 7 Room 149	None Detected			
27	12" White VFT & Mastic	Room 106 Room 158 Room 159	None Detected			
28	12" Cream VFT & Mastic	Room 250 2 nd Floor Hall	None Detected			
29	12" Blue Marbled VFT & Mastic	Room 155 Room 158	None Detected			
	12" Gray with White VFT	Utility Room 2	6% Chrysotile	150	Non- Friable	Good
30	Mastic for 12" Gray with White VFT	Utility Room 2	None Detected			
31	12" Brown Marble VFT Mastic	Room 137	None Detected			
32	12" Green Marble VFT & Mastic	1 st Floor Lobby 2 nd Floor Staff Lounge	None Detected			
33	12" Gray VFT & Mastic	2 nd Floor Staff Lounge Windowed Hallway Outside Room 248	None Detected			
34	Light Green VFT & Mastic	Lobby	None Detected			
35	Floor Texture Coating	Room 130	None Detected			
36	1' White Tile, Grout & Mastic	Restroom 12 Restroom 13	None Detected			
37	1' Tan Tile, Grout & Mastic	Restroom 9 Restroom 10	None Detected			
38	4" Blue Tiles, Grout & Mastic	Restroom 3 Restroom 12	None Detected			
39	4" Blue Tiles, Grout & Mastic	Changing Room Restroom 5	None Detected			
40	4"x4" Pink Wall Tiles and Mastic	Restroom 4 Restroom 6	None Detected			



Homogenous Material Number	Material Description	Location	Asbestos Content (% Weight)	Material Quantity *	Friability **	Condition
40	Drywall Joint Compound Behind 4"x4" Pink Wall Tiles	Restroom 4 Restroom 6	2% Chrysotile	See Homogenous #14	Non- Friable	Good
41	4" Brown Tiles, Grout & Mastic	Kitchen 16D Utility Room 6	None Detected			
42	4" Salmon Tiles & Grout	Restroom 13 Utility Room 6	None Detected			
43	4"x4" Black Wall Tiles & Mastic	Restroom 9	None Detected			
44	Roof Core	North Roof	None Detected			
45	Black / White Penetration Mastic	North Roof	< 0.1% Chrysotile			
46	Black Roofing Mastic	North Roof	4% Chrysotile	120 SF	Non- Friable	Good
47	Gray HVAC Mastic	North Roof – HVAC Ducting	None Detected			
48	White HVAC Mastic	North Roof – HVAC Ducting	None Detected			
49	Gray HVAC Coating	Center Roof – HVAC Ducting	4% Chrysotile	90 SF	Non- Friable	Good
50	White Vent Coating	Center Roof – HVAC Ducting	5% Chrysotile	65 SF	Non- Friable	Good
51	Penetration Mastic	Center Roof	5% Chrysotile	85 SF	Non- Friable	Good
52	Roof Core	Center Roof	None Detected			

^{*} All quantities are approximations and should be verified by an abatement contractor.

2.5 Asbestos Recommendations

If materials found to contain asbestos and/or presumed to contain asbestos may be impacted during renovation or demolition activities, by law, they must first be abated and properly disposed of by a licensed asbestos abatement contractor prior to such work. Contractors are licensed for asbestos-related work by the California Department of Industrial Relations (DIR) Department of Occupational Safety and Health (DOSH). A list of contractors with current licenses may be found at:

https://www.dir.ca.gov/databases/doshacru/acrusearch.html.

Any suspect materials, that are not identified above and may be impacted during work activities, must be presumed to contain asbestos until laboratory analysis of an adequate number of samples proves otherwise.



^{**} Non-friable materials may be rendered friable during removal by mechanical or other aggressive methods.

It is highly recommended that abatement monitoring be performed by the asbestos consultant if asbestos abatement is to be performed while non-abatement persons (employees, tenants, other building occupants, or general public) are present in adjacent areas. Abatement monitoring includes the collection of air samples in adjacent areas to demonstrate that asbestos fibers are not migrating out of the regulated areas. In addition to air sampling, the monitoring includes oversight of the abatement contractor to ensure that the work is being conducted in compliance with all applicable regulations and in accordance with the scope of work and abatement specifications. Such abatement monitoring services can reduce risk and limit the legal liabilities of the building owner.

3. Lead-Based Paint Assessment

A total of 500 XRF readings were collected to test painted and coated surfaces for lead-based paint (LBP). The results are summarized in Section 3.1 and the table of results attached in Appendix III.

3.1 Lead Results Summary

The following building components were found to be coated with LBP:

Building 1: Main Structure -

- White Metal Drain Room 160 1 mg/cm²
- White Ceramic Wall Restroom #14 23.5 mg/cm²
- Pink Ceramic Wall Tile Restroom #6 21.8 mg/cm²
- Blue Ceramic Wall Restroom #5 21.7 mg/cm²
- White Ceramic Wall Tile Restroom #3 21.1 mg/cm²
- Pink Ceramic Wall Tile Restroom #3 25.9 mg/cm²
- Blue Ceramic Wall Tile Changing Room 22.8 mg/cm²
- White Porcelain Sink Room 105 B 30 mg/cm²
- Tan Ceramic Wall Tile Restroom #1 12.7 mg/cm²
- Tan Ceramic Wall Restroom #2 22.3 mg/cm²
- White Porcelain Sink Room 142 56 mg/cm²
- Light-Blue Ceramic Tile Pool 130 18.9 mg/cm²
- Tan Ceramic Wall Tile Women's Restroom 5.3 mg/cm²
- Blue Ceramic Wall Men's Restroom 17.8 mg/cm²
- Pink Ceramic Tile Women's Restroom 23.4 mg/cm²
- White Ceramic Tile 209 29.4 mg/cm²

Building 2: Small House Structure -

- Tan Wood Wall Kitchen 1.3 to 2.0 mg/cm²
- Blue Wood Window Frame Bedroom #3 2.8 mg/cm²
- Blue Wood Window Seal Bedroom #3 2 mg/cm²
- White Wood Door Hallway 4.5 mg/cm²
- Brown Wood Wall Exterior 5.3 mg/cm²
- Dark Brown Wood Trim Exterior 3 mg/cm²
- Dark Brown Wood Window-Frame Exterior 6.4 mg/cm²
- Dark Brown Wood Window Seal Exterior 3.2 mg/cm²
- Brown Wood Wall Exterior 10 mg/cm²
- Brown Wood Door Frame Exterior 3.6 mg/cm²



- Brown Wood Door Exterior 4.3 mg/cm²
- Brown Wood Window Seal Exterior 1.1 mg/cm²
- Brown Wood Wall Exterior 5.9 mg/cm²
- Brown Wood Facia Exterior 6.5 mg/cm²
- Brown Wood Eves Exterior 6.5 mg/cm²
- Brown Wood Window Frame Exterior 1.4 mg/cm²

None of the other painted or coated components tested by XRF are at or above the respective levels considered to be lead-based paint (LBP); however, paint may contain detectable levels of lead in the coatings which make work impacting those surfaces subject to the Cal / OSHA Lead in Construction Standard (Title 8 CCR 1532.1).

3.2 Methodology

XRF testing of the painted surfaces was performed in general accordance with Chapter 7 of the <u>HUD Guide Lines</u> for the <u>Evaluation and Control of Lead-Based Paint Hazards in Housing</u>. In every "room equivalent" within the tested property, one representative surface of each "testing combination" was tested. Multiple readings were collected to resolve inconsistencies in the test results.

The method employed was X-ray fluorescence (XRF) using a Heuresis PE 200i Cobalt 57. The instrument was operated in "Quick Mode," where the duration for each test result is determined by a combination of the:

- actual reading relative to the designated action level;
- age of the radioactive source; and
- substrate on which the test was taken.

The instrument's calibration was verified according to the manufacturer's specifications in compliance with the Performance Characteristic Sheet (PCS) developed for this instrument. The readings from this instrument produce a 95% confidence level that the "lead" reading accurately reflects the actual level of lead in the tested surfaces, relative to the federal action level.

3.3 Regulatory Limits

Government agencies have promulgated different regulatory threshold levels to classify Lead-Based Paint. Some of the established "levels" are quantified in different units of measurement. Listed below are the current regulatory agencies that have defined LBP, along with the respective action level:

<u>Agency</u>	Ordinance #	Action level (mg / cm ²)	Action level (ppm)
HUD / EPA	24 CFR 35.86 & 40 CFR 745.103	$1.0 \text{ mg} / \text{cm}^2$	5,000 ppm
L.A. County	Title 11, 11.28.010	$0.7 \text{ mg} / \text{cm}^2$	Not Specified
OSHA / CAL OSHA	29 CFR 1926.62 & Title 8, 1532.1	Not Specified	600 ppm

The Federal threshold for lead-based paint, 0.5 percent by weight, is higher than the local Los Angeles County action level and the lower of the two thresholds is the one that everyone within Los Angeles County must adhere to. In recognition of the various action levels the testing results are classified as follows for this report:

- Painted surfaces with readings at or above 0.7 mg / cm² are considered Positive
- Painted surfaces with readings below 0.7 mg / cm² are considered Negative



The individual readings have been provided in the XRF Results Table located in Appendix III. Any future change in action levels by one of the regulating agencies may affect the classification of results.

For purposes of this survey, any material containing any detectable level of lead is subject to OSHA's Lead Exposure in Construction Rule (29 CFR Part 1926) and CAL/ OSHA Lead in Construction Standard (Title 8 CCR 1532.1). Any work that impacts these materials must be performed in accordance with these and any other applicable standards.

3.4 Lead Recommendations

All lead laden components identified in this report shall be demolished or abated by certified lead trained personnel in accordance with all applicable federal, state and local regulations. All suspected lead laden components shall undergo paint film stabilization before components are removed by manual intact methods. LBP that will be impacted by hot work (welding, torch cutting, etc.) must be removed from the component by lead abatement workers to allow a minimum of 6 inches clearance on either side of the location of the hot work to prevent the volatilization of lead into the air.

Paint / surface coatings that were tested and found to have lead concentrations below the LBP threshold (i.e. 0.7 mg/cm²) may still contain detectable concentrations of lead. Thus, work impacting those surfaces are subject to the Cal/OSHA Lead in Construction Standard 1532.1. This standard requires that respiratory protection and containment is used when performing "trigger tasks" until results of personal air monitoring indicate that workers are not exposed to lead above the action level or permissible exposure level. Additionally, the demolition or removal of lead or components with lead coatings is subject to Title 17, Division 1, Chapter 8 of the California Code of Regulations.

Should the contractor choose not to remove the identified LBP materials and demolish the structure in its entirety with the lead-paint components in place, it is recommended that the contractor stabilize the LBP components prior to demolition and then collect samples representative of the entire mass of the prospective waste stream. These samples should then be analyzed according to the United States Environmental Protection Agency (EPA) and the California Department of Toxic Substances Control (DTSC) prior to disposal facility acceptance.

4.0 Limitations

The inspection and testing report is based on the condition of the subject property existing and apparent on the precise time and exact date of the inspection. Not all conditions may be apparent on the inspection and testing date due to weather conditions, inoperable systems, inaccessibility of areas of the subject property, or for other reasons.

EFI Global has prepared this report for the exclusive use of its client. EFI Global, in performing its professional services, has applied scientific judgment that it believes is consistent with industry standards. EFI Global inspected structures and/or contents in a good faith effort to observe pertinent detail. Due to the limitations of time, access, and other variables, certain details may have been overlooked. EFI Global has relied in good faith upon the information and representations of others in the preparation of this report and the opinions expressed herein. Accordingly, EFI Global accepts no responsibility for deficiencies, omissions, misrepresentations, or fraudulent acts of persons interviewed.

EFI Global assumes no liability for any loss, injury, claim, or damage arising directly or indirectly from any use or reliance on this report or the opinions expressed herein. EFI Global makes no warranty, express or implied. This



report is limited only to the samples taken and locations sampled. Additional sampling may be needed to further identify other pollutants or asbestos affected areas inside the property.

Since destructive investigation was not performed during the survey, the report may not reveal concealed asbestos-containing materials. Subsequently, additional investigation including construction documents review and/or destructive investigation is recommended as a precaution to prevent accidental exposure when construction or demolition is planned for this facility.

Thank you for the opportunity to work with you on this project. Please contact the undersigned at (310) 854-6300, if you have questions or if additional services are necessary.

Prepared by:

Heriberto Romero

DOSH Certified Site Surveillance Technician No.15-5572 CDPH Certifies Lead Sampling Technician No. LRC-00002172

Reviewed by:

Michael Pinkerton

CDPH Certified Lead Inspector/Assessor No. LRC-00003397

Reviewed by:

Brent Weisbrod

DOSH Certified Asbestos Consultant No. 14-5186

APPENDICES:

I. Site Diagrams


II. Asbestos Analysis Results and Chains of Custody


III. Lead XRF Results Table


IV. Personnel Certifications




APPENDIX I Site Diagram









APPENDIX II
Asbestos Analysis Results and Chain of Custody



EMSL Order: 042019621 Customer ID: 32ANDE85

Customer PO: Project ID:

Attention: Heriberto Romero Phone: (888) 705-6300

EFI Global, Inc. Fax:

5261 West Imperial Highway Received Date: 08/13/2020 10:20 AM

Los Angeles, CA 90045 Analysis Date: 08/17/2020 Collected Date: 08/07/2020

Project: 045.04081 / 585 House

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			<u>Asbestos</u>		
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
1A-Drywall	Restroom 1 - N - Drywall Systems	Brown/White Fibrous	15% Cellulose	85% Non-fibrous (Other)	None Detected
042019621-0001 1A-Joint Compound	Restroom 1 - N -	Homogeneous Tan		100% Non-fibrous (Other)	None Detected
042019621-0001A	Drywall Systems	Non-Fibrous Homogeneous			
1B-Drywall	Restroom 2 - E - Drywall Systems	Brown/White Fibrous	15% Cellulose	85% Non-fibrous (Other)	None Detected
042019621-0002		Homogeneous -			
1B-Joint Compound	Restroom 2 - E - Drywall Systems	Tan Non-Fibrous		100% Non-fibrous (Other)	None Detected
	Closet 1 - NE -	Homogeneous Brown/White	20% Cellulose	77% Non-fibrous (Other)	None Detected
1C-Drywall 042019621-0003	Drywall Systems	Fibrous Homogeneous	3% Glass	77 70 NOTI-TIDIOUS (Ottlet)	None Detected
1C-Joint Compound	Closet 1 - NE - Drywall Systems	Tan Non-Fibrous		100% Non-fibrous (Other)	None Detected
042019621-0003A	, ,	Homogeneous			
2A	Bedroom 1 - E - Wallpaper	Brown Fibrous	70% Cellulose	30% Non-fibrous (Other)	None Detected
042019621-0004		Homogeneous			
2B	Bedroom 1 - W - Wallpaper	Brown Fibrous	50% Cellulose	50% Non-fibrous (Other)	None Detected
042019621-0005		Homogeneous			
3A	Exterior - E - Window Putty	Beige Non-Fibrous		100% Non-fibrous (Other)	None Detected
042019621-0006		Homogeneous			
3B 042019621-0007	Exterior - SE - Window Putty	Beige Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
3C	Exterior - W - Window	Beige		100% Non-fibrous (Other)	None Detected
042019621-0008	Putty	Non-Fibrous Homogeneous			
4A	Kitchen - E - Sink Undercoating - White	White Fibrous	15% Cellulose	85% Non-fibrous (Other)	None Detected
042019621-0009		Homogeneous			
4B	Kitchen - E - Sink Undercoating - White	White Fibrous	15% Cellulose	85% Non-fibrous (Other)	None Detected
042019621-0010		Homogeneous			
5A	Restroom 2 - N - FRP Backing Mastic -	Black Non-Fibrous		100% Non-fibrous (Other)	None Detected
042019621-0011	Black	Homogeneous			
5B	Restroom 2 - W - FRP Backing Mastic -	Black Non-Fibrous		100% Non-fibrous (Other)	None Detected
042019621-0012 6A-Counter Top Tile	Black Living Room - E -	Homogeneous White		100% Non-fibrous (Other)	None Detected
042019621-0013	Counter Top Tile - 4x4 White	Non-Fibrous Homogeneous			

Initial report from: 08/18/2020 07:34:22



EMSL Order: 042019621 **Customer ID:** 32ANDE85

Customer PO: Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			Non-Asbe	<u>estos</u>	Asbestos		
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type		
6A-Grout	Living Room - E - Grout	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected		
6A-Counter Top Tile 2	Living Room - E - Counter Top Tile - 4x4	Brown/Tan Fibrous	30% Cellulose	70% Non-fibrous (Other)	None Detected		
042019621-0013B	White	Homogeneous					
6A-Thinset 042019621-0013C	Living Room - E - Thinset	Gray Non-Fibrous		100% Non-fibrous (Other)	None Detected		
6A-Adhesive	Living Room - E - Adhesive	Homogeneous White Non-Fibrous		100% Non-fibrous (Other)	None Detected		
042019621-0013D	Adilesive	Homogeneous					
6B-Counter Top Tile	Kitchen - N - Counter Top Tile - 4x4 White	White/Blue Non-Fibrous		100% Non-fibrous (Other)	None Detected		
042019621-0014		Homogeneous					
6B-Grout	Kitchen - N - Grout	White Non-Fibrous		100% Non-fibrous (Other)	None Detected		
042019621-0014A	120.1	Homogeneous		4000/ N 5" (5")	N 5		
6B-Thinset 042019621-0014B	Kitchen - N - Thinset	Gray Non-Fibrous		100% Non-fibrous (Other)	None Detected		
	Vitaban N	Homogeneous		1000/ Non fibrage (Other)	Nana Datastad		
6B-Adhesive 042019621-0014C	Kitchen - N - Adhesive	White Non-Fibrous		100% Non-fibrous (Other)	None Detected		
	Kitchen - N - Counter	Homogeneous Brown	35% Cellulose	65% Non-fibrous (Other)	None Detected		
6B-Counter Top 2	Top Tile - 4x4 White	Fibrous Homogeneous	33% Cellulose	05% Non-librous (Other)	None Detected		
A-Floor Tile	Restroom 1 - N -	White		100% Non-fibrous (Other)	None Detected		
042019621-0015	Floor Tile - White	Non-Fibrous Homogeneous					
7A-Grout	Restroom 1 - N - Grout	Beige Non-Fibrous		100% Non-fibrous (Other)	None Detected		
042019621-0015A		Homogeneous					
7A-Thinset	Restroom 1 - N - Thinset	Gray Non-Fibrous		100% Non-fibrous (Other)	None Detected		
042019621-0015B		Homogeneous					
7B-Floor Tile	Restroom 2 - S - Floor Tile - White	Tan/White Non-Fibrous		100% Non-fibrous (Other)	None Detected		
042019621-0016	Destruction 2 2	Homogeneous		4000/ Nov. 51 (OII)	No. B. C. C.		
7B-Grout 042019621-0016A	Restroom 2 - S - Grout	Beige Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected		
B-Thinset	Restroom 2 - S -	Gray		100% Non-fibrous (Other)	None Detected		
042019621-0016B	Thinset	Non-Fibrous Homogeneous		100% Holl librous (Other)	Hono Delected		
7B-Adhesive	Restroom 2 - S -	White		100% Non-fibrous (Other)	None Detected		
042019621-0016C	Adhesive	Non-Fibrous Homogeneous		- (,			
BA-VFT	Bedroom 1 - Under Wood Flooring - N -	Tan Non-Fibrous		100% Non-fibrous (Other)	None Detected		
042019621-0017	VFT - Tan	Homogeneous					
BA-Mastic	Bedroom 1 - Under Wood Flooring - N -	Yellow Non-Fibrous		100% Non-fibrous (Other)	None Detected		
042019621-0017A	Mastic	Homogeneous					
8B-VFT	Bedroom 1 - Under Wood Flooring - N -	Tan Non-Fibrous		100% Non-fibrous (Other)	None Detected		
042019621-0018	VFT - Tan	Homogeneous					

Initial report from: 08/18/2020 07:34:22



EMSL Order: 042019621 **Customer ID:** 32ANDE85

Customer PO: Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			Non-Asbe	<u>stos</u>	<u>Asbestos</u>
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
8B-Mastic	Bedroom 1 - Under Wood Flooring - N - Mastic	Yellow Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
9A-VFT	Closet 1 - N - VFT - Beige	Beige Fibrous	30% Cellulose 10% Synthetic	60% Non-fibrous (Other)	None Detected
9A-Adhesive	Closet 1 - N - Adhesive	Yellow Non-Fibrous		100% Non-fibrous (Other)	None Detected
042019621-0019A		Homogeneous			
PA-VFT 2	Closet 1 - N - VFT	Tan Fibrous	30% Cellulose	50% Non-fibrous (Other)	20% Chrysotile
042019621-0019B	Claratid C VET	Homogeneous	050/ 0	COO/ Now Share (Other)	Nama Datastad
9B-VFT 942019621-0020	Closet 1 - S - VFT - Beige	Beige Fibrous Homogeneous	25% Synthetic 15% Glass	60% Non-fibrous (Other)	None Detected
9B-Adhesive	Closet 1 - S - Adhesive	Yellow Non-Fibrous		100% Non-fibrous (Other)	None Detected
042019621-0020A	Oleranda O. MET	Homogeneous		700/ No. 51 (01)	200/ Ok t''
9B-VFT 2 942019621-0020B	Closet 1 - S - VFT	Tan Fibrous Homogeneous		70% Non-fibrous (Other)	30% Chrysotile
10A	Closet 3 - N - VSF - Brown	Brown Fibrous	25% Cellulose 5% Synthetic	70% Non-fibrous (Other)	None Detected
042019621-0021		Homogeneous	·		
0B	Closet 3 - S - VSF - Brown	Brown/Gray Fibrous	35% Cellulose	65% Non-fibrous (Other)	None Detected
142019621-0022	Kitchen - W - VSF -	Homogeneous Tan		1000/ Non fibrage (Other)	Nana Datastad
11A-VSF 042019621-0023	Tan	Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
11A-Adhesive	Kitchen - W - Adhesive	Clear Non-Fibrous		100% Non-fibrous (Other)	None Detected
042019621-0023A		Homogeneous			
11A-VSF 2 142019621-0023B	Kitchen - W - VFT	Tan Fibrous	25% Cellulose 5% Synthetic	70% Non-fibrous (Other)	None Detected
11A-Floor Tile	Kitchen - W - Floor Tile	Tan Non-Fibrous Homogeneous		98% Non-fibrous (Other)	2% Chrysotile
11A-Mastic	Kitchen - W - Mastic	Black Non-Fibrous		98% Non-fibrous (Other)	2% Chrysotile
42019621-0023D		Homogeneous			
1B-VSF 42019621-0024	Kitchen - E - VSF - Tan	Tan Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
1B-Adhesive	Kitchen - E -	Clear		100% Non-fibrous (Other)	None Detected
42019621-0024A	Adhesive	Non-Fibrous Homogeneous			. ISAN DOLONION
1B-VSF 2	Kitchen - E - VSF	Tan Fibrous	25% Synthetic 15% Glass	60% Non-fibrous (Other)	None Detected
42019621-0024B		Homogeneous			
1B-Adhesive 2	Kitchen - E - Adhesive	Yellow Non-Fibrous		100% Non-fibrous (Other)	None Detected
042019621-0024C 11B-Floor Tile	Kitchen - E - Floor	Homogeneous Tan Non-Fibrous		97% Non-fibrous (Other)	3% Chrysotile
042019621-0024D	Tile.	Homogeneous			

Initial report from: 08/18/2020 07:34:22



EMSL Order: 042019621 Customer ID: 32ANDE85

Customer PO: Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			<u>Asbestos</u>		
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
11B-Mastic	Kitchen - E - Mastic	Black Non-Fibrous Homogeneous		97% Non-fibrous (Other)	3% Chrysotile
12A-Shingle 042019621-0025	Roof - N - Roof Core	Tan/Black Fibrous Homogeneous	15% Glass	85% Non-fibrous (Other)	None Detected
12A-Tar Paper 042019621-0025A	Roof - N - Roof Core	Black Fibrous Homogeneous	40% Cellulose	60% Non-fibrous (Other)	None Detected
12B-Shingle 042019621-0026	Roof - E - Roof Core	Tan/Black Fibrous Homogeneous	15% Glass	85% Non-fibrous (Other)	None Detected
12B-Tar Paper 042019621-0026A	Roof - E - Roof Core	Black Fibrous Homogeneous	40% Cellulose	60% Non-fibrous (Other)	None Detected
12C-Shingle	Roof - S - Roof Core	Tan/Black Fibrous Homogeneous	20% Glass	80% Non-fibrous (Other)	None Detected
12C-Tar Paper 042019621-0027A	Roof - S - Roof Core	Black Fibrous Homogeneous	50% Cellulose	50% Non-fibrous (Other)	None Detected
13A 042019621-0028	Roof - N - Roofing Mastic	Black Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
13B 042019621-0029	Roof - E - Roofing Mastic	Black Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
13C 042019621-0030	Roof - S - Roofing Mastic	Brown/Black Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected

Analyst(s)

Daniel Blake (24) John Witcraft (31) Sarah Kleinbrahm (9) Samantha Rundstrom, Laboratory Manager or Other Approved Signatory

EMSL maintains liability limited to cost of analysis. Interpretation and use of test results are the responsibility of the client. This report relates only to the samples reported above, and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. The report reflects the samples as received. Results are generated from the field sampling data (sampling volumes and areas, locations, etc.) provided by the client on the Chain of Custody. Samples are within quality control criteria and met method specifications unless otherwise noted. The above analyses were performed in general compliance with Appendix E to Subpart E of 40 CFR (previously EPA 600/M4-82-020 "Interim Method") but augmented with procedures outlined in the 1993 ("final") version of the method. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis . Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Estimation of uncertainty is available on request.

Samples analyzed by EMSL Analytical, Inc. Cinnaminson, NJ NVLAP Lab Code 101048-0, AIHA-LAP, LLC-IHLAP Lab 100194, NYS ELAP 10872, NJ DEP 03036, PA ID# 68-00367, LA #04127

EFI Global Project No.:

Project Name:

Sampling By:

Number of Samples:

Date(s) Collected:

Page No.:

8/7/20

ರ

2

Pages Total.

285 House

efi global

Chain of Custody Laboratory

> Turn Around Time - (Circle)
> *Please select based on laboratory being used

> > 3hr

Standard

6hr


24hr 48hr (72hr)

12-0102hC

	Special Instructions:	4		Relinquished By (Print & Sign) (Date & Time)	Harriban	Relinquished By (Print & Sign)(Date & Time)			-										1						•	Sample No.:	8040,540
	ns:			& Sign) (Date &	は大き	& Sign)(Date & I				:									A		2	\	アス)		Sample Locar	
	٦		\	Time)	nero H	(ime)	3											1	attached		ት	6	タント			Sample Location & Comments	707 (100)
					of Kno									0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0												5	Hikomero
Υ	Stop Positive:	.i.v	·	Received B	8/0/2	Received B					7		٠										-		End Flow Rate		
Yes	tive:		1	y (Print & Si	0	y (Print & Si				! ! ! !																-	20
No				gn) (Date & Tir	10/20 CM3	Received By (Print & Sign) (Date & Time)		,	*1.															,	Stop Time	Start Time	. 4
Her ber to Romero @ FF / Grobal, com	E-mail to Additional Party:				7			,	:																Area/SQFT	Total Volume	817/20
170 anomo	Party:				8-13-6 B		Serial No.:	Analysis Type:	Serial No.:	Analysis Type:	Serial No.:	Analysis Type:	Serial No.:	Analysis Type:	Serial No.:	Analysis Type:	Serial No.:	Analysis Type:	Serial No.:	Analysis Type:	Serial No.:	Analysis Type: 🖊		Analysis Type: 🦪	Sample Se	Type of	
=1600px11	A seguin of the seguing of the second				6.265					7 9 9 9 9 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		9	S	! `	03 40 44	: 1		£. ₹ 5	₩.	201 O			PCP/	7/ NA	Sample Serial Number	Type of Analysis	4
Com	· 1	L *,				٠ن		,	·	i		Dag		1	Ωf	· · ·	-	<u>. </u>	· · · ·		·						

多

4



PROJECT LOCATION: 585

House DATE: 8/7/20

COMPLETED BY: H.R.


PROJECT NAME:

PROJECT NUMBER:

ASBESTOS FIELD BULK SAMPLE TABLE

S / TSI/ MISC	F / NF G D SD		1	\	<u></u>	BA
s /	G p SD	90	>	Restroom 2	FRP Backing Hastic	5 A
s /	F / NF G D SD		12	-	< - :	J B
s /	Ø F / ₹), SD	10	E	Kitchen	Sink under Coating	ЧA
s /	F / NF G D SD		٦	\	4	740
s ·	F / NF G D SD		7			8
S / 1881/	S S S S S S S S S S S S S S S S S S S	30	<i>C</i>	Exterior	window Putty	3 A
: I ^{ୟୁ} ଣ ଓ	F / NF G D SD		- 2	\	<u> </u>	18
S / DOI	Ģ p sd	90	3-1	Bedroom	Wallpaper	2 <i>A</i>
· s	F / NF G D SD		-NE	Closet 1		J.
s /	F / NF G D SD		3.	1 2		00
(2)	F M SD		/ - N	Restroom	Drywall Systems	[]
* HOMOGENOUS APPLICATION	CONDITION	APPROX. SQUARE FOOTAGE	ATION	SAMPLE LOCATION	SAMPLE DESCRIPTION	SAMPLENUMBER

10%



ASBESTOS FIELD BULK SAMPLE TABLE

PROJECT NUMBER: 045,0408		PROJECT NAME:			
PROJECT LOCATION: 585 Hauge	DATE:_	8/7/20 COMPLE	TED BY: H.R.		
SAMELENUMBER	SAMPLE DESCRIPTION	SAMPLE LOCATION	APPROX. SQUARE FOOTAGE	CONDITION	HOMOGENOUS APPLICATION
6A	Counter Top Tile (elxu)	Living Room - E		F / NF G D SD	S / TSI/ MISC
名々	\	Kitchen ~		F / NF G D SD	S / TSI / MISC
74	Floor Tite white	Rostroom 1 - N		F / NF G D SD	S WTSI /_MISC
97	<u> </u>	. 4 2 -5		F / NF G D SD	S STIST / FAIRCE
SA	VFT (Tan)	Bedroom 1	7	F / NF G D SD	2 10 4 S
←	V		ξ_	F / NF G D SD	S / HSC D
9A	VSF (Beige) + Adhesive Closet 1	Closet 1 - ~		F / NF G D SD	s /-981/ MISC
84	4+4	1 -5		F / NF G D SD	S / TSI / MISC
10A	VSF(Brown)	Closetis - N		F / NF G D SD	S / TSI/ MISC
4	\(\)	-5		F / NF G D SD	S / TSI/ MISC
	USF (Taw) + layers +	Kitchen - W		F / NF G D SD	S / TSI / MISC
\(\frac{1}{2}\)	< X	3 .		F / NF G D SD	S / TSI/ MISC



PROJECT LOCATION: 585 House DATE: 8/7/20	PROJECT NUMBER: 045.04081
DATE: 8/7/20	PROJECT NAME:
 COMPLETED BY: H.R.	

						↓ C	S)	13 A Roofing Hastic	+ C	(Z	12A Roof Corc	SAME TRANSCOMMEN
						V -5	3-	7	5 -	3 -	Roof - N	SCHALL DE POCCULION
								20		. `	1,200	FOOTAGE
F / NF G D SD	F / NF G D SD	F / NF G D SD	F / NF G D SD	F / ND D SD	F / NF G D SD	F / NF G D SD	F / ∰ D SD	FOOTAGE				
S / TSI/ MISC	s / G ISI/ MISC	S / MISCO	S CISI/SING S	SOUNT NEWSC	S C TSI / MISC	S / TSI/ MISC	S / TSI/ MISC	S / TSI MISO	APPLICATION			

Robbacho

4



200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

042019627

32ANDE85

Attn: Phone: (888) 705-6300 Heriberto Romero

Collected: 5261 West Imperial Highway

Received: 8/13/2020 Los Angeles, CA 90045 Analyzed: 8/25/2020

045.04081 / 1800 E. Laveta Proj:

EFI Global, Inc.

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

Fax:

042019627-0001 Lab Sample ID: Client Sample ID: 14A-Drywall

Sample Description: 2nd Floor - Room 200-E/Drywall

	Analyzed		Non	-Asbestos				
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment		
PLM	8/14/2020	Brown/White	20.0%	80.0%	None Detected			
Client Sample ID:	14A-Joint Compound					Lab Sample ID:	042019627-0001A	

Sample Description: 2nd Floor - Room 200-E/Joint Compound

	Analyzed		Non-Asb	estos		
TEST	Date	Color	Fibrous Nor	n-Fibrous	Asbestos	Comment
PLM	8/14/2020	White	0.0%	98.0%	2% Chrysotile	

042019627-0002 Lab Sample ID: Client Sample ID: 14B-Drywall

Sample Description: 2nd Floor - Room 227 - N/Drywall

	Analyzed		Non	-Asbestos				
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment		
PLM	8/14/2020	Brown/White	20.0%	80.0%	None Detected			
Client Sample ID:	14B-Joint Compound					Lab Sample ID:	042019627-0002A	

Sample Description: 2nd Floor - Room 227 - N/Joint Compound

	Analyzed		Non-	Asbestos			
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	White	0.0%	98.0%	2% Chrysotile		

Client Sample ID: Lab Sample ID: 042019627-0003 14C-Drywall

Sample Description: 2nd Floor - Room 245 - NE/Drywall

	Analyzed		Non	-Asbestos				
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comm	ent	
PLM	8/14/2020	Brown/White	20.0%	80.0%	None Detected			

Lab Sample ID: 042019627-0003A Client Sample ID: 14C-Joint Compound

Sample Description: 2nd Floor - Room 245 - NE/Joint Compound

	Analyzed		Non	-Asbestos			
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	White	0.0%	97.0%	3% Chrysotile		
Client Sample ID:	14D-Drywall					Lab Sample ID:	042019627-0004

Sample Description: 2nd Floor - Room 232 - SW/Drywall

	Analyzed		Non	-Asbestos		
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment
PLM	8/14/2020	Brown/White	20.0%	80.0%	None Detected	



200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

042019627 32ANDE85

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

Client Sample ID:	14D-Joint Compound				<u> </u>	Lab Sample ID:	042019627-0004A
Sample Description:	2nd Floor - Room 232 - SW	//Joint Compound					
TEST	Analyzed Date	Color		-Asbestos Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	White	0.0%	98.0%	2% Chrysotile	Comment	
		VVIIILE	0.070	90.070	2 /6 Chrysothe	Lab Samula ID:	040040007.0004B
Client Sample ID:	14D-Texture					Lab Sample ID:	042019627-0004B
Sample Description:	2nd Floor - Room 232 - SW	//Texture					
	Analyzed		Non.	-Asbestos			
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	White	0.0%	100.0%	None Detected		
Client Sample ID:	14E-Drywall					Lab Sample ID:	042019627-0005
Sample Description:	1st Floor - Utility Rm 6 - SE	/Drywall					
	ist i looi - Suilty Mill 0 - SL	, D. y Wali					
	Analyzed		Non-	-Asbestos			
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	Brown/White	20.0%	80.0%	None Detected		
Client Sample ID:	14E-Joint Compound					Lab Sample ID:	042019627-0005A
Sample Description:	1st Floor - Utility Rm 6 - SE	/Joint Compound					
	•	·					
	Analyzed		Non-	-Asbestos			
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	White	0.0%	100.0%	None Detected		
Client Sample ID:	14E-Texture					Lab Sample ID:	042019627-0005B
Sample Description:	1st Floor - Utility Rm 6 - SE	/Texture					
	Analyzed			-Asbestos		•	
TEST PLM	8/14/2020	Color White	0.0%	Non-Fibrous 100.0%	Asbestos None Detected	Comment	
		vviille	0.076	100.0%	None Detected		
Client Sample ID:	14F-Drywall					Lab Sample ID:	042019627-0006
Sample Description:	1st Floor - Room 106 - SE/	Drywall					
	Analyzad		No-	-Asbestos			
TEST	Analyzed Date	Color		-Aspestos Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	Brown/White	20.0%	80.0%	None Detected		
Client Sample ID:	14F-Joint Compound					Lab Sample ID:	042019627-0006A
Sample Description:	1st Floor - Room 106 - SE/	loint Compound					,
p 2 2001 p. 1011	151 1001 - 1100111 100 - SE/	John Compound					
	Analyzed		Non-	-Asbestos			
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	White	0.0%	98.0%	2% Chrysotile		
Client Sample ID:	14F-Texture					Lab Sample ID:	042019627-0006B
Sample Description:	1st Floor - Room 106 - SE/	Texture					
-							
	Analyzed		Non-	-Asbestos			

Fibrous Non-Fibrous

100.0%

0.0%

Date

8/14/2020

Color

White

TEST

PLM

Comment

Asbestos

None Detected



200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

32ANDE85

042019627

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

Client Sample ID:	14G-Drywall					Lab Sample ID:	042019627-0007
ample Description:	1st Floor - Room 145 - SE	E/Drywall					
	Analyzed			Asbestos			
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	Brown/White	20.0%	80.0%	None Detected		
Client Sample ID:	14G-Joint Compound					Lab Sample ID:	042019627-0007A
Sample Description:	1st Floor - Room 145 - SE	/Joint Compound					
	Anglyzod		Non	Asbestos			
TEST	Analyzed Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	White	0.0%	100.0%	None Detected		
Client Sample ID:	14H-Drywall					Lab Sample ID:	042019627-0008
Sample Description:	1st Floor - Room 158 - NV	V/Dravell				zas campic is.	042013027-0000
sample Bescription.	15t F1001 - R00111 130 - NV	v/Drywaii					
	Analyzed		Non-	Asbestos			
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Brown/White	20.0%	80.0%	None Detected		
Client Sample ID:	14H-Joint Compound					Lab Sample ID:	042019627-0008A
Sample Description:	1st Floor - Room 158 - NV	V/Joint Compound					
	Analyzed			Asbestos			
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM 	8/17/2020	White	0.0%	100.0%	None Detected		
Client Sample ID:	14H-Texture					Lab Sample ID:	042019627-0008B
Sample Description:	1st Floor - Room 158 - NV	V/Texture					
	Amahimad		Nam	Ashaataa			
TEST	Analyzed Date	Color		Asbestos Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	White	0.0%	100.0%	None Detected		
Client Sample ID:	14I-Drywall					Lab Sample ID:	042019627-0009
Sample Description:	1st Floor - Room 159 - NE	-/Dravell				Lub Gumpie ib.	042013027-0003
oumpre Decempaem	15t F1001 - R00111 139 - NE	z/Drywaii					
	Analyzed		Non-	Asbestos			
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Brown/White	15.0%	85.0%	None Detected		
Client Sample ID:	14I-Joint Compound					Lab Sample ID:	042019627-0009A
Sample Description:	1st Floor - Room 159 - NE	/Joint Compound					
	Analyzed			Asbestos		_	
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	White	0.0%	100.0%	None Detected		
Client Sample ID:	14I-Texture					Lab Sample ID:	042019627-0009B
Sample Description:	1st Floor - Room 159 - NE	/Texture					
TEOT	Analyzed		Non-	Asbestos	A . D f	0	

Fibrous Non-Fibrous

100.0%

0.0%

Date

8/17/2020

Color

White

TEST

PLM

Comment

Asbestos

None Detected



200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

042019627

32ANDE85

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

Client Sample ID:	15A					Lab Sample ID:	042019627-0010
ample Description:	1st Floor - Room 145 - E/Acous	tic Texture				-	
•							
	Analyzed		Non-	Asbestos			
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	White	0.0%	100.0%	None Detected		
Client Sample ID:	15B					Lab Sample ID:	042019627-0011
Sample Description:	1st Floor Room 145 - S/Acousti	c Texture					
	Analyzed			Asbestos		_	
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	White	0.0%	100.0%	None Detected		
Client Sample ID:	15C					Lab Sample ID:	042019627-0012
Sample Description:	1st Floor - Room 142 - N/Acous	tic Texture					
				A . b d			
TEST	Analyzed Date	Color		Asbestos Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	White	0.0%	100.0%	None Detected	Comment	
		VVIIIG	0.070	100.070	None Detected	lab Samula IS	042040607 0046
Client Sample ID:	16A-Adhesive					Lab Sample ID:	042019627-0013
Sample Description:	Utility Room 6 - SE/Adhesive (T	an)					
	Analyzod		Non	Asbestos			
TEST	Analyzed Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	Tan	0.0%	100.0%	None Detected		
Client Sample ID:	16A-Cove Base					Lab Sample ID:	042019627-0013A
Sample Description:	Utility Room 6 - SE/Cove Base	(Proup)					0.20.002. 00.0.
	Ottility Nooth 0 - 3L/Cove base	(DIOWII)					
	Analyzed		Non-	Asbestos			
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	Brown	0.0%	100.0%	None Detected		
Client Sample ID:	16B-Adhesive					Lab Sample ID:	042019627-0014
Sample Description:	Utility Room 7 - E/Adhesive (Ta	n)					
	,	•					
	Analyzed		Non-	Asbestos			
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/15/2020	Tan	0.0%	100.0%	None Detected		
Client Sample ID:	16B-Cove Base					Lab Sample ID:	042019627-0014A
Sample Description:	Utility Room 7 - E/Cove Base (E	Brown)					
	Analyzed			Asbestos		_	
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/15/2020	Brown	0.0%	100.0%	None Detected		
Client Sample ID:	16C-Adhesive					Lab Sample ID:	042019627-0015
Sample Description:	1st Floor - Room 106 - S/Adhes	ive (Tan)					
	Analyzed		Non-	Asbestos			
TEOT	D-4-	0-1	Ethan .				

Fibrous Non-Fibrous

100.0%

0.0%

Date

8/15/2020

Color

Tan/Yellow

TEST

PLM

Comment

Asbestos

None Detected



EMSL Analytical, Inc.

200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

32ANDE85

042019627

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

Lab Sample ID: 042019627-0015A Client Sample ID: 16C-Cove Base

Sample Description: 1st Floor - Room 106 - S/Cove Base (Gray)

	Analyzed		Non	-Asbestos				
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment		
PLM	8/15/2020	Gray	0.0%	100.0%	None Detected			
Client Sample ID:	16D-Adhesive			_		Lab Sample ID:	042019627-0016	

Sample Description: 1st Floor - Room 110 - N/Adhesive (Tan)

	Analyzed		Non	-Asbestos				
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment		
PLM	8/15/2020	Tan	0.0%	100.0%	None Detected			
Client Sample ID:	16D-Cove Base					Lab Sample ID:	042019627-0016A	

Sample Description: 1st Floor - Room 110 - N/Cove Base (Gray)

	Analyzed		Non	-Asbestos				
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment		
PLM	8/15/2020	Gray	0.0%	100.0%	None Detected			
Client Sample ID:	16E-Adhesive					Lab Sample ID:	042019627-0017	

Sample Description: 1st Floor - Room 159 - NE/Adhesive (Tan)

	Analyzed		Non	-Asbestos		
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment
PLM	8/15/2020	Tan/White	5.0%	95.0%	None Detected	Result includes a small amount of inseparable attached material
Client Sample ID:	16E-Cove Base					Lab Sample ID: 042019627-0017A

Sample Description: 1st Floor - Room 159 - NE/Cove Base (Gray)

		Analyzed		Non	-Asbestos			
TEST		Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM		8/15/2020	Gray	0.0%	100.0%	None Detected		
Client Sample ID:	17A		_		_		Lab Sample ID:	042019627-0018

Client Sample ID:

Sample Description: 1st Floor - Room 158 - NW/Ceiling Tile (12x12)

	Analyzed		Non-	-Asbestos		
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment
PLM	8/15/2020	Gray/White	90.0%	10.0%	None Detected	
•						

Lab Sample ID: 042019627-0019 17B Client Sample ID:

Sample Description: 1st Floor - Room 106 - W/Ceiling Tile (12x12)

		Analyzed		Non	-Asbestos				
TEST		Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment		
PLM		8/17/2020	Gray/White	80.0%	20.0%	None Detected			
Client Sample ID:	18A		_			_	Lab Sample ID:	042019627-0020	

Sample Description: 2nd Floor - Room 202 - E/Ceiling Tile (24x48)

	Analyzed		Non-	Asbestos		
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment
PLM	8/15/2020	Tan/White	80.0%	20.0%	None Detected	



Client Sample ID:

EMSL Analytical, Inc.

200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Lab Sample ID:

Project ID:

042019627 32ANDE85

042019627-0024

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

Lab Sample ID: 042019627-0021 Client Sample ID: 18B

Sample Description: 2nd Floor - Room 226 - S/Ceiling Tile (24x48)

Analyzed Non-Asbestos **TEST** Date Color Fibrous Non-Fibrous Asbestos Comment PLM 8/17/2020 Gray/White 80.0% 20.0% None Detected Client Sample ID: 19A Lab Sample ID: 042019627-0022

Sample Description: 1st Floor - Room 149 - S/Sink Under Coating

Analyzed Non-Asbestos TEST Non-Fibrous Comment Date Color **Fibrous** Asbestos PLM 8/17/2020 Gray/White 0.0% 97.0% 3% Chrysotile Lab Sample ID: Client Sample ID: 19B 042019627-0023

Sample Description: 1st Floor - Room 149 - S/Sink Under Coating

Analyzed Non-Asbestos **TEST** Date Color Fibrous Non-Fibrous Asbestos Comment PLM 8/17/2020 Gray/White 0.0% 97.0% 3% Chrysotile

Sample Description: Changing Rm 1 - S/Carpet Adhesive (Tan)

23A

Analyzed Non-Asbestos **TEST** Date Color Fibrous Non-Fibrous Asbestos Comment PLM 8/17/2020 Tan/White 0.0% 96.0% 4% Chrysotile Result includes a small amount of inseparable attached linoleum 042019627-0025 20A Lab Sample ID:

Sample Description: Restroom 13 - N/Sink Caulking (White)

Analyzed Non-Asbestos **TEST** Non-Fibrous Date Color Fibrous Asbestos Comment PLM 8/17/2020 White 0.0% 100.0% None Detected Lab Sample ID: Client Sample ID: 042019627-0026

Sample Description: Restroom 2 - N/Sink Caulking (White)

Analyzed Non-Asbestos **TEST** Date Color **Fibrous** Non-Fibrous Asbestos Comment PLM 8/17/2020 White 0.0% 100.0% None Detected Lab Sample ID: 042019627-0027 Client Sample ID: 21A

Sample Description: Lobby - N/Stone Grout (Gray)

Non-Asbestos Analyzed Fibrous Non-Fibrous TEST Date Color Asbestos Comment PLM 8/17/2020 0.0% 100.0% None Detected Gray 042019627-0028 Lab Sample ID: Client Sample ID:

Sample Description: Exterior - W/Stone Grout (Gray)

Analyzed Non-Asbestos **TEST** Date Color **Fibrous** Non-Fibrous **Asbestos** Comment PLM 8/17/2020 None Detected Gray 0.0% 100.0%



200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

042019627 32ANDE85

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

Lab Sample ID: 042019627-0029 Client Sample ID:

Sample Description: Exterior - N/Stucco

	Analyzed		Non-	-Asbestos			
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Gray	0.0%	100.0%	<1% Chrysotile		
1000 PLM Pt Ct	8/25/2020	Gray	0.00%	99.90%	0.1% Chrysotile		

Lab Sample ID: 042019627-0030 Client Sample ID: 22B

Sample Description: Exterior - NE/Stucco

	Analyzed		Non-	Asbestos			
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Gray	0.0%	100.0%	<1% Chrysotile		
1000 PLM Pt Ct	8/25/2020	Gray	0.00%	99.80%	0.2% Chrysotile		

22C Lab Sample ID: 042019627-0031 Client Sample ID:

Sample Description: Exterior - E/Stucco

	Analyzed		Non-	-Asbestos			
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Gray	0.0%	100.0%	<1% Chrysotile		
1000 PLM Pt Ct	8/25/2020	Gray	0.0%	100.0%	<0.1% Chrysotile		

Lab Sample ID: 042019627-0032 Client Sample ID:

Sample Description: Exterior - S/Stucco

	Analyzed		Non-Asbest	os		
TEST	Date	Color	Fibrous Non-F	brous Asbestos	Comment	
PLM	8/17/2020	White	0.0% 100	0.0% None Detect	ed	

042019627-0033 Lab Sample ID: Client Sample ID: 22E

Sample Description: Exterior - SW/Stucco

	Analyzed		Non-	Asbestos		
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment
PLM	8/17/2020	White	0.0%	100.0%	None Detected	

Lab Sample ID: 042019627-0034 Client Sample ID:

Sample Description: Exterior -W/Stucco

	Analyzed		Non-Asb	estos			
TEST	Date	Color	Fibrous No	n-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Gray	0.0%	100.0%	<1% Chrysotile		
1000 PLM Pt Ct	8/25/2020	Gray	0.00%	99.80%	0.2% Chrysotile		

Client Sample ID: Lab Sample ID: 042019627-0035

Sample Description: Exterior -W/Stucco

	Analyzed		Non-	Asbestos			
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Gray	0.0%	100.0%	<1% Chrysotile		
1000 PLM Pt Ct	8/25/2020	Gray	0.00%	99.90%	0.1% Chrysotile		



200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

042019627

32ANDE85

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

Client Sample ID:	23B					Lab Sample ID:	042019627-0036
Sample Description:	Changing Rm 1-N/Carpet A	dhesive (Tan)					
TEOT	Analyzed	Onlan.		sbestos	Ashastas	0	
TEST	Date	Color		Non-Fibrous	Asbestos	Comment Result includes a	amall amount of
PLM	8/17/2020	Tan/White	0.0%	96.0%	4% Chrysotile	inseparable attach	
Client Sample ID:	24A					Lab Sample ID:	042019627-0037
Sample Description:	Room 126 - NW/VSF (White	e Speckled)					
TEST	Analyzed Date	Color		sbestos Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	White	15.0%	85.0%	None Detected	Comment	
		Wille	10.070	00.070	None Detected	Lab Sampla ID:	0.4004.0007.0000
Client Sample ID:	24B					Lab Sample ID:	042019627-0038
Sample Description:	Room 126 - N/VSF (White S	speckled)					
	Analyzed		Non-A	sbestos			
TEST	Date	Color	Fibrous I	Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	White	25.0%	75.0%	None Detected		
Client Sample ID:	25A					Lab Sample ID:	042019627-0039
Sample Description:	Restroom 3 - W/VSF (Green	n Speckled)					
		-					
	Analyzed			sbestos		_	
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Green	23.0%	77.0%	None Detected		
Client Sample ID:	25B					Lab Sample ID:	042019627-0040
Sample Description:	Restroom 3 - NW/VSF (Gre	en Speckled)					
	Analyzed		Non-A	sbestos			
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Green	35.0%	65.0%	None Detected		
Client Sample ID:	26A-VSF					Lab Sample ID:	042019627-0041
Sample Description:	Utility Room 7 - E/VSF (Gra	y Pebble Pattern)				-	
- -	, (,					
	Analyzed			sbestos			
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Gray	20.0%	80.0%	None Detected		
Client Sample ID:	26A-Mastic					Lab Sample ID:	042019627-0041A
Sample Description:	Utility Room 7 - E/Mastic						
	Analyzad		Non A	sbestos			
TEST	Analyzed Date	Color		Aspestos Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	White/Yellow	0.0%	100.0%	None Detected	Result includes a	small amount of
						inseparable attach	ed leveler.
							04004000= 0040
· ·	26B-VSF					Lab Sample ID:	042019627-0042
· ·	26B-VSF Utility Room 7 - E/VSF (Gra	y Pebble Pattern)				Lab Sample ID:	042019627-0042
Client Sample ID: Sample Description:		y Pebble Pattern)	No. A	sbestos		Lab Sample ID:	042019627-0042

20.0%

Gray

80.0%

None Detected

PLM

8/17/2020



EMSL Analytical, Inc.

200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Lab Sample ID:

Project ID:

042019627

32ANDE85

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

Lab Sample ID: 042019627-0042A Client Sample ID: 26B-Mastic

Sample Description: Utility Room 7 - E/Mastic

26C-VSF

Analyzed Non-Asbestos **TEST** Date Color Fibrous Non-Fibrous Asbestos Comment PLM 8/17/2020 White/Yellow 0.0% 100.0% Result includes a small amount of None Detected inseparable attached leveler 042019627-0043

Sample Description: Room 149 - NW/VSF (Gray Pebble Pattern)

Non-Asbestos Analyzed **TEST** Date Color Fibrous Non-Fibrous **Asbestos** Comment PLM 15% Chrysotile Sample is not homogeneous with others in 8/17/2020 Gray 20.0% 65.0% HA group.

Lab Sample ID: 042019627-0043A Client Sample ID: 26C-Mastic

Sample Description: Room 149 - NW/Mastic

Analyzed Non-Asbestos TEST Date Color Fibrous Non-Fibrous **Asbestos** Comment PLM Result includes a small amount of 8/17/2020 White/Yellow 0.0% 100.0% None Detected inseparable attached leveler Lab Sample ID: 042019627-0044 Client Sample ID: 27A-VFT

Sample Description: Room 106 - SW/VFT (White 12x12)

Analyzed Non-Asbestos **TEST** Date Color **Fibrous** Non-Fibrous **Asbestos** Comment PLM 8/17/2020 White 0.0% 100.0% None Detected

042019627-0044A Lab Sample ID: Client Sample ID: 27A-Adhesive

Sample Description: Room 106 - SW/Adhesive

Analyzed Non-Asbestos TEST Date **Fibrous** Non-Fibrous Comment Color Asbestos PLM 8/17/2020 100.0% Yellow 0.0% None Detected

Lab Sample ID: 042019627-0045 Client Sample ID: 27B-VFT

Sample Description: Room 158 - NW/VFT (White 12x12)

Analyzed Non-Asbestos TEST Date Color Fibrous Non-Fibrous Asbestos Comment PLM 8/17/2020 White 0.0% 100.0% None Detected 042019627-0045A Client Sample ID: 27B-Adhesive Lab Sample ID:

Sample Description: Room 158 - NW/Adhesive

Analyzed Non-Asbestos **TEST** Date Non-Fibrous Comment Fibrous Asbestos Color PLM 8/17/2020 Yellow 0.0% 100.0% None Detected

Client Sample ID: 27C-VFT Lab Sample ID: 042019627-0046

Sample Description: Room 159 - NE/VFT (White 12x12)

Analyzed Non-Asbestos **TEST** Date Color Fibrous Non-Fibrous Asbestos Comment PLM 8/17/2020 White 0.0% 100.0% None Detected



200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

042019627 32ANDE85

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

Lab Sample ID: 042019627-0046A Client Sample ID: 27C-Adhesive Sample Description: Room 159 - NE/Adhesive

Analyzed Non-Asbestos **TEST** Date Color Fibrous Non-Fibrous Asbestos Comment PLM 8/17/2020 Yellow 0.0% 100.0% None Detected Client Sample ID: 28A-VFT Lab Sample ID: 042019627-0047

Sample Description: 2nd Floor Room 250 - E/VFT (Cream 12x12)

Analyzed Non-Asbestos TEST Date Non-Fibrous Comment Color **Fibrous** Asbestos PLM 8/17/2020 White/Beige 0.0% 100.0% None Detected Lab Sample ID: Client Sample ID: 28A-Adhesive 042019627-0047A

Sample Description: 2nd Floor Room 250 - E/Adhesive

Analyzed Non-Asbestos **TEST** Date Color **Fibrous** Non-Fibrous Asbestos Comment PLM 8/17/2020 Yellow 0.0% 100.0% None Detected

Lab Sample ID: 042019627-0048 Client Sample ID: 28B-VFT

Sample Description: 2nd Floor Hall - Center/VFT (Cream 12x12)

Analyzed Non-Asbestos **TEST** Date Color Fibrous Non-Fibrous Asbestos Comment PLM 8/17/2020 White/Beige 0.0% 100.0% None Detected 042019627-0048A Lab Sample ID: Client Sample ID: 28B-Adhesive

Sample Description: 2nd Floor Hall - Center/Adhesive

Analyzed Non-Asbestos **TEST** Date **Fibrous** Non-Fibrous **Asbestos** Comment Color PLM 8/17/2020 Yellow 0.0% 100.0% None Detected

29A-VFT Lab Sample ID: 042019627-0049 Client Sample ID:

Sample Description: Room 155 - SE/VFT (Blue Marbled 12x12)

Non-Asbestos Analyzed TEST Fibrous Non-Fibrous Comment Date Color Asbestos PLM 8/17/2020 Blue 0.0% 100.0% None Detected

29A-Adhesive Lab Sample ID: 042019627-0049A Client Sample ID:

Sample Description: Room 155 - SE/Adhesive

Analyzed Non-Asbestos Comment **TEST** Date Color **Fibrous** Non-Fibrous **Asbestos** PLM 8/17/2020 Yellow 0.0% 100.0% None Detected Lab Sample ID: 042019627-0050 29B-VFT Client Sample ID:

Sample Description: Room 158 - NW/VFT (Blue Marbled 12x12)

Analyzed Non-Asbestos Non-Fibrous **TEST** Date Color Fibrous Asbestos Comment PLM 8/17/2020 Blue 0.0% 100.0% None Detected



Client Sample ID:

EMSL Analytical, Inc.

200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Lab Sample ID:

Project ID:

042019627

32ANDE85

042019627-0051A

042019627-0052

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

Lab Sample ID: 042019627-0050A Client Sample ID: 29B-Adhesive

Sample Description: Room 158 - NW/Adhesive

Analyzed Non-Asbestos **TEST** Date Color Fibrous Non-Fibrous Asbestos Comment PLM 8/17/2020 Yellow 0.0% 100.0% None Detected Client Sample ID: 30A-VFT Lab Sample ID: 042019627-0051

Sample Description: Utility Room 2 - N/VFT (Gray with White Streaks 12x12)

Analyzed Non-Asbestos TEST Date **Fibrous** Non-Fibrous Comment Color Asbestos PLM 8/17/2020 Gray/White 0.0% 94.0% 6% Chrysotile Lab Sample ID:

Sample Description: Utility Room 2 - N/Adhesive

30B-VFT

30A-Adhesive

Analyzed Non-Asbestos **TEST** Date Color **Fibrous** Non-Fibrous Asbestos Comment PLM 8/17/2020 Tan 0.0% 100.0% None Detected

Sample Description: Utility Room 2 - S/VFT (Gray with White Streaks 12x12)

Analyzed Non-Asbestos **TEST** Date Color Fibrous Non-Fibrous Asbestos Comment PLM 8/17/2020 Gray 0.0% 94.0% 6% Chrysotile Lab Sample ID: 042019627-0052A Client Sample ID: 30B-Adhesive

Sample Description: Utility Room 2 - S/Adhesive

Analyzed Non-Asbestos **TEST** Date Non-Fibrous **Asbestos** Comment Color **Fibrous** PLM 8/17/2020 Tan 0.0% 100.0% None Detected

31A-VFT Lab Sample ID: 042019627-0053 Client Sample ID:

Sample Description: Room 137 - NW/VFT (Brown Marbled 12x12)

Non-Asbestos Analyzed TEST Fibrous Non-Fibrous Comment Date Asbestos Color PLM 8/17/2020 0.0% 100.0% None Detected Brown 31A-Adhesive Lab Sample ID: 042019627-0053A

Client Sample ID:

Sample Description: Room 137 - NW/Adhesive

Analyzed Non-Asbestos Comment **TEST** Date Color **Fibrous** Non-Fibrous **Asbestos** PLM 8/17/2020 Yellow 0.0% 100.0% None Detected Lab Sample ID: 042019627-0054 31B-VFT Client Sample ID:

Sample Description: Room 137 - W/VFT (Brown Marbled 12x12)

Analyzed Non-Asbestos **TEST** Date Color Fibrous Non-Fibrous Asbestos Comment PLM 8/17/2020 Brown 0.0% 100.0% None Detected



EMSL Analytical, Inc.

200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

042019627

042019627-0055A

32ANDE85

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

Lab Sample ID: 042019627-0054A Client Sample ID: 31B-Adhesive

Sample Description: Room 137 - W/Adhesive

Analyzed Non-Asbestos **TEST** Date Color Fibrous Non-Fibrous Asbestos Comment PLM 8/17/2020 Yellow 0.0% 100.0% None Detected Client Sample ID: 32A-VFT Lab Sample ID: 042019627-0055

Sample Description: 1st Floor - Lobby - N/VFT (Green Marbled 12x12)

Analyzed Non-Asbestos TEST Date **Fibrous** Non-Fibrous Comment Color Asbestos PLM 8/17/2020 Green 0.0% 100.0% None Detected Lab Sample ID:

Client Sample ID: 32A-Adhesive

Sample Description: 1st Floor - Lobby - N/Adhesive

32B-VFT

Analyzed Non-Asbestos **TEST** Date Color **Fibrous** Non-Fibrous Asbestos Comment PLM 8/17/2020 Yellow 0.0% 100.0% None Detected Lab Sample ID: 042019627-0056

Sample Description: 2nd Floor - Staff Lounge - SW/VFT (Green Marbled 12x12)

Analyzed Non-Asbestos **TEST** Date Color Fibrous Non-Fibrous Asbestos Comment PLM 8/17/2020 Green 0.0% 100.0% None Detected 042019627-0056A Lab Sample ID: Client Sample ID: 32B-Adhesive

Sample Description: 2nd Floor - Staff Lounge - SW/Adhesive

Analyzed Non-Asbestos **TEST Fibrous** Non-Fibrous **Asbestos** Comment Date Color PLM 8/17/2020 Yellow 0.0% 100.0% None Detected

32C-VFT Lab Sample ID: 042019627-0057 Client Sample ID:

Sample Description: 2nd Floor - Staff Lounge - S/VFT (Green Marbled 12x12)

Analyzed Non-Asbestos TEST Fibrous Non-Fibrous Comment Date Color Asbestos PLM 8/17/2020 0.0% 100.0% None Detected Green 32C-Adhesive Lab Sample ID: 042019627-0057A Client Sample ID:

Sample Description: 2nd Floor - Staff Lounge - S/Adhesive

Analyzed Non-Asbestos Comment **TEST** Date Color **Fibrous** Non-Fibrous **Asbestos** PLM 8/17/2020 Yellow 0.0% 100.0% None Detected 33A-VFT Lab Sample ID: 042019627-0058 Client Sample ID:

Sample Description: 2nd Floor - Staff Lounge - S/VFT (Grey 12x12)

Analyzed Non-Asbestos Non-Fibrous **TEST** Date Color Fibrous Asbestos Comment PLM 8/17/2020 Gray 0.0% 100.0% None Detected



EMSL Analytical, Inc.

200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

042019627 32ANDE85

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

Lab Sample ID: 042019627-0058A Client Sample ID: 33A-Adhesive

Sample Description: 2nd Floor - Staff Lounge - S/Adhesive

		Analyzed		Non	-Asbestos				
TEST		Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment		
PLM		8/17/2020	Black/Yellow	5.0%	95.0%	None Detected			
Client Sample ID:	33B-VFT						Lab Sample ID:	042019627-0059	

Sample Description: 2nd Floor Windowed Hall - N/VFT (Grey 12x12)

	Analyzed		Non	-Asbestos			
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Gray	0.0%	100.0%	None Detected		
Client Sample ID:	33B-Adhesive					Lab Sample ID:	042019627-0059A

Sample Description: 2nd Floor Windowed Hall - N/Adhesive

		Analyzed		Non	-Asbestos				
TEST		Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment		
PLM		8/17/2020	Yellow	0.0%	100.0%	None Detected			_
Client Sample ID:	33C-VFT						Lab Sample ID:	042019627-0060	

Sample Description: 2nd Floor - In Front of Room 248 - W/VFT (Grey 12x12)

	Analyzed		Non	-Asbestos			
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Gray	0.0%	100.0%	None Detected		
Client Sample ID:	33C-Adhesive					Lab Sample ID:	042019627-0060A

Sample Description: 2nd Floor - In Front of Room 248 - W/Adhesive

		Analyzed		Non	-Asbestos			
TEST		Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM		8/17/2020	Yellow	0.0%	100.0%	None Detected		
Client Sample ID:	34A-VFT						Lab Sample ID:	042019627-0061

Client Sample ID:

Sample Description: Lobby - SW/VFT (Light Green)

	Analyzed		Non	-Asbestos				
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment		
PLM	8/17/2020	Green	0.0%	100.0%	None Detected			
Client Sample ID:	34A-Adhesive					Lab Sample ID:	042019627-0061A	

Sample Description: Lobby - SW/Adhesive

	Analyzed Non		-Asbestos					
TEST		Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM		8/17/2020	Yellow	0.0%	100.0%	None Detected		
Client Sample ID:	34B-VFT					_	Lab Sample ID:	042019627-0062

Sample Description: Lobby - S/VFT (Light Green)

	Analyzed		Non-Asb	estos		
TEST	Date	Color	Fibrous Nor	n-Fibrous	Asbestos	Comment
PLM	8/17/2020	Green		100.0%	None Detected	



200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

042019627

32ANDE85

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

Oliant Carry II ID	Summary Test Rep	2011 101 730	Join Analysis Of	San matorial via L		
Client Sample ID:	34B-Adhesive				Lab Sample ID:	042019627-0062A
Sample Description:	Lobby - S/Adhesive					
	Analyzed		Non-Asbestos			
TEST	Date	Color	Fibrous Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Yellow	0.0% 100.0%	None Detected		
Client Sample ID:	35A				Lab Sample ID:	042019627-0063
Sample Description:	Room 130 - N/Floor Texture	e Coating				
		J				
	Analyzed		Non-Asbestos			
TEST	Date	Color	Fibrous Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	White	0.0% 100.0%	None Detected		
Client Sample ID:	35B				Lab Sample ID:	042019627-0064
Sample Description:	Room 130 - E/Floor Texture	Coating				
TEST	Analyzed	Co!	Non-Asbestos	A-b4	Cam	
TEST PLM	8/14/2020	Color White	Fibrous Non-Fibrous 0.0% 100.0%	Asbestos None Detected	Comment	
		vviille	0.0% 100.0%	None Detected		
Client Sample ID:	35C				Lab Sample ID:	042019627-0065
Sample Description:	Room 130 - W/Floor Texture	e Coating				
	Analyzod		Non-Asbestos			
TEST	Analyzed Date	Color	Fibrous Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	White	0.0% 100.0%	None Detected		
Client Sample ID:	36A-Floor Tile				Lab Sample ID:	042019627-0066
Sample Description:	Restroom 12 NE/Floor Tile	(1v1 \M\hito)			Zaz Gampie iz.	042010021 0000
sampre Becompain.	Restroom 12 NE/Floor me	(TXT WITHE)				
	Analyzed		Non-Asbestos			
TEST	Date	Color	Fibrous Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	White/Blue	0.0% 100.0%	None Detected		
Client Sample ID:	36A-Grout				Lab Sample ID:	042019627-0066A
Sample Description:	Restroom 12 NE/Grout					
	Analyzed		Non-Asbestos			
TEST	Date	Color	Fibrous Non-Fibrous		Comment	
PLM 	8/14/2020	Gray	0.0% 100.0%	None Detected		
Client Sample ID:	36A-Leveler				Lab Sample ID:	042019627-0066B
Sample Description:	Restroom 12 NE/Leveler					
			<u>.</u>			
TEST	Analyzed	Color	Non-Asbestos Fibrous Non-Fibrous	Achastas	Commont	
TEST PLM	8/14/2020	Color Gray	0.0% 100.0%	Asbestos None Detected	Comment	
		Glay	0.070 100.070	Note Defected	1 - 1 - 0 1 - 1 -	040040007 0007
Client Sample ID:	36B-Floor Tile				Lab Sample ID:	042019627-0067
Sample Description:	Restroom 13 N/Floor Tile (1	x1 White)				
	Anglyzad		Non Ashastas			
TEST	Analyzed Date	Color	Non-Asbestos Fibrous Non-Fibrous	Asbestos	Comment	
	0.47/0000	20.01	0.00/ 400.00/			

8/17/2020

Gray

0.0%

100.0%

None Detected



200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

042019627 32ANDE85

Summary Tost Panort for Ashastos Analysis of Rulk Material via EPA 600/P-93/116

	Summary Test Re	port for Asb	estos An	alysis of Bul	lk Material via E	PA 600/R-93/	116
Client Sample ID:	36B-Grout					Lab Sample ID:	042019627-0067A
Sample Description:	Restroom 13 N/Grout						
	Analyzed			-Asbestos		_	
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Gray	0.0%	100.0%	None Detected		
Client Sample ID:	36B-Leveler					Lab Sample ID:	042019627-0067B
Sample Description:	Restroom 13 N/Leveler						
TEST	Analyzed Date	Color		-Asbestos Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Gray	0.0%		None Detected	Comment	
					None Beledied	Lab Cample ID:	040040007.0000
Client Sample ID:	37A-Floor Tile					Lab Sample ID:	042019627-0068
Sample Description:	Restroom 9/Floor Tile (1x1	Tan)					
	Analyzed		Non	-Asbestos			
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	Tan/White	0.0%		None Detected		
Client Sample ID:	37A-Grout					Lab Sample ID:	042019627-0068A
Sample Description:	Restroom 9/Grout					zas campie iz.	042010021 000070
Campie Becompation.	Nestroom 9/Grout						
	Analyzed		Non	-Asbestos			
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	Gray	0.0%	100.0%	None Detected		
Client Sample ID:	37B-Floor Tile					Lab Sample ID:	042019627-0069
Sample Description:	Restroom 10/Floor Tile (1x	1 Tan)					
	(,					
	Analyzed		Non	-Asbestos			
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Tan	0.0%	100.0%	None Detected		
Client Sample ID:	37B-Grout					Lab Sample ID:	042019627-0069A
Sample Description:	Restroom 10/Grout						
	Analyzed			-Asbestos			
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Gray	0.0%	100.0%	None Detected		
Client Sample ID:	37B-Leveler					Lab Sample ID:	042019627-0069B
Sample Description:	Restroom 10/Leveler						
TEST	Analyzed	Color		-Asbestos	Anhestes	Commont	
PLM	8/17/2020	Color Gray/White	0.0%	Non-Fibrous 100.0%	Asbestos None Detected	Comment	
		Gray/Wille	0.0%	100.070	Notic Defected	1.1.0. 1.5	0.400.40.007.007.
Client Sample ID:	38A-Wall Tile					Lab Sample ID:	042019627-0070
Sample Description:	Restroom 3/Wall Tile (4x4 I	Blue)					
	A t		Mari	Ashantas			
TEST	Analyzed Date	Color		-Asbestos Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	White	0.0%		None Detected		
	0/11/2020		0.070				



200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

042019627

32ANDE85

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

	Summary Test Re	port for Asb	estos Anai	ysis of Bui	K Materiai via E	PA 600/R-93/	116
Client Sample ID:	38A-Grout					Lab Sample ID:	042019627-0070A
Sample Description:	Restroom 3/Grout						
	Analyzed		Non-As				
TEST	Date	Color	Fibrous No		Asbestos	Comment	
PLM	8/14/2020	White	0.0%	100.0%	None Detected		
Client Sample ID:	38A-Leveler					Lab Sample ID:	042019627-0070B
Sample Description:	Restroom 3/Leveler						
	Analyzed		Non-As				
TEST	Date	Color	Fibrous No		Asbestos	Comment	
PLM	8/14/2020	Gray	0.0%	100.0%	None Detected		
Client Sample ID:	38A-Mastic					Lab Sample ID:	042019627-0070C
Sample Description:	Restroom 3/Mastic						
	Analyzed		Non-As				
TEST	Date	Color	Fibrous No		Asbestos	Comment	
PLM	8/14/2020	Yellow	0.0%	100.0%	None Detected		
Client Sample ID:	38B-Wall Tile					Lab Sample ID:	042019627-0071
Sample Description:	Restroom 3/Wall Tile (4x4	Blue)					
	Analyzed		Non-As	bestos			
TEST	Date	Color	Fibrous No	on-Fibrous	Asbestos	Comment	
PLM	8/14/2020	White/Blue	0.0%	100.0%	None Detected		
Client Sample ID:	38B-Leveler					Lab Sample ID:	042019627-0071A
Sample Description:	Restroom 3/Leveler						
	Analyzed		Non-As	bestos			
TEST	Date	Color	Fibrous No	on-Fibrous	Asbestos	Comment	
PLM	8/14/2020	Gray	0.0%	100.0%	None Detected		
Client Sample ID:	38B-Mastic					Lab Sample ID:	042019627-0071B
Sample Description:	Restroom 3/Mastic						
	Analyzed		Non-As	bestos			
TEST	Date	Color	Fibrous No	on-Fibrous	Asbestos	Comment	
PLM	8/14/2020	Yellow	0.0%	100.0%	None Detected		
Client Sample ID:	38C-Wall Tile					Lab Sample ID:	042019627-0072
Sample Description:	Restroom 12/Wall Tile (4x4	4 Blue)				-	
	. 100.00 12/17dii 1110 (4A-	,					
	Analyzed		Non-As	bestos			
TEST	Date	Color	Fibrous No		Asbestos	Comment	
PLM	8/17/2020	White/Blue	0.0%	100.0%	None Detected		
Client Sample ID:	38C-Grout					Lab Sample ID:	042019627-0072A
Sample Description:	Restroom 12/Grout						
zapro z osoripuon.	17621100111 12/G1001						
	Analyzed		Non-As	bestos			
TEST	Date	Color	Fibrous No		Asbestos	Comment	
5114	0/47/0000	10.0.	0.00/	400.00/		-	

8/17/2020

White

0.0%

100.0%

None Detected



200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

042019627

32ANDE85

	Summary restrict	port for ASD	estos An	alysis of bu	lk Material via E	PA 600/K-33/	110
Client Sample ID:	38C-Plaster					Lab Sample ID:	042019627-0072B
Sample Description:	Restroom 12/Plaster						
	Analyzed			-Asbestos		_	
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Gray	0.0%	100.0%	None Detected		
Client Sample ID:	39A					Lab Sample ID:	042019627-0073
Sample Description:	Chaning Room - W/Wall Ti	le (4x4 Blue)					
TEST	Analyzed Date	Color		-Asbestos Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	Blue	0.0%	100.0%	None Detected	Comment	
					None Beledied	Lab Cample ID:	0.400.400.07.007.4
Client Sample ID:	39B-Wall Tile					Lab Sample ID:	042019627-0074
Sample Description:	Restroom 5 - E/Wall Tile (4	x4 Blue)					
	Analyzed		Non	-Asbestos			
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	White/Pink	0.0%	100.0%	None Detected		
Client Sample ID:	39B-Grout					Lab Sample ID:	042019627-0074A
Sample Description:	Restroom 5 - E/Grout						
campic Becompation.	Restroom 3 - L/Grout						
	Analyzed		Non-	-Asbestos			
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	White	0.0%	100.0%	None Detected		
Client Sample ID:	40A-Wall Tile					Lab Sample ID:	042019627-0075
Sample Description:	Restroom 4 - S/Wall Tile (F	Pink 4x4)					
	,	,					
	Analyzed		Non	-Asbestos			
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	Pink	0.0%	100.0%	None Detected		
Client Sample ID:	40A-Leveler					Lab Sample ID:	042019627-0075A
Sample Description:	Restroom 4 - S/Leveler						
TEOT	Analyzed	0.1		-Asbestos	A . I	0	
TEST PLM	Date 9/44/2020	Color		Non-Fibrous	Asbestos	Comment	
	8/14/2020	Gray	0.0%	100.0%	None Detected		
Client Sample ID:	40A-Joint Compound					Lab Sample ID:	042019627-0075B
Sample Description:	Restroom 4 - S/Joint Comp	oound					
	A national		Ne:-	-Asbestos			
TEST	Analyzed Date	Color		-Asbestos Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	White	0.0%	98.0%	2% Chrysotile		
Client Sample ID:	40B-Wall Tile				,,,,,,,,	Lab Sample ID:	042019627-0076
Sample Description:		Starte AccAN				Lab Sample ID.	042013027-0070
затріє везсприоп:	Restroom 6 - N/Wall Tile (F	rink 4x4)					
	Analyzed		Non	-Asbestos			
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	White/Pink	0.0%	100.0%	None Detected		



200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

042019627 32ANDE85

	Summary Test Rep	ort for As	bestos An	alysis of Bu	ik Materiai via E	PA 600/R-93/	116
Client Sample ID:	40B-Plaster					Lab Sample ID:	042019627-0076A
Sample Description:	Restroom 6 - N/Plaster						
	Analyzed		Non-	Asbestos			
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Gray	0.0%	100.0%	None Detected		
Client Sample ID:	40B-Joint Compound					Lab Sample ID:	042019627-0076B
Sample Description:	Restroom 6 - N/Joint Compo	und				•	
, , , , , , , , , , , , , , , , , , , ,	reseasement research	ana					
	Analyzed		Non-	Asbestos			
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	White	0.0%	98.0%	2% Chrysotile		
Client Sample ID:	41A-Wall Tile					Lab Sample ID:	042019627-0077
Sample Description:	Kitchen 160 - S/Wall Tile (Br	own 4x4)					
	Analyzed			Asbestos			
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	Brown	0.0%	100.0%	None Detected		
Client Sample ID:	41A-Grout					Lab Sample ID:	042019627-0077A
Sample Description:	Kitchen 160 - S/Grout						
	A. a. b		No.	A - b 4			
TEST	Analyzed Date	Color		Asbestos Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	Gray	0.0%	100.0%	None Detected		
Client Sample ID:	41A-Leveler	· · · · · · · · · · · · · · · · · · ·				Lab Sample ID:	042019627-0077B
Client Sample ID: Sample Description:						Lub Gampie ib.	042013027-00772
sample Bescription.	Kitchen 160 - S/Leveler						
	Analyzed		Non-	Asbestos			
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	Black	0.0%	100.0%	None Detected		
Client Sample ID:	41A-Joint Compound					Lab Sample ID:	042019627-0077C
Sample Description:	Kitchen 160 - S/Joint Compo	und					
	Analyzed		Non-	Asbestos			
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	White	0.0%	100.0%	None Detected		
Client Sample ID:	41B-Wall Tile					Lab Sample ID:	042019627-0078
Sample Description:	Utility Rm 6 - SE/Wall Tile (B	rown 4x4)					
TEST	Analyzed	Calar		Asbestos	Anhartas	Comment	
TEST PLM	8/17/2020	Color Brown	0.0%	Non-Fibrous 100.0%	Asbestos None Detected	Comment	
		DIOWII	0.076	100.070	None Detected	1-6-0	040040057 0070 :
Client Sample ID:	41B-Grout					Lab Sample ID:	042019627-0078A
Sample Description:	Utility Rm 6 - SE/Grout						
	Analyzed		Non	Asbestos			
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
	Duto	00101	. 151043		Acadotos		

8/17/2020

Brown

0.0%

100.0%

None Detected



200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

042019627 32ANDE85

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

Client Sample ID:	41B-Leveler		•		Lab Sample ID:	042019627-0078B
Sample Description:	Utility Rm 6 - SE/Leveler					
	Analyzed		Non-Asbestos			
TEST	Date	Color	Fibrous Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Black	0.0% 100.0%	None Detected		
Client Sample ID:	41B-Joint Compound				Lab Sample ID:	042019627-0078C
Sample Description:	Utility Rm 6 - SE/Joint Com	pound				
	Analyzed		Non-Asbestos			
TEST	Date	Color	Fibrous Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	White	0.0% 100.0%	None Detected		
Client Sample ID:	42A-Wall Tile				Lab Sample ID:	042019627-0079
Sample Description:	Restroom 13 - N/Wall Tile (Salmon 4x4)				
	Analyzed		Non-Asbestos			
TEST	Date	Color	Fibrous Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	Pink	0.0% 100.0%	None Detected		
Client Sample ID:	42A-Grout				Lab Sample ID:	042019627-0079A
Sample Description:	Restroom 13 - N/Grout					
	Analyzed		Non-Asbestos			
TEST	Date	Color	Fibrous Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	White	0.0% 100.0%	None Detected		
Client Sample ID:	42B-Wall Tile				Lab Sample ID:	042019627-0080
Sample Description:	Utility Rm 6 - N/Wall Tile (S	almon 4x4)				
	Analyzed		Non-Asbestos			
TEST	Date	Color	Fibrous Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	White/Pink	0.0% 100.0%	None Detected		
Client Sample ID:	42B-Grout				Lab Sample ID:	042019627-0080A
Sample Description:	Utility Rm 6 - N/Grout					
	Analyzed		Non-Asbestos			
TEST	Date	Color	Fibrous Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	White	0.0% 100.0%	None Detected		
Client Sample ID:	43A				Lab Sample ID:	042019627-0081
Sample Description:	Restroom 9 - W/Wall Tile (E	Black 4x4)				
	Analyzed		Non-Asbestos			
TEST	Date	Color	Fibrous Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	White/Black	0.0% 100.0%	None Detected		
Client Sample ID:	43B				Lab Sample ID:	042019627-0082
Sample Description:	Restroom 9 - W/Wall Tile (E	Black 4x4)				
	Analyzed		Non-Asbestos			
TEST	Date	Color	Fibrous Non-Fibrous	Asbestos	Comment	

100.0%

0.0%

None Detected

PLM

8/17/2020

White/Black



200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

042019627 32ANDE85

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

Oliant Came II ID	Summary Test Repo			,			
Client Sample ID:	46C					Lab Sample ID:	042019627-0083
Sample Description:	North Roof - S/Roofing Mastic	(Black)					
	Analyzed		Non-As	sbestos			
TEST	Date	Color	Fibrous N		Asbestos	Comment	
PLM	8/17/2020	Black	0.0%	96.0%	4% Chrysotile		
Client Sample ID:	44A-Tar Felt					Lab Sample ID:	042019627-0084
Sample Description:	North Rolled on Roof - East/Ta	r Felt					
	Analyzed		Non-As	sbestos			
TEST	Date	Color	Fibrous N		Asbestos	Comment	
PLM	8/14/2020	Black	75.0%	25.0%	None Detected		
Client Sample ID:	44A-Tar					Lab Sample ID:	042019627-0084A
Sample Description:	North Rolled on Roof - East/Ta	r					
TEST	Analyzed	Color		sbestos	Ashast	Comment	
TEST PLM	8/14/2020	Color Black	Fibrous N	100.0%	Asbestos None Detected	Comment	
		DIACK	0.070	100.070	Notic Defected	1-6-0	040040007 0007
Client Sample ID:	44B-Tar Felt					Lab Sample ID:	042019627-0085
Sample Description:	North Rolled on Roof - East/Ta	r Felt					
	Analyzed		Non As	sbestos			
TEST	Date	Color	Fibrous N		Asbestos	Comment	
PLM	8/14/2020	Black	70.0%	30.0%	None Detected		
Client Sample ID:	44B-Tar					Lab Sample ID:	042019627-0085A
Sample Description:	North Rolled on Roof - East/Ta	r					
	Notti Notice of Noor - Lasty ra	ı					
	Analyzed		Non-As	sbestos			
TEST	Date	Color	Fibrous N	on-Fibrous	Asbestos	Comment	
PLM	8/14/2020	Black	0.0%	100.0%	None Detected		
Client Sample ID:	44C-Tar Felt					Lab Sample ID:	042019627-0086
Sample Description:	North Rolled on Roof - North/Ta	ar Felt					
	Analyzed		Non-As	sbestos			
TEST	Date	Color	Fibrous N		Asbestos	Comment	
PLM	8/14/2020	Black	80.0%	20.0%	None Detected		
Client Sample ID:	44C-Tar					Lab Sample ID:	042019627-0086A
Sample Description:	North Rolled on Roof - North/Ta	ar					
TEST	Analyzed	Color	Non-As Fibrous N	sbestos on Eibrous	Ashastas	Comment	
PLM	Date 8/14/2020	Color Black	0.0%	100.0%	Asbestos None Detected	Comment	
		Didok	0.070	100.070	14010 Detected	Lob Complete	042040627 00005
Client Sample ID:	44C-Membrane					Lab Sample ID:	042019627-0086B
Sample Description:	North Rolled on Roof - North/M	embrane					
	Analyzed		Non-As	chaetae			
TEST	Date	Color	Fibrous N		Asbestos	Comment	
DIM	9/14/2020	Crov	20.00/	90.00/	Nama Datastad		

20.0%

Gray

80.0%

None Detected

8/14/2020



200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

042019627 32ANDE85

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

Client Sample ID:	44D-Tar Felt	OI ASSESTED AII	aryono or Be	in material via El	Lab Sample ID:	042019627-0087
Sample Description:	North Rolled on Roof - North Cente	r/Tar Folt				0-12010027 0007
sampre Becompaism.	North Notice of Noor - North Cente	i/Tai Teit				
	Analyzed	Non	-Asbestos			
TEST	Date C	olor Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020 B	lack 80.0%	20.0%	None Detected		
Client Sample ID:	44D-Tar				Lab Sample ID:	042019627-0087A
Sample Description:	North Rolled on Roof - North Cente	r/Tar				
	Analyzed	Non	-Asbestos			
TEST			Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020 B	lack 0.0%	100.0%	None Detected		
Client Sample ID:	44E-Tar Felt				Lab Sample ID:	042019627-0088
Sample Description:	North Rolled on Roof - South Center	er/Tar Felt				
TEOT	Analyzed		-Asbestos	Asharta	0	
TEST PLM		olor Fibrous lack 60.0%	Non-Fibrous 40.0%	Asbestos Nana Datastad	Comment	
	8/11/2020 B	1ack 60.0%	40.0%	None Detected		
Client Sample ID:	44E-Tar				Lab Sample ID:	042019627-0088A
Sample Description:	North Rolled on Roof - South Cente	er/Tar				
TEST	Analyzed Date C		-Asbestos Non-Fibrous	Asbestos	Comment	
PLM		lack 0.0%		None Detected	Comment	
					Lab Sample ID:	042019627-0089
Client Sample ID:	44F-Tar Felt				Lab Sample ID.	042019021-0009
Sample Description:	North Rolled on Roof - Northeast/Ta	ar Felt				
	Analyzed	Non	-Asbestos			
TEST	-		Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020 B	lack 60.0%	40.0%	None Detected		
Client Sample ID:	44F-Tar				Lab Sample ID:	042019627-0089A
Sample Description:	North Rolled on Roof - Northeast/Ta	ar			,	
	Analyzed	Non	-Asbestos			
TEST	Date C	olor Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020 B	lack 0.0%	100.0%	None Detected		
Client Sample ID:	44F-Backing				Lab Sample ID:	042019627-0089B
Sample Description:	North Rolled on Roof - Northeast/Ba	acking				
		-				
	Analyzed	Non	-Asbestos			
TEST			Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020 Br	rown 98.0%	2.0%	None Detected		
Client Sample ID:	44G-Tar Felt				Lab Sample ID:	042019627-0090
Sample Description:	North Rolled on Roof - NorthWest/T	ar Felt				
	Analyzed		-Asbestos			
TEST	Date C	olor Fibrous	Non-Fibrous	Asbestos	Comment	

8/17/2020

Black

60.0%

40.0%

None Detected



200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

042019627

32ANDE85

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

Lab Sample ID: 042019627-0090A Client Sample ID: 44G-Tar

Sample Description: North Rolled on Roof - NorthWest/Tar

	Analyzed		Non	-Asbestos			
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Black	0.0%	100.0%	None Detected		
Client Sample ID:	44G-Backing					Lab Sample ID:	042019627-0090B

Sample Description: North Rolled on Roof - NorthWest/Backing

		Analyzed		Non	-Asbestos				
TEST		Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment		
PLM		8/17/2020	Brown	98.0%	2.0%	None Detected			
Client Sample ID:	45A						Lab Sample ID:	042019627-0091	

Sample Description: North Roof - N/Roofing Mastic (Black/White)

	Analyzed		Non-	-Asbestos			
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	White/Black	25.0%	75.0%	<1% Chrysotile		
1000 PLM PtCt Grav. Red.	8/25/2020	White/Black	0.0%	100%	<0.1% Chrysotile		

Lab Sample ID: 042019627-0092 Client Sample ID: 45B

Sample Description: North Roof - C/Roofing Mastic (Black/White)

	Analyzed		Non-	Asbestos		
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment
PLM	8/14/2020	White/Black	25.0%	75.0%	<1% Chrysotile	Result includes a small amount of inseparable attached material
1000 PLM PtCt Grav. Red.	8/25/2020	White/Black	0.0%	100%	<0.1% Chrysotile	

Lab Sample ID: 042019627-0093 Client Sample ID: 45C

Sample Description: North Roof - S/Roofing Mastic (Black/White)

		Analyzed		Non	-Asbestos				
TEST		Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment		
PLM		8/17/2020	White/Black	40.0%	60.0%	None Detected			
Client Sample ID:	46A						Lab Sample ID:	042019627-0094	

Sample Description: North Roof - N/Roofing Mastic (Black)

TEST	Date	Calar				_
	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment
PLM	8/14/2020	Gray/Black	0.0%	96.0%	4% Chrysotile	

Lab Sample ID: 042019627-0095 Client Sample ID: 46B

Sample Description: North Roof - C/Roofing Mastic (Black)

		Analyzed		Non	-Asbestos				
TEST		Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment		
PLM		8/14/2020	Gray/Black	0.0%	96.0%	4% Chrysotile			
Client Sample ID:	47A						Lab Sample ID:	042019627-0096	

Sample Description: North Roof - C/HVAC Mastic (Smooth Gray)

	Analyzed		Non-Asi	bestos		
TEST	Date	Color	Fibrous No	n-Fibrous	Asbestos	Comment
PLM	8/14/2020	Gray	6.0%	94.0%	None Detected	



200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

042019627

32ANDE85

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

		port for Asb	estos Analysis of	Buik Maleriai via E		
Client Sample ID:	47B				Lab Sample ID:	042019627-0097
Sample Description:	North Roof - S/HVAC Mas	tic (Smooth Gray)				
	Analyzod		Non-Asbestos			
TEST	Analyzed Date	Color	Fibrous Non-Fibrous	Asbestos	Comment	
PLM	8/14/2020	Gray/White	6.0% 94.0%	None Detected		
Client Sample ID:	47C				Lab Sample ID:	042019627-0098
Sample Description:	North Roof - S/HVAC Mas	tic (Smooth Gray)				042010021 0000
ampre 2000 i paom	Notti Nooi - 3/11VAC Mas	lic (Sillootii Gray)				
	Analyzed		Non-Asbestos			
TEST	Date	Color	Fibrous Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Gray/White	0.0% 100.0%	None Detected		
Client Sample ID:	48A				Lab Sample ID:	042019627-0099
Sample Description:	North Roof - S/HVAC Mas	tic (Textured White)				
		·				
	Analyzed		Non-Asbestos			
TEST	Date	Color	Fibrous Non-Fibrous	Asbestos	Comment	
PLM	8/15/2020	White	0.0% 100.0%	None Detected		
Client Sample ID:	48B				Lab Sample ID:	042019627-0100
Sample Description:	North Roof - S/HVAC Mas	tic (Textured White)				
	Analyzed		Non-Asbestos			
TEST PLM	8/15/2020	Color White	Fibrous Non-Fibrous 0.0% 100.0%	Asbestos None Detected	Comment	
		vviille	0.0% 100.0%	None Detected		
Client Sample ID:	48C				Lab Sample ID:	042019627-0101
Sample Description:	North Roof - E/HVAC Mas	tic (Textured White)				
	Analyzed		Non-Asbestos			
TEST	Date	Color	Fibrous Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	White	0.0% 100.0%	None Detected		
Client Sample ID:	49A				Lab Sample ID:	042019627-0102
Sample Description:	Center Roof - HVAC Ducti	ng SW/HV/AC Coo	ting (Crov)		Las Gampie is.	042010021 0102
p. 0 = 0001.p	Center Noor - TIVAC Ducti	ilg - SW/TVAC Coa	ung (Grey)			
	Analyzed		Non-Asbestos			
TEST	Date	Color	Fibrous Non-Fibrous	Asbestos	Comment	
PLM	8/15/2020	Gray	0.0% 100.0%	None Detected		
Client Sample ID:	49B				Lab Sample ID:	042019627-0103
Sample Description:	Center Roof - HVAC Ducti	ng - E/HVAC Coatin	g (Grey)			
		-				
	Analyzed		Non-Asbestos			
TEST	Date	Color	Fibrous Non-Fibrous	Asbestos	Comment	
PLM	8/15/2020	White/Black	0.0% 96.0%	4% Chrysotile		
Client Sample ID:	49C				Lab Sample ID:	042019627-0104
Sample Description:	Center Roof - HVAC Ducti	ng - Center/HVAC C	Coating (Grey)			
	Analyzed	_	Non-Asbestos		_	
TEST	Date	Color	Fibrous Non-Fibrous	Asbestos	Comment	

0.0%

100.0%

None Detected

8/17/2020

Gray



200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

042019627 32ANDE85

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

Lab Sample ID: 042019627-0105 Client Sample ID: 50A-Coating Sample Description: Center Roof - HVAC Ducting - S. Center/Vent Coating (White) Analyzed Non-Asbestos **TEST** Date Color Fibrous Non-Fibrous Asbestos Comment PLM 8/15/2020 White 0.0% 100.0% None Detected Client Sample ID: 50A-Mastic Lab Sample ID: 042019627-0105A Sample Description: Center Roof - HVAC Ducting - S. Center/Mastic Analyzed Non-Asbestos TEST Non-Fibrous Comment Date Color **Fibrous** Asbestos PLM 8/15/2020 Black 0.0% 95.0% 5% Chrysotile Lab Sample ID: Client Sample ID: 50B-Coating 042019627-0106 Sample Description: Center Roof - HVAC Ducting - Center/Vent Coating (White) Analyzed Non-Asbestos **TEST** Date Color **Fibrous** Non-Fibrous Asbestos Comment PLM 8/15/2020 White 0.0% 100.0% None Detected Lab Sample ID: 042019627-0106A Client Sample ID: 50B-Mastic Sample Description: Center Roof - HVAC Ducting - Center/Mastic Analyzed Non-Asbestos **TEST** Date Color Fibrous Non-Fibrous Asbestos Comment PLM 8/15/2020 Black 0.0% 95.0% 5% Chrysotile Lab Sample ID: 042019627-0107 Client Sample ID: Sample Description: Center Roof - HVAC Ducting - W. Center/Vent Coating (White) Analyzed Non-Asbestos **TEST** Non-Fibrous Asbestos Comment Date Color **Fibrous** PLM 5% Chrysotile 8/17/2020 White/Black 0.0% 95.0% Lab Sample ID: 042019627-0108 51A Client Sample ID: Sample Description: Center Roof - at 3 Pipes - S/Penetration Mastic (White/Black) Non-Asbestos Analyzed TEST Fibrous Non-Fibrous Comment Date Color Asbestos PLM 8/15/2020 White/Black 0.0% 100.0% None Detected 51B Lab Sample ID: 042019627-0109 Client Sample ID: Sample Description: Center Roof - Roof Hatch - Center/Penetration Mastic (White/Black) Analyzed Non-Asbestos Comment **TEST** Date Color **Fibrous** Non-Fibrous Asbestos PLM 8/15/2020 White/Black 0.0% 95.0% 5% Chrysotile Lab Sample ID: 042019627-0110 51C Client Sample ID:

Non-Asbestos

Non-Fibrous

95.0%

Asbestos

5% Chrysotile

Comment

Fibrous

0.0%

Center Roof - Roof Hatch - SW/Penetration Mastic (White/Black)

Color

Black

Analyzed

Date

8/17/2020

Sample Description:

TEST



200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

042019627 32ANDE85

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

Client Sample ID:	52A			ilk Material via El	Lab Sample ID:	042019627-0111
ample Description:	Center Roof - Roof Hatch - SE/Roof C	ore				042010027 0111
ampie Becompacini	Center Noor - Noor Haterr - 3E/Noor C	ore				
	Analyzed	Non	-Asbestos			
TEST	Date Cold	r Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/15/2020 Blac	k 80.0%	20.0%	None Detected		
Client Sample ID:	52B-Tar Felt				Lab Sample ID:	042019627-0112
Sample Description:	Center Roof - Roof Hatch - S/Tar Felt					
	Analyzed	Non	-Asbestos			
TEST	Date Colo		Non-Fibrous	Asbestos	Comment	
PLM	8/15/2020 Blac	k 80.0%	20.0%	None Detected		
Client Sample ID:	52B-Tar				Lab Sample ID:	042019627-0112A
Sample Description:	Center Roof - Roof Hatch - S/Tar					
TEOT	Analyzed		-Asbestos	Asharta	0	
TEST PLM	Date Cold 8/15/2020 Blace		Non-Fibrous	Asbestos None Detected	Comment	
~LIVI	8/15/2020 Blac	k 0.0%	100.0%	None Detected		
Client Sample ID:	52C-Tar Felt				Lab Sample ID:	042019627-0113
Sample Description:	Center Roof - Roof Hatch - Center/Tar	Felt				
TEST	Analyzed Date Colo		-Asbestos Non-Fibrous	Asbestos	Comment	
PLM	8/15/2020 Blac			None Detected	Comment	
			20.070	None Detected	Lab Sample ID:	042040627 0442 4
Client Sample ID:	52C-Tar				Lab Sample ID:	042019627-0113A
Sample Description:	Center Roof - Roof Hatch - Center/Tar					
	Analyzed	Non	-Asbestos			
TEST	Date Colo		Non-Fibrous	Asbestos	Comment	
PLM	8/15/2020 Blac			None Detected		
Client Sample ID:	52D-Tar Felt				Lab Sample ID:	042019627-0114
Sample Description:	Center Roof - Roof Hatch - N/Tar Felt					
	Center 1001 - 1001 Hater - 10/ Fai Felt					
	Analyzed	Non	-Asbestos			
TEST	Date Cold	r Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/15/2020 Blac	k 80.0%	20.0%	None Detected		
Client Sample ID:	52D-Tar				Lab Sample ID:	042019627-0114A
Sample Description:	Center Roof - Roof Hatch - N/Tar				-	
•						
	Analyzed	Non	-Asbestos			
TEST	Date Colo	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/15/2020 Blac	k 0.0%	100.0%	None Detected		
Client Sample ID:	52E-Tar Felt				Lab Sample ID:	042019627-0115
Sample Description:	Center Roof - Roof Hatch - W/Tar Felt					
	Analyzed	Non	-Asbestos			
TEST	Date Cold	r Fibrous	Non-Fibrous	Asbestos	Comment	

8/17/2020

Black

65.0%

35.0%

None Detected



TEST

PLM

EMSL Analytical, Inc.

200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: Customer PO:

Project ID:

042019627 32ANDE85

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

Client Sample ID:	52E-Tar					Lab Sample ID:	042019627-0115A
Sample Description:	Center Roof - Roof Hatch -	W/Tar					
	Analyzed		Non-	Asbestos			
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Black	0.0%	100.0%	None Detected		
Client Sample ID:	52F-Tar Felt					Lab Sample ID:	042019627-0116
Sample Description:	South Roof - S/Tar Felt						
	Analyzed		Non-	Asbestos			
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Black	60.0%	40.0%	None Detected		
Client Sample ID:	52F-Tar					Lab Sample ID:	042019627-0116A
Sample Description:	South Roof - S/Tar						
	Analyzed		Non-	Asbestos			
TEST	Date	Color	Fibrous	Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Black	0.0%	100.0%	None Detected		
Client Sample ID:	52F-Shingle					Lab Sample ID:	042019627-0116B
Sample Description:	South Roof - S/Shingle						
	Analyzed		Non-	Asbestos			
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Gray/Black	20.0%	80.0%	None Detected		
Client Sample ID:	52G-Tar Felt					Lab Sample ID:	042019627-0117
Sample Description:	South Roof - SE/Tar Felt						
	Analyzed		Non-	Asbestos			
TEST	Date	Color		Non-Fibrous	Asbestos	Comment	
PLM	8/17/2020	Black	60.0%	40.0%	None Detected		
Client Sample ID:	52G-Tar					Lab Sample ID:	042019627-0117A
Sample Description:	South Roof - SE/Tar						
	Analyzed		Non-	Asbestos			

Fibrous Non-Fibrous

100.0%

0.0%

Asbestos

None Detected

Comment

Date

8/17/2020

Color

Black



200 Route 130 North Cinnaminson, NJ 08077 Phone/Fax: (800) 220-3675 / (856) 786-5974 http://www.EMSL.com / cinnasblab@EMSL.com EMSL Order ID: Customer ID: 042019627 32ANDE85

Customer PO: Project ID:

Summary Test Report for Asbestos Analysis of Bulk Material via EPA 600/R-93/116

Analyst(s):

Daniel Blake 1000 PLM Pt Ct (3)

Gregory Barry PLM 1000 PC - Gravimetric (2)

1000 PLM Pt Ct (2)

John Witcraft PLM (20)

Kyle DeKarski PLM (67)

Mark Shuts PLM (21)

Michelle Quach PLM (50)

Rachel Irwin PLM (46)

Reviewed and approved by:

Samantha Rundstrom, Laboratory Manager or Other Approved Signatory

Samantha Runghtono

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported above and may not be reproduced, except in full, without written approval by EMSL. This test report must not be used to claim product endorsement by NVLAP or any agency of the U.S. Government. EMSL bears no responsibility for sample collection activities or analytical method limitations. The laboratory is not responsible for the accuracy of results when requested to physically separate and analyze layered samples. PLM alone is not consistently reliable in detecting asbestos in floor coverings and similar NOBs

Samples analyzed by EMSL Analytical, Inc. Cinnaminson, NJ NVLAP Lab Code 101048-0, AIHA-LAP, LLC-IHLAP Lab 100194, NYS ELAP 10872, NJ DEP 03036, LA #04127

(Initial report from: 08/17/202017:58:45

OrderID: 042019627

efi global Laboratory

Chain of Custody

Turn Around Time - (Circle) *Please select based on laboratory being used

24hr 6hr 3hr


48hr Standard

Start Time	EFI Global Project No.:	Project Name:	Sampling By:	Number of Samples:		Date(s) Collected:	Page No.:		Total Pages
Sample Location & Comments End Flow Rate Stop Time Area/SQFT Analysis Type: Serial No.: Serial No.: Serial No.: Serial No.: Serial No.: Analysis Type: Serial No.: Serial No.: Analysis Type: Serial No.: Analysis Type: Serial No.: Serial No	18020.540		Harberto F	2, 11-	3	121	/	Of	11
Analysis Type: P.L.M. Serial No.: P.L.M. Serial No.		e Location & Comments	Star	rt Flow Rate	Start Time Stop Time	Total Volume Area/SQFT	Type Sample S	of Analy Serial No	sis ımber
Analysis Type: Analysis Type: Analysis Type: Serial No.: Serial No.: Serial No.: Serial No.: Serial No.: Serial No.: Analysis Type: Serial No.: Serial	1	Seast					Analysis Type: Serial No.:	79	M
Analysis Type: Serial No: Serial		28					Analysis Type: Serial No.:	30	X
Analysis Type: Serial No.: Analysis Type: Serial No.:		Attached					Analysis Type: Serial No.:		
Analysis Type: Serial No.:							Analysis Type: Serial No.:		20
Analysis Type: Serial No.:							Analysis Type: Serial No.:		CINHA 20 AU
Analysis Type: Serial No.:							Analysis Type: Serial No.:		
Analysis Type: Serial No.: Received By (Print & Sign) (Date & Time) Received By (Print & Sign) (Date & Time) Received By (Print & Sign) (Date & Time)							Analysis Type: Serial No.:		
Serial No Secrived By (Print & Sign) (Date & Time) Received By (Print & Sign) (Date & Time) Received By (Print & Sign) (Date & Time)			-				Analysis Type: Serial No.:		÷ 25
Received By (Print & Sign) (Date & Time) (15.12) Received By (Print & Sign) (Date & Time)							Analysis Type: Serial No.:		
	Relinquished By (Print & Sign)(3	02/048	eceived By (Print &	Sign) (Date & Tin				
	Relinquished By (Print & Sign)	Date & Time)	/ / Re	eceived By (Print &	Sign) (Date & Tin	ne))	

Special Instructions:	Stop Positive:		E-mail to Additional Party:
	Yes	No	
		100	

5261 West Imperial Hwy Los Angeles, CA 90045, Ph (310) 854-6300, Fax (310) 854-0199





ASBESTOS FIELD BULK SAMPLE TABLE

PROJECT NUMBER:

DATE:

PROJECT LOCATION:

COMPLETED BY: H.R.

SAMPLE NUMBER	SAMPLE DESCRIPTION	SAMPLE LOCATION	APPROX. SQUARE FOOTAGE	CONDITION	HOMOGENOUS APPLICATION
MM	Drywall System	2 rd Floor-Room200-6		F / NF G D SD	S / TSI / MISC
1 8		Room227 - ~		F / NF G D SD	S / TSI / MISC
J		Boomzys -NE		F / NF G D SD	S / TSI / MISC
Ω		1 ROOM232-5W		F / NF G D SD	S / TSI / MISC
D		1st Floor - Utility Run 6-5E		F / NF G D SD	S / TSI / MISC
		- Room 106 - SE		F / NF G D SD	S / TSI / MISC
. 5		35- 541		F / NF G D SD	S / TSI / MISC
#		WN 851		F / NF G D SD	S / TSI / MISC
7	\rightarrow	V 159 NE		F / NF G D SD	S / TSI / MISC
ISA	AcousticTexture	15+ Floor - Room 145		F / NF G D SD	CSIN / AUC
. 8		> 1		F / NF G D SD	A / ISO / S
) >	>	~-2H1mood-		F / NF G D SD	S TISI/GANSC
					N.J.

efi global

ASBESTOS FIELD BULK SAMPLE TABLE

PROJECT NUMBER:

PROJECT NAME:

PROJECT LOCATION:

COMPLETED BY: H.R.

DATE:

ENOUS	TSI / MISC	TSI / MISC	TSI / MISC	TSI / MISC	TSI / MISC	TSI / MISC	TSI / MISC	TSI / MISC	TSI/ MISC	TSI / MISC	CON AUC	A CONTRACTOR	SON, N.
HOMOGENOUS APPLICATION	S / TSI	S / TSI	S / TSI	IST / S	S / TSI	S / TSI	S / TSI	S / TSI	S / TSI	ISI / S	/ S	8 / 8	AM II: 2
CONDITION	F / NF G D SD	F / NF G D SD	F / NF G D SD	F / NF G D SD	F / NF G D SD	F / NF G D SD	F / NF G D SD	F / NF G D SD	F / NE G D SĎ	F / NF G D SD	F / NF G D SD	F / NF G D SD	
APPROX. SQUARE FOOTAGE													
SAMPLE LOCATION	Utility Room 6 -SE	Utility Room 7 - E	127 loor-Room 106-5	- Room 110-N	V-RoomISA	- Room 158-NW	M-901 - 1	2 202 - 202 - Z	5-922 1 - 1	12tFloor-Room 149-5	5 7	changing pm 1 - 5	r
SAMPLE DESCRIPTION	Adhesinc (Tan)+ Covelase	t (Brown)	+ (Grey)	*	$\begin{array}{c} \rightarrow \\ \rightarrow \\ \rightarrow \\ \rightarrow \end{array}$	Ceiling Tile (12×12)	<i>></i>	Ceiling Tile (24×18)	\	Sink undercoating	\rightarrow	Carpet Adhesive (Tan)	
SAMPLE NUMBER	16 A	30	J			1 A	<i>∞</i>	18A	> B	46	48	23.4	

(@) efi global

ASBESTOS FIELD BULK SAMPLE TABLE

PROJECT NUMBER:

PROJECT LOCATION:

PROJECT NAME:


DATE:

COMPLETED BY: H.R.

SAMPLE NUMBER	SAMPLE DESCRIPTION	SAMPLE LOCATION	APPROX. SQUARE FOOTAGE	CONDITION	HOMOGENOUS APPLICATION
20A	Sink Coultines (White)	Restroom 13 - N		F / NF G D SD	S / TSI / MISC
₹ A	<i>→</i>	~-2 1		F / NF G D SD	S / TSI/ MISC
214	Stone Grow (Gray)	Cobby - reddon		F / NF G D SD	S / TSI / MISC
4 B	→	Exterior - w		F / NF G D SD	S / TSI / MISC
22 A	Stucco	3		F / NF G D SD	S / TSI / MISC
- 13		- NE		F / NF G D SD	S / TSI / MISC
O	i	1		F / NF G D SD	S / TSI / MISC
4.		`		F / NF G D SD	S / TSI / MISC
m		3		F / NF G D SD	S / TSI / MISC
1		3		F / NF G D SD	S / SAUC
5	7	3		F / NF G D SD	S CTSI/ARS
23 8	Corpet Addressive (Tam)	changing Rm I-		F / NF G D SD	Elosocist M.
					N.J.

PAGE 4 OF

32019627



ASBESTOS FIELD BULK SAMPLE TABLE

PROJECT NUMBER:

PROJECT LOCATION:

PROJECT NAME:

DATE:

COMPLETED BY: H.R.

											RECE	IVE	
HOMOGENOUS APPLICATION	S / TSI / MISC	S / TSI / MISC	S / TSI / MISC	S / TSI / MISC	S / TSI / MISC	S / TSI / MISC	S / TSI / MISC	S / TSI / MISC	S / TSK MISC	ABIG 1 S	S / FET MISC	S / INI S	l.J. 25
CONDITION	F / NF G D SD	F / NF G D SD	F / NF G D SD	F / NF G D SD	F / NF G D SD	F / NF G D SD	F / NF G D SD	F / NF G D SD	F / NF G D SD	F / NF G D SD	F / NF G D SD	F / NF G D SD	
APPROX. SQUARE FOOTAGE		8.											
SAMPLE LOCATION	MV - 921 WOOZ	7	Restroom 3-W	AN T	Utility Room 7 - E	\ -(t)	Room 149 - NW	Room 106 - Sw	MN - 851	159 - NE	2 2 2 500 1 50 E	VHall - Center	
SAMPLE DESCRIPTION	VSF (white speckled)	\rightarrow	VSF (Green Speckled)	\rightarrow	USF (Gray Pebble Pattern)		→	VFT(white 12x12)+		\rightarrow	VFT (Cream 12×12) +	→	
SAMPLE NUMBER	A 12	₹ 8	25 A	> x	764	> >	>	777	SC .	> >	28A	~ ~	

PAGE SOF

(®) efi global

ASBESTOS FIELD BULK SAMPLE TABLE

PROJECT NUMBER:

PROJECT LOCATION:

PROJECT NAME:

DATE: COMI

COMPLETED BY: H.R.

SAMPLE NUMBER	SAMPLE DESCRIPTION	SAMPLE LOCATION	APPROX. SQUARE FOOTAGE	CONDITION	HOMOGENOUS APPLICATION
294	VFT (Blue Marbled 12x12)	Room 155 - 5E		F / NF G D SD	S / TSI / MISC
20	\rightarrow	Room 158 - NW		F / NF G D SD	S / TSI / MISC
30A	VFT (Gray with white)	Utility Room ? - ~		F / NF G D SD	S / TSI / MISC
4	150	\ \ \		F / NF G D SD	S / TSI / MISC
31A	VFT (Brown Marbled 12x12)	Room 137 - NW		F / NF G D SD	S / TSI / MISC
~ ~		}		F / NF G D SD	S / TSI / MISC
¥25	VFT (Careen Marbled 12x12)	151 Floor - Lobby - 2		F / NF G D SD	S / Terr MISC
8		2nd Floor - Stafflounguesu		F / NF G D SD	AZG MAZG
) }	<i>→</i>	5- >		F / NF G D SD	
33A	VET (Grey 12×12)	Staff loungue - 5		F / NF G D SD	S / #BI / MISC
00	+	windowed Hall - N		F / NF G D SD	25 / S
\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	7 + >	Vinfront of Roomsy8-u	}	F / NF G D SD	S / TSI / MISC

PAGE 6 OF

L29610212

efi global

ASBESTOS FIELD BULK SAMPLE TABLE

PROJECT NAME: PROJECT NUMBER:

DATE:

								TEEL	VED				
	HOMOGENOUS APPLICATION	MISC	MISC	MISC	MISC	MISC	MISC	ESM!		MISC	MISC	MISC	MISC
	GEN	SI/ N	TSI / MISC	TSI / MISC	TSI / MISC					-	TSI / MISC	SI/ N	TSI / MISC
1	HOMOGENOUS	S / TSI / MISC	_	S / T	_		20 ĀU		AP I	: 25	_	S / TSI / MISC	S / T
	H	S	S	S	S	S	S	S	S	S	S	S	S.
	NOI	NF SD	IF SD	NF SD	IF SD	VF SD	NF SD	IF SD	NF SD	IF SD	VF SD	NF SD	NF SD
	CONDITION	F / NF G D SD	F / NF G D SD	_ 0	F / NF G D SD	F 7 NF G D SE	_ O	F / NF G D SD	_ 0	F / NF 3 D SD	_ Q	F / NF G D SI	F / NF G D SI
	00	D O	D	G F	G H	O G	G G	D	G F	G E	G F	- 0	0
COMPLETED BY: H.R.	XE GE												
. X	APPROX. SQUARE FOOTAGE												
ED E	SC FO												
ET		}		5			NE	2					
MPI	-	\ <u>\</u>		<	Ш	3	~						
00	SAMPLE LOCATION	,		١	,	1					2	N	5
	OCA			Ó			4	13	5	0	1		
	LEL	+	19	Room 130			Restroom		Restroom		Restrooms		\rightarrow
	AMP	hago	Lobby	0		7	1000	\rightarrow	1	\Rightarrow	+5		
	S	107	1	Ro			265)		200		N		
							1						
:: 				5	7		_				_		
DATE:		(coating			FloorTile (Ix I white)				(dxy Blue)		
	LION	3					Jhi.		Tak		9		
	SAMPLE DESCRIPTION	Green)	exten			-X				X		
	DESC	1		X			5		FloorTile (1x		ゴ		>
	PLE	thought of	-	To the		\rightarrow	7-	->	2 -	\rightarrow	2		
	SAM	JA		500			1				WallTile		
		77		0			00		200		7		
ä		>-	7	1			-لمد		T		3		
PROJECT LOCATION:	N N												
OCA	MBE	X	22	T	20	0	4	20	V	20	\triangleleft	20	\cup
TL	ENO	344	1	N		\rightarrow	36A	>	57	>	38 A		\rightarrow
JEC	SAMPLE NUMBER	(1)		h			(~1		1		,		
PRO	SA												
										L			

efi global

ASBESTOS FIELD BULK SAMPLE TABLE

PROJECT NUMBER: PROJE

PROJECT NAME:

COMPLETED BY: H.R.	
DATE:	
JECT LOCATION:	

🍘 efi global

ASBESTOS FIELD BULK SAMPLE TABLE


PROJECT NUMBER:

PROJECT LOCATION: 100 ft Date:

COMPLETED BY: H.R.

SAMPLE NUMBER	SAMPLE DESCRIPTION	SAMPLE LOCATION	APPROX. SQUARE FOOTAGE	CONDITION	HOMOGENOUS APPLICATION
HAH	Roof Core	North Rolled on Roof		F / NF G D SD	S / TSI/ MISC
8		East	a.	F / NF G D SD	S / TSI / MISC
U		- North		F / NF G D SD	S / TSI / MISC
0		- N. Center		F / NF G D SD	S / TSI / MISC
777		- S. Center		F / NF G D SD	S / TSI / MISC
1		N.East		F / NF G D SD	S / TSI / MISC
5	\rightarrow	1.W.S.		F / NF G D SD	S / TSL/ MISC
USA	Roofing Mastic (Black)	NORTH ROOM		F / NF G D SD	S / AUG
8		2		F / NF G D SD	S / GIST MISCO
0	\rightarrow	}		F / NF G D SD	VEORY ISING S
46A	Roofing Mastic (Black)			F / NF G D SD	S TSI FMISC
1 8	→ · · ·			F / NF G D SD	S / TSI / MISC

296/02/10




ASBESTOS FIELD BULK SAMPLE TABLE

COMPLETED BY: H.R. PROJECT NAME: DATE: PROJECT LOCATION: PROJECT NUMBER:

							RECE	WED				
HOMOGENOUS APPLICATION	S / TSI / MISC	S / TSI / MISC	TSI / MISC	S / TSI / MISC	S / TSI / MISC	I/ MISC	-	Sign.	I/ MISC	/ TSI / MISC	S / TSI / MISC	S / TSI / MISC
HOMOC	S / TS	S / TS	S / TS	S / TS	ST / S	DZOFAL S	6 ¹ 3	AMI S	1: 25	S / TS	S / TS	S / TS
CONDITION	F / NF G D SD	F / NF G D SD	F / NF G D SD	F / NF G D SD	F / NF G D SD	F / NF G D SD	F / NF G D SD	F / NF G D SD	F / NF G D SD			
APPROX. SQUARE FOOTAGE		2										
SAMPLE LOCATION	north Roof	5	~	\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	S)	2-7	Center Roof - Sul		1 - center	- S.Center	Center	Jenter - W. Contex
SAMPLE DESCRIPTION	HVAC Mastic		\rightarrow	(stime browners)		→	HVAC COOLING		\rightarrow	Ventcoating		7
SAMPLE NUMBER	477	2	→ →	48A	2	>	497	20	>	50A	2	>

PAGE 10 OF VI



ASBESTOS FIELD BULK SAMPLE TABLE

PROJECT NUMBER:

PROJECT LOCATION:

PROJECT NAME:

DATE:

COMPLETED BY: H.R.

SAMPLE NUMBER	SAMPLE DESCRIPTION	SAMPLE LOCATION	APPROX. SQUARE FOOTAGE	CONDITION	HOMOGENOUS APPLICATION
V 15	Penetration Mastic	Center Roof -		F / NF G D SD	S / TSI / MISC
1 8		4		F / NF G D SD	S / TSI / MISC
$\overset{\bigcirc}{\rightarrow}$	\rightarrow	. 5		F / NF G D SD	S / TSI / MISC
¥25	Roof Core	S E		F / NF G D SD	S / TSI / MISC
0		S		F / NF G D SD	S / TSI / MISC
O .		Cente		F / NF G D SD	S / TSI / MISC
4	Parapet	>		F / NF G D SD	S / TSI / MISC
M	- Paracet	}		F / NF G D SD	S / TSI / S
H	Parapet	south Roof 5		F / NF G D SD	S / TSI
5	\rightarrow	>		F / NF G D SD	S / TSI MISC
				F / NF G D SD	S / TST MISE
				F / NF G D SD	S / TSI / MISC

APPENDIX III
Lead XRF Results



Tan VSF Purple Drywall
Door Metal
Metal
Drywall
Metal
Drywall
VFT
VFT
Brown Wood
Brown Metal
White Drywall
Green Metal
White Porcelain
White Drywall
Tan Ceramic
Peach Ceramic
urquoies Ceramic
White Wood
Drywall
Green Metal
White Ceramic
Blue Ceramic
Red Ceramic
CALIBRATION
CALIBRATION
CALIBRATION
CALIBRATION
Color Substrate



Intact	T-Bar	Metal	White	South	Lobby	NEG	0.3	0	65	8/6/2020
Intact	Ceiling	Ceiling Tile	White	South	Lobby	NEG	0.2	-0.1	64	8/6/2020
Intact	Elevator Door	Metal	White	South	Lobby	NEG	0.3	-0.1	63	8/6/2020
Intact	Wall	Drywall	White	West	Lobby	NEG	0.3	-0.1	62	8/6/2020
Intact	Floor	VFT	Green	East	Lobby	NEG	0.3	0	61	8/6/2020
Intact	Floor	VFT	Light-Brown	East	Lobby	NEG	0.3	0.1	60	8/6/2020
Intact	Baseboard	Wood	Green	West	Lobby	NEG	0.2	-0.2	59	8/6/2020
Intact	Wall	Drywall	White	North	Lobby	NEG	0.3	0.1	58	8/6/2020
Intact	Pipe Electrical	Metal	Tan	East	Utility #6	NEG	0.3	0.2	57	8/6/2020
Intact	Panel	Metal	Blue	West	Utility #6	NEG	0.3	0	56	8/6/2020
Intact	Conduit	Metal	Blue	West	Utility #6	NEG	0.3	0	55	8/6/2020
Intact	Floor Tile	Ceramic	Red	West	Utility #6	NEG	0.3	0.2	54	8/6/2020
Intact	Wall Tile	Ceramic	Grey	West	Utility #6	NEG	0.3	0.2	53	8/6/2020
Intact	Wall Tile	Ceramic	Tan	South	Utility #6	NEG	0.2	0.4	52	8/6/2020
Intact	Wall	Drywall	Grey	South	Utility #6	NEG	0.3	0.1	51	8/6/2020
Intact	Drain	Metal	Tan	West	160	NEG	0.2	0.4	50	8/6/2020
Intact	Door	Metal	Blue	West	160	NEG	0.3	0.1	49	8/6/2020
Intact	Door Frame	Metal	Brown	West	160	NEG	0.3	-0.1	48	8/6/2020
Intact	Drain	Metal	White	West	160	POS	0.2	1	47	8/6/2020
Intact	Baseboard	Ceramic	Red	West	160	NEG	0.3	-0.4	46	8/6/2020
Intact	Floor	Ceramic	Red	West	160	NEG	0.3	-0.1	45	8/6/2020
Intact	Panel Wall	Wood	White	West	160	NEG	0.3	0	44	8/6/2020
Intact	Door	Wood	Tan	West	154	NEG	0.3	-0.1	43	8/6/2020
Intact	Door Frame	Metal	Tan	West	154	NEG	0.3	-0.2	42	8/6/2020
Intact	Cabinet	Wood	Tan	West	154	NEG	0.3	0	41	8/6/2020
Intact	Baseboard	Wood	Brown	West	154	NEG	0.3	0	40	8/6/2020
Intact	Wall	Drywall	Tan	South	154	NEG	0.3	0	39	8/6/2020
Intact	Floor	VFT	White	East	456	NEG	0.3	0	38	8/6/2020
Intact	Floor	VFT	Blue	East	456	NEG	0.3	0.2	37	8/6/2020
Intact	Wall	Drywall	Yellow	South	456	NEG	0.3	0.1	36	8/6/2020
Intact	Ceiling Tile	Cardboard	White	North	155	NEG	0.2	0	35	8/6/2020
Intact	Door	Wood	Green	North	155	NEG	0.3	-0.2	34	8/6/2020
Intact	Window Frame	Metal	Green	North	155	NEG	0.3	0.1	33	8/6/2020
Condition	Component	Substrate	Color	Direction	Room	Result	+/-	Pb (mg/cm2)	Sample #	Date



C
White Drywall
White VFT
Blue VFT
White Drywall
Green Wood
Green Wood
White Wood
Grey Drywall
White VSF
Tan Wood
White Metal
White Wood
Green Drywall
Tan Drywall
White Concrete
Brown Wood
Brown Wood
Tan Cork
Brown Wood
Tan Drywall
Brown Wood
Brown Metal
Brown Wood
White VFT
Tan Drywall
Brown Wood
Brown Wood
Grey Sheet Ceramic
Brown Wood
Tan Drywall
Color Substrate



Intact	Tile Floor	Ceramic	Light-Blue	West	Changing Room	NEG	0.3	0	124	8/6/2020
Intact	Tile Floor	Ceramic	Grey	West	Changing Room	NEG	0.3	-0.1	123	8/6/2020
Intact	Wall Tile	Ceramic	Blue	West	Changing Room	POS	0.3	22.8	122	8/6/2020
Intact	Urinal	Porcelain	White	East	Restrom #3	NEG	0.3	0	121	8/6/2020
Intact	Ceiling	Drywall	White	East	Restrom #3	NEG	0.3	0	120	8/6/2020
Intact	Wall Tile	Ceramic	Pink	East	Restroom #3	POS	0.3	25.9	119	8/6/2020
Intact	Wall	Drywall	Green	North	Room 112	NEG	0.3	0.1	118	8/6/2020
Intact	Sink	Porcelain	White	North	Restrom #3	NEG	0.3	-0.6	117	8/6/2020
Intact	Floor	Sheet Vinal	Green	North	Restrom #3	NEG	0.3	0	116	8/6/2020
Intact	Wall	Drywall	White	North	Restrom #3	NEG	0.3	0.1	115	8/6/2020
Intact	Wall Tile	Ceramic	White	North	Restrom #3	POS	0.3	21.1	114	8/6/2020
Intact	Cabinets	Wood	Green	West	Room 110	NEG	0.3	0	113	8/6/2020
Intact	Electric Post	Conduit	Purple	West	Room 110	NEG	0.3	0.2	112	8/6/2020
Intact	Floor	VFT	White	West	Room 110	NEG	0.3	0.1	111	8/6/2020
Intact	Floor	VFT	Blue	West	Room 110	NEG	0.3	0.3	110	8/6/2020
Intact	Post	Metal	Cream	South	Room 110	NEG	0.3	-0.3	109	8/6/2020
Intact	Wall	Drywall	Green	North	Room 110	NEG	0.3	0.1	108	8/6/2020
Intact	Wall	Drywall	Purple	East	Room 110	NEG	0.3	0.2	107	8/6/2020
Intact	Ceiling	Drywall	White	West	Restroom #5	NEG	0.3	0	106	8/6/2020
Intact	Wall	Ceramic	Blue	West	Restroom #5	POS	0.3	21.7	105	8/6/2020
Intact	Door Frame	Wood	Green	South	Restroom #6	NEG	0.3	0	104	8/6/2020
Intact	Door	Wood	Green	South	Restroom #6	NEG	0.3	0	103	8/6/2020
Intact	Sink	Porcelain	White	South	Restroom #6	NEG	0.3	-0.4	102	8/6/2020
Intact	Wall Tile	Ceramic	Pink	West	Restroom #6	POS	0.3	21.8	101	8/6/2020
Intact	Toilet	Porcelain	White	South	Restroom #14	NEG	0.3	0	100	8/6/2020
Intact	Ceiling	Drywall	White	South	Restroom #14	NEG	0.3	0.1	99	8/6/2020
Intact	Floor	Ceramic	Grey	South	Restroom #14	NEG	0.3	0.1	98	8/6/2020
Condition	Component	Substrate	Color	Direction	Room	Result	+/-	Pb (mg/cm2)	Sample #	Date



Intact	Wall Tile	Ceramic	Tan	West	Restroom #1	POS	0.3	12.7	156	8/6/2020
Intact	White	Drywall	White	West	Restroom #1	NEG	0.3	0	155	8/6/2020
Intact	Door Frame	Metal	Yellow	West	Utility #1	NEG	0.3	0.1	154	8/6/2020
Intact	Door	Wood	Yellow	West	Utility #1	NEG	0.3	-0.1	153	8/6/2020
Intact	Door Frame	Metal	Yellow	South	Utility #1	NEG	0.3	0.1	152	8/6/2020
Intact	Wall	Drywall	White	North	Utility #1	NEG	0.3	0.1	151	8/6/2020
Intact	Ceiling	Ceiling Tile	White	North	105 B	NEG	0.2	0	150	8/6/2020
Intact	T-Bar	Metal	White	North	105 B	NEG	0.3	0	149	8/6/2020
Intact	Sink	Porcelain	White	North	105 B	POS	0	30	148	8/6/2020
Intact	Door Frame	Metal	Yellow	East	105 B	NEG	0.3	0.2	147	8/6/2020
Intact	Door	Wood	Yellow	East	105 B	NEG	0.3	-0.1	146	8/6/2020
Intact	Floor	Floor	Green	North	105 B	NEG	0.3	0	145	8/6/2020
Intact	Wall	Drywall	White	North	105 B	NEG	0.3	0	144	8/6/2020
Intact	Window Frame	Metal	Grey	West	105 A	NEG	0.3	-0.1	143	8/6/2020
Intact	Frame	Metal	Yellow	South	105 A	NEG	0.3	0	142	8/6/2020
Intact	Cabinet	Wood	Green	South	105 A	NEG	0.2	0.1	141	8/6/2020
Intact	Wall	Drywall	Green	North	105 A	NEG	0.3	0.1	140	8/6/2020
Intact	Molding	Wood	Blue	North	105 A	NEG	0.3	-0.4	139	8/6/2020
Intact	Cabinet	Wood	Yellow	East	105 A	NEG	0.3	0.1	138	8/6/2020
Intact	Wall	Drywall	White	East	105 A	NEG	0.3	0.1	137	8/6/2020
Intact	Wall	Drywall	Blue	East	105 A	NEG	0.3	0	136	8/6/2020
Intact	Wall	Fiser Board	Blue	North	105 A	NEG	0.2	0.1	135	8/6/2020
Intact	Floor	VFT	Grey	East	Utility #2	NEG	0.1	0.7	134	8/6/2020
Intact	Ceiling	Drywall	Green	East	Utility #2	NEG	0.3	0	133	8/6/2020
Intact	Wall	Drywall	Tan	East	Utility #2	NEG	0.3	0.1	132	8/6/2020
Intact	Shelf	Wood	Blue	West	149	NEG	0.3	0	131	8/6/2020
Intact	Floor	Laminate	Tan	East	149	NEG	0.3	0.1	130	8/6/2020
Intact	Ceiling	Drywall	Tan	West	149	NEG	0.3	0.1	129	8/6/2020
Intact	Wall	Drywall	Tan	North	149	NEG	0.3	0.1	128	8/6/2020
Intact	Wall	Drywall	Blue	West	149	NEG	0.3	0	127	8/6/2020
Intact	Post	Drywall	White	West	149	NEG	0.3	0.2	126	8/6/2020
Intact	Tile Floor	Ceramic	Blue	West	Changing Room	NEG	0.3	0	125	8/6/2020
Condition	Component	Substrate	Color	Direction	Room	Result	+/-	Pb (mg/cm2)	Sample #	Date
									(



	\\ <u>\</u>	7	Grev	5011 + b	125	NEC NEC	,	0.1	181	8/6/2020
Intact	Door Frame	Metal	Blue	West	Restrom #9	NEG	0.3	-0.1	180	8/6/2020
Intact	Toilet	Porcelain	White	East	Restrom #9	NEG	0.3	-0.4	179	8/6/2020
Intact	Stals	Metal	Tan	North	Restrom #9	NEG	0.3	0.1	178	8/6/2020
Intact	Tileboard	Ceramic	Black	East	Restrom #9	NEG	0.3	-0.1	177	8/6/2020
Intact	Tile	Ceramic	Brown	East	Restrom #9	NEG	0.3	0	176	8/6/2020
Intact	Trim Tile	Ceramic	White	East	Restrom #9	NEG	0.3	-0.1	175	8/6/2020
Intact	Floor Tile	Ceramic	Tan	East	Restrom #9	NEG	0.3	0.1	174	8/6/2020
Intact	Wall Tile	Ceramic	White	East	Restrom #9	NEG	0.1	0.5	173	8/6/2020
Intact	Wall Tile	Ceramic	Black	East	Restrom #9	NEG	0.3	0.2	172	8/6/2020
Intact	Wall	Concrete	Green	East	Restrom #9	NEG	0.3	-0.2	171	8/6/2020
Intact	Wall	Concrete	Green	North	Restroom #10	NEG	0.3	-0.4	170	8/6/2020
Intact	Sink	Porcelain	White	East	Restroom #10	NEG	0.2	0.3	169	8/6/2020
Intact	Tile Baseboard	Ceramic	White	East	Restroom #10	NEG	0.3	0	168	8/6/2020
Intact	Floor Tile	Ceramic	Tan	South	Restroom #10	NEG	0.3	0	167	8/6/2020
Intact	Floor Tile	Ceramic	Tan	South	Restroom #10	NEG	0.3	0.2	166	8/6/2020
Intact	Wall Tile	Ceramic	White	North	Restroom #10	NEG	0.3	-0.2	165	8/6/2020
Intact	Wall Tile	Ceramic	Brown	East	Restroom #10	NEG	0.3	0.3	164	8/6/2020
Intact	Wall	Drywall	Green	East	Restroom #10	NEG	0.3	0.1	163	8/6/2020
Intact	Toilet	porcelain	White	West	Restroom #2	NEG	0.3	-0.2	162	8/6/2020
Intact	Toilet	Porcelain	White	South	Restroom #2	NEG	0.3	-0.1	161	8/6/2020
Intact	Wall	Ceramic	Tan	South	Restroom #2	POS	0.3	22.3	160	8/6/2020
Intact	Wall	Drywall	White	West	Restroom #2	NEG	0.3	0	159	8/6/2020
Intact	Celinng	Drywall	White	West	Restroom #1	NEG	0.3	0	158	8/6/2020
Intact	Sink	Porcelain	White	West	Restroom #1	NEG	0.3	-0.3	157	8/6/2020
Condition	Component	Substrate	Color	Direction	Room	Result	+/-	Pb (mg/cm2)	Sample #	Date



		_	_	_	г	г —	г —	г	т —	т —	т —	г	_		1	T	г —	_	_	_	_	_	_	_	_		_	_	_	$\overline{}$	_	$\overline{}$		4
8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	8/6/2020	Date	
214	213	212	211	210	209	208	207	206	205	204	203	202	201	200	199	198	197	196	195	194	193	192	191	190	189	188	187	186	185	184	183	182	Sample #	
-0.1	56	0	0	-0.1	0	0	-0.1	0	0.2	0	-0.1	-0.4	-0.4	-0.3	0.2	-0.6	-0.1	-0.2	0.1	0.1	0	0.2	0	-0.2	-0.1	9.0	0.3	0	0.2	-0.1	-0.3	0.1	Pb (mg/cm2)	
0.3	0	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.2	0.3	0.3	0.3	0.3	0.3	0.3	0.2	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.1	0.3	0.3	0.3	0.3	0.2	0.3	+/-	
NEG	POS	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	Result	
Room 142	Room 142	Room 142	Room 142	Room 142	Room 141	Room 141	Room 141	Room 141	Room 141	Restroom #7	Restroom #7	Restroom #7	Restroom #7	Restroom #8	Restroom #8	Restroom #8	145	145	145	145	145	Restroom 15	135	135	135	135	Room							
East	East	East	East	West	South	West	West	West	West	North	East	South	South	South	South	South	North	North	North	East	East	East	East	East	East	East	East	East	North	West	East	North	Direction	
Green	White	White	Blue	Green	White	Green	Green	Tan	White	White	Tan	White	Tan	White	Green	Tan	Green	Green	Blue	Green	Blue	Grey	White	Dark Grey	Grey	White	White	Grey	Grey	Grey	Blue	Blue	Color	
Wood	Porcelain	Ceramic	Drywall	Concrete	Metal	Wood	Metal	VSF	Drywall	Drywall	Wood	Porcelain	Ceramic	Porcelain	Metal	Ceramic	Metal	Wood	Ероху	Drywall	Drywall	Ceramic	Ceramic	Ceramic	Ceramic	Porcelain	FRP	Drywall	plaster	Plaster	Wood	Wood	Substrate	
Baseboard	Sink	Wall-Tile	Wall	Wall	Window Frame	Door	Door-Frame	Floor	Wall	Wall	Cabinet	Sink	Wall Tile	Sink	Stall	Tile Wall	Door Frame	Baseboard	Floor	Post	Wall	Baseboard	Floor	Floor	Wall Tile	Sink	Wall	Wall	Ceiling	wall	Vent	Door	Component	
Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Condition	



Intact	Baseboard	Wood	White	North	Bathroom 1	NEG	0.3	0.1	246	8/7/2020
Intact	Celing	Drywall	White	North	Bathroom 1	NEG	0.3	0.1	245	8/7/2020
Intact	Toilet	Porcelain	White	North	Bathroom 1	NEG	0.3	-0.2	244	8/7/2020
Intact	Sink	Porcelain	White	North	Bathroom 1	NEG	0.3	0.1	243	8/7/2020
Intact	Wall	Drywall	Grey	North	Bathroom 1	NEG	0.2	0.1	242	8/7/2020
Intact	Wall	Wood	Varnish	West	Bathroom 1	NEG	0.2	0	241	8/7/2020
Intact	Wal	Drywall	Green	North	Bathroom 1	NEG	0.3	0.1	240	8/7/2020
Intact	Wall	Drywall	White	West	Bathroom 1	NEG	0.2	0.2	239	8/7/2020
Intact	Ceiling	Wood	Blue	West	Bedroom 1	NEG	0.3	0.1	238	8/7/2020
Intact	Crown Molding	Wood	White	West	Bedroom 1	NEG	0.3	0	237	8/7/2020
Intact	Door	Wood	Blue	West	Bedroom 1	NEG	0.2	0	236	8/7/2020
Intact	Door Frame	Wood	Blue	West	Bedroom 1	NEG	0.2	0.3	235	8/7/2020
Intact	Baseboard	Wood	Blue	West	Bedroom 1	NEG	0.3	0.2	234	8/7/2020
Intact	Window Seal	Wood	Blue	West	Bedroom 1	NEG	0.2	0	233	8/7/2020
Intact	Window Frame	Wood	Blue	West	Bedroom 1	NEG	0.2	0.3	232	8/7/2020
Intact	Wall	Wood	Blue	West	Bedroom 1	NEG	0.3	0	231	8/7/2020
Intact	Wall	Wood	Blue	North	Bedroom 1	NEG	0.3	0.1	230	8/7/2020
Intact	Wall	Wood	Blue	East	Bedroom 1	NEG	0.2	0.2	229	8/7/2020
Intact	Wall	Wood	Blue	South	Bedroom 1	NEG	0.2	0.2	228	8/7/2020
			מא	585 South Tustin - House	585 South					
1	!	1	CALIBRATION	1	-	NEG	0.2	-0.3	227	8/7/2020
1	1	1	CALIBRATION	1	1	POS	0.3	1.2	226	8/7/2020
1	1	1	CALIBRATION	1	1	POS	0.3	1.2	225	8/7/2020
1	-	-	CALIBRATION		-	POS	0.3	1.2	224	8/7/2020
			CALIBRATION			NEG	0.3	0	223	8/6/2020
			CALIBRATION			POS	0.3	1.2	222	8/6/2020
			CALIBRATION			POS	0.3	1.1	221	8/6/2020
			CALIBRATION			POS	0.3	1.1	220	8/6/2020
Intact	Fence	Metal	Black	North	Pool 130	NEG	0.3	0	219	8/6/2020
Intact	Tile Wall	Ceramic	Blue	North	Pool 130	NEG	0.3	0.1	218	8/6/2020
Intact	Tile	Ceramic	Blue	North	Pool 130	NEG	0.3	0	217	8/6/2020
Intact	Tile	Ceramic	Light-Blue	North	Pool 130	POS	0.3	18.9	216	8/6/2020
Intact	Post	Metal	Green	East	Room 142	NEG	0.3	0.1	215	8/6/2020
Condition	Component	Substrate	Color	Direction	Room	Result	-/+	Pb (mg/cm2)	Sample #	Date
									(



Project No.: 045.04081

8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 8/7/2020 Sample # Pb (mg/cm2) 247 276 270 267 257 256 248 249 274 273 272 271 269 268 266 265 264 263 262 261 260 259 258 255 254 253 252 251 250 0.2 -0.8 -0.1 0.1 0.1 0.7 1.9 0 0 0 0 0 0 0 0.3 +/-0.3 0.2 0.2 0.1 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.1 0.3 0.3 0.3 0.2 0.2 0.2 0.3 0.3 0.2 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.3 0.2 Result NEG POS POS NEG POS Bedroom #3 Bedroom #2 Bedroom #2 Bedroom #2 Bedroom #2 Bedroom #2 Bathroom 1 Bedroom #3 Bedroom #3 Bedroom #2 Bedroom #2 Bedroom #2 Bedroom #2 Bedroom #2 Bedroom #2 **Living Room** Bathroom 1 Bedroom #3 Bedroom #3 Living Room Living Room **Living Room** Living Room Living Room Living Room Living Room Kitchen Kitchen Kitchen Kitchen Kitchen Kitchen Direction North North North North North North South North South North West South South West East East East East East East East Brown White Brown Brown Brown Brown White White White White White White White White White Blue Blue Tan Tan Tan Tan Tan Tan Substrate Drywall Ceramic Ceramic Ceramic Drywall Ceramic Wood Window Frame Window Frame Window Frame Window Seal Blasé board Door Frame Component Ceiling Cabinet Ceiling Wall Door Wall Seal Ξie ∏e Tile Condition Intact Intact



Intact	Door	Wood	Brown	North	Exterior	POS	0.3	4.3	312	8/7/2020
Intact	Door Frame	Wood	Brown	North	Exterior	POS	0.3	3.6	311	8/7/2020
Intact	Eves	Wood	Brown	North	Exterior	NEG	0.1	0.7	310	8/7/2020
Intact	Wall	Wood	Brown	North	Exterior	POS	0.3	10	309	8/7/2020
Intact	Eves	Wood	Brown	East	Exterior	NEG	0.3	0	308	8/7/2020
Intact	Eves	Wood	Brown	East	Exterior	NEG	0.1	0.5	307	8/7/2020
Intact	Facia	Metal	Brown	East	Exterior	NEG	0.2	0.1	306	8/7/2020
Intact	Door	Wood	Red	East	Exterior	NEG	0.3	-0.1	305	8/7/2020
Intact	Post	Wood	Dark Brown	East	Exterior	NEG	0.3	0	304	8/7/2020
Intact	Window Seal	Wood	Dark Brown	East	Exterior	POS	0.3	3.2	303	8/7/2020
Intact	Window-Frame	Wood	Dark Brown	East	Exterior	POS	0.3	6.4	302	8/7/2020
Intact	Trim	Wood	Dark Brown	East	Exterior	POS	0.3	3	301	8/7/2020
Intact	Wall	Wood	Brown	East	Exterior	POS	0.3	5.3	300	8/7/2020
Intact	Wall	Wood	Yellow	South	Exterior	NEG	0.2	0.3	299	8/7/2020
Intact	Door	Wood	White	East	Hallway	POS	0.3	4.5	298	8/7/2020
Intact	Door Frame	Wood	White	East	Hallway	NEG	0.3	0.1	297	8/7/2020
Intact	Cabinet	Wood	Varnish	East	Hallway	NEG	0.2	0.4	296	8/7/2020
Intact	Ceiling Tile	Cardboard	White	East	Hallway	NEG	0.2	0.1	295	8/7/2020
Intact	Wall	Drywall	White	East	Hallway	NEG	0.3	0	294	8/7/2020
Intact	Wall	Drywall	White	East	Hallway	NEG	0.2	0.1	293	8/7/2020
Intact	Wall	Drywall	White	East	Hallway	NEG	0.2	0.1	292	8/7/2020
Intact	Wall	Porcelain	White	East	Bath #2	NEG	0.2	0.1	291	8/7/2020
Intact	Sink	Ceramic	Tan	East	Bath #2	NEG	0.3	-0.5	290	8/7/2020
Intact	Floor	Wood	White	East	Bath #2	NEG	0.3	-0.2	289	8/7/2020
Intact	Window Frame	Wood	White	East	Bath #2	NEG	0.3	0.2	288	8/7/2020
Intact	Baseboard	Wood	White	East	Bath #2	NEG	0.2	0.2	287	8/7/2020
Intact	Door Frame	Wood	White	East	Bath #2	NEG	0.3	0.2	286	8/7/2020
Intact	Ceiling	Wood	White	East	Bath #2	NEG	0.3	0	285	8/7/2020
Intact	Wall	Wood	White	East	Bath #2	NEG	0.3	0.1	284	8/7/2020
Intact	Wall	Wood	Tan	South	Bath #2	NEG	0.3	0.1	283	8/7/2020
Intact	Wall	Wood	Tan	West	Bath #2	NEG	0.2	0	282	8/7/2020
Intact	Wall	Wood	Tan	North	Bath #2	NEG	0.3	0.2	281	8/7/2020
Intact	Window Seal	Wood	Blue	East	Bedroom #3	POS	0.3	2	280	8/7/2020
Condition	Component	Substrate	Color	Direction	Room	Result	+/-	Pb (mg/cm2)	Sample #	Date
									(



8/7/2020 344	8/7/2020 343	8/7/2020 342	8/7/2020 341	8/7/2020 340	8/7/2020 339	8/7/2020 338	8/7/2020 337	8/7/2020 336	8/7/2020 335	8/7/2020 334	8/7/2020 333	8/7/2020 332	8/7/2020 331	8/7/2020 330	8/7/2020 329	8/7/2020 328	8/7/2020 327	8/7/2020 326		8/7/2020 325	8/7/2020 324	8/7/2020 323	8/7/2020 322	8/7/2020 321	8/7/2020 320	8/7/2020 319	8/7/2020 318	8/7/2020 317	8/7/2020 316	8/7/2020 315	8/7/2020 314	8/7/2020 313	Date Sample #	
4 0.1	3 0.1	2 0.1	1 0.2	0 0.1	9 -0.2	8 0.1	7 0.2	6 0.1	5 0	4 0.1	3 0	2 -0.1	1 -0.1	0 0	9 0.1	8 0.1	7 0	6 -0.1		5 0.1	4 -0.3	3 0.1	2 0	1 0.1	0 0.4	9 1.4	8 6.5	7 6.5	6 5.9	5 0	4 1.1		le # Pb (mg/cm2)	
0.3	0.3	0.3	0.3	0.3	0.2	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3		0.3	0.3	0.3	0.3	0.3	0.2	0.2	0.3	0.3	0.3	0.3	0.3	0.1	+/-	
NEG		NEG	NEG	NEG	NEG	NEG	NEG	POS	POS	POS	POS	NEG	POS	NEG	Result																			
252	252	252	252	252	256	256	256	256	256	256	257	257	257	257	257	257	257	Garage	1800 La V	Garage	Garage	Garage	Garage	Garage	Exterior	Room								
North	South	East	West	North	South	South	South	East	West	North	East	East	East	East	South	West	North	East	Veta - 2nd Floor	East	East	North	West	South	North	West	West	West	West	North	North	North	Direction	
White	White	White	White	White	Tan	White	White	White	White	White	Tan	Tan	Tan	White	White	White	White	Blue		Blue	White	White	White	White	Brown	Color								
Drywall	Drywall	Drywall	Drywall	Drywall	Metal	Metal	Drywall	Drywall	Drywall	Drywall	Wood	Wood	Metal	Drywall	Drywall	Drywall	Drywall	Metal		Metal	Brick	Drywall	Drywall	Drywall	Wood	Substrate								
Pillar	Wall	Wall	Wall	Wall	Door Frame	T-Bar	Wall	Wall	Wall	Wall	Window Frame	Door	Door Frame	Wall	Wall	Wall	Wall	Door		Door Frame	Wall	Wall	Wall	Wall	Window Seal	Window Frame	Eves	Facia	Wall	Attic Hatch	Window Seal	Window Frame	Component	
Intact		Intact	Condition																															



Intact	Wall	Drywall	Dark Grey	East	251	NEG	0.3	0.2	377	8/7/2020
Intact	Door	Wood	Red	East	253	NEG	0.3	-0.1	376	8/7/2020
Intact	Door Frame	Metal	Red	East	253	NEG	0.3	0	375	8/7/2020
Intact	Wall	Drywall	Grey	East	253	NEG	0.3	0	374	8/7/2020
Intact	Wall	Drywall	Grey	South	253	NEG	0.3	0	373	8/7/2020
Intact	Wall	Drywall	Grey	West	253	NEG	0.3	0.1	372	8/7/2020
Intact	Wall	Drywall	Grey	North	253	NEG	0.3	0	371	8/7/2020
Intact	Door	Wood	Red	East	254	NEG	0.3	-0.1	370	8/7/2020
Intact	Door Frame	Metal	Red	East	254	NEG	0.3	-0.1	369	8/7/2020
Intact	Wall	Drywall	Grey	East	254	NEG	0.3	0	368	8/7/2020
Intact	Wall	Drywall	Grey	South	254	NEG	0.3	0	367	8/7/2020
Intact	Wall	Drywall	Grey	West	254	NEG	0.3	0	366	8/7/2020
Intact	Wall	Drywall	Grey	North	254	NEG	0.3	0.1	365	8/7/2020
Intact	Door	Wood	Blue	East	250	NEG	0.3	-0.1	364	8/7/2020
Intact	Door Frame	Metal	Blue	East	250	NEG	0.3	-0.1	363	8/7/2020
Intact	Wall	Drywall	White	East	250	NEG	0.3	0.1	362	8/7/2020
Intact	Wall	Drywall	White	South	250	NEG	0.3	0	361	8/7/2020
Intact	Wall	Drywall	White	West	250	NEG	0.3	0	360	8/7/2020
Intact	Wall	Drywall	White	North	250	NEG	0.3	0.1	359	8/7/2020
Intact	Sink	Porcelain	White	West	W Restroom	NEG	0.1	0.5	358	8/7/2020
Intact	Floor	Ceramic	Grey	West	W Restroom	NEG	0.3	0.3	357	8/7/2020
Intact	Wall Tile	Ceramic	Tan	West	W Restroom	POS	0.3	5.3	356	8/7/2020
Intact	Door Frame	Metal	Purple	West	Restroom 14	NEG	0.3	0	355	8/7/2020
Intact	Urinal	Porcelain	White	South	Restroom 14	NEG	0.3	-0.1	354	8/7/2020
Intact	Sink	Porcelain	White	South	Restroom 14	NEG	0.3	-0.2	353	8/7/2020
Intact	Tile	Ceramic	Orange	South	Restroom 14	NEG	0.2	0.4	352	8/7/2020
Intact	Tile	Ceramic	Pink	South	Restroom 14	NEG	0.3	-0.6	351	8/7/2020
Intact	Tile	Ceramic	Yellow	South	Restroom 14	NEG	0.3	0.2	350	8/7/2020
Intact	Wall	Drywall	White	East	248	NEG	0.3	0.1	349	8/7/2020
Intact	Wall	Drywall	White	East	248	NEG	0.3	-0.1	348	8/7/2020
Intact	Wall	Drywall	White	West	248	NEG	0.3	0	347	8/7/2020
Intact	Wall	Drywall	White	North	248	NEG	0.3	0.1	346	8/7/2020
Intact	Chair Rail	Wood	Brown	North	252	NEG	0.3	-0.1	345	8/7/2020
Condition	Component	Substrate	Color	Direction	Room	Result	+/-	Pb (mg/cm2)	Sample #	Date



0 0.3 NEG 25.1 West Dark Grey Drywall Wall Inflact 0.1 0.3 NEG 251 East Dark Grey Drywall Wall Inflact 0.1 0.3 NEG 251 South Red Metal Door Frame Inflact 0.1 0.3 NEG 251 South Red Metal Door Inflact 0.2 0.3 NEG 250 North Grey Drywall Wall Inflact 0.2 0.3 NEG 250 South Grey Drywall Wall Inflact 0.2 0.3 NEG 250 East Red Wood Door Inflact 0.1 0.3 NEG 252 North White Drywall Wall Inflact 0.1 0.3 NEG 252 North White Drywall Wall Inflact 0.1 0.3 <	8/7/2020 408 8/7/2020 409
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 251 South Red Metal Door 0.3 NEG 250 North Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall 0.3 NEG 250 East Grey Drywall Wall 0.3 NEG 250 East Red Wood Door 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 North Red Wood Door Frame 0.3 NEG 239 North White	
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 250 South Red Metal Door Frame 0.3 NEG 250 West Grey Drywall Wall 0.3 NEG 250 West Grey Drywall Wall 0.3 NEG 250 East Grey Drywall Wall 0.3 NEG 250 East Red Wood Door Frame 0.3 NEG 252 Rest White Drywall Wall 0.3 NEG 252 South White Drywall Wall 0.3 NEG 252 North White Drywall Wall 0.3 NEG 239 South White <td></td>	
0.3 NeG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 250 North Red Metal Door Frame 0.3 NEG 250 West Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall 0.3 NEG 250 East Grey Drywall Wall 0.3 NEG 250 East Red Wood Door Frame 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 North Red Wood Door Frame 0.3 NEG 252 North White<	8/7/2020 407
0.3 NeG 251 West Dark Grey Drywall Wall 0.3 NeG 251 East Dark Grey Drywall Wall 0.3 NeG 251 South Red Metal Door Frame 0.3 NeG 251 South Red Metal Door Frame 0.3 NeG 250 North Grey Drywall Wall 0.3 NeG 250 West Grey Drywall Wall 0.3 NeG 250 East Grey Drywall Wall 0.3 NeG 250 East Grey Drywall Wall 0.3 NeG 250 East Metal Door Frame 0.3 NeG 252 North White Drywall Wall 0.3 NEG 252 North West White Drywall Wall 0.3 NEG 239 North West <td>8/7/2020 406</td>	8/7/2020 406
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 250 North Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall 0.3 NEG 250 East Grey Drywall Wall 0.3 NEG 250 East Red Wood Door Frame 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 North Red Wood Door Frame 0.3 NEG 252 North Red </td <td>8/7/2020 405</td>	8/7/2020 405
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 250 North Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall 0.3 NEG 250 East Grey Drywall Wall 0.3 NEG 250 East Red Wood Door Frame 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 East White Drywall Wall 0.3 NEG 252 North Red Metal Door Frame 0.3 NEG 252 North White	8/7/2020 404
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 251 South Red Metal Door 0.3 NEG 250 North Grey Drywall Wall 0.3 NEG 250 West Grey Drywall Wall 0.3 NEG 250 East Grey Drywall Wall 0.3 NEG 250 East Red Mood Door 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 West White Drywall Wall 0.3 NEG 252 West White Drywall Wall 0.3 NEG 252 North White <t< td=""><td>8/7/2020 403</td></t<>	8/7/2020 403
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 250 North Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall 0.3 NEG 250 East Grey Drywall Wall 0.3 NEG 250 East Red Wood Door 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 North White	8/7/2020 402
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 250 North Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall 0.3 NEG 250 East Grey Drywall Wall 0.3 NEG 250 East Red Wood Door Frame 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 East White Drywall Wall 0.3 NEG 252 North White Door Wall 0.3 NEG 252 North Red	8/7/2020 401
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 250 North Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall 0.3 NEG 250 East Grey Drywall Wall 0.3 NEG 250 East Red Wood Door Frame 0.3 NEG 252 Rast White Drywall Wall 0.3 NEG 252 West White Drywall Wall 0.3 NEG 252 South White Drywall Wall 0.3 NEG 252 North Red	8/7/2020 400
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 251 South Red Metal Door 0.3 NEG 250 North Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall 0.3 NEG 250 East Grey Drywall Wall 0.3 NEG 250 East Red Metal Door 0.3 NEG 250 East Red Wood Door 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 North Red Mo	8/7/2020 399
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 250 North Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall 0.3 NEG 250 East Grey Drywall Wall 0.3 NEG 250 East Red Wood Door Frame 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 West White Drywall Wall 0.3 NEG 252 West White Drywall Wall 0.3 NEG 252 North Red	8/7/2020 398
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 250 North Grey Drywall Wall 0.3 NEG 250 West Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall 0.3 NEG 250 East Grey Drywall Wall 0.3 NEG 250 East Red Wood Door Frame 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 West White Drywall Wall 0.3 NEG 252 West White Drywall Wall 0.3 NEG 252 North White	8/7/2020 397
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 250 North Red Metal Door Frame 0.3 NEG 250 West Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall 0.3 NEG 250 East Grey Drywall Wall 0.3 NEG 250 East Red Metal Door Frame 0.3 NEG 250 East Red Wood Door 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 East White Drywall Wall 0.3 NEG 252 North White	8/7/2020 396
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 250 North Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall 0.3 NEG 250 East Grey Drywall Wall 0.3 NEG 250 East Red Wood Door Frame 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 West White Drywall Wall 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 North Metal </td <td>8/7/2020 395</td>	8/7/2020 395
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 250 North Red Metal Door Frame 0.3 NEG 250 West Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall 0.3 NEG 250 East Grey Drywall Wall 0.3 NEG 250 East Red Metal Door Frame 0.3 NEG 250 East Red Wood Door 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 East White Drywall Wall 0.3 NEG 252 South White	8/7/2020 394
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 250 North Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall 0.3 NEG 250 East Grey Drywall Wall 0.3 NEG 250 East Red Metal Door Frame 0.3 NEG 250 East Red Wood Door 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 South White	8/7/2020 393
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 250 North Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall 0.3 NEG 250 East Grey Drywall Wall 0.3 NEG 250 East Red Metal Door Frame 0.3 NEG 250 East Red Wood Door Frame 0.3 NEG 250 East Red Wood Door Frame 0.3 NEG 252 North White Drywall Wall 0.3 NEG 252 North White Drywall Wall	8/7/2020 392
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 250 North Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall 0.3 NEG 250 East Grey Drywall Wall 0.3 NEG 250 East Red Metal Door Frame 0.3 NEG 250 East Red Wood Door Frame 0.3 NEG 250 East Red Wood Door 0.3 NEG 250 East Red Wood Door 0.3 NEG 250 East Red Wood Door 0.3 NEG 250 East Door Wall	8/7/2020 391
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 250 North Red Metal Door 0.3 NEG 250 West Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall 0.3 NEG 250 East Grey Drywall Wall 0.3 NEG 250 East Red Metal Door Frame 0.3 NEG 250 East Red Wood Door 0.3 NEG 250 East Red Wood Door	8/7/2020 390
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 250 North Grey Drywall Wall 0.3 NEG 250 West Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall 0.3 NEG 250 East Grey Drywall Wall 0.3 NEG 250 East Grey Drywall Wall 0.3 NEG 250 East Red Metal Door Frame 0.3 NEG 250 East Red Mood Door Frame	8/7/2020 389
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 250 North Grey Drywall Wall 0.3 NEG 250 West Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall 0.3 NEG 250 East Grey Drywall Wall	8/7/2020 388
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 251 South Red Metal Door 0.3 NEG 250 North Grey Drywall Wall 0.3 NEG 250 West Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall	8/7/2020 387
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 251 South Red Metal Door 0.3 NEG 250 North Grey Drywall Wall 0.3 NEG 250 West Grey Drywall Wall 0.3 NEG 250 South Grey Drywall Wall	8/7/2020 386
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 251 South Red Metal Door 0.3 NEG 250 North Grey Drywall Wall 0.3 NEG 250 West Grey Drywall Wall	8/7/2020 385
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall 0.3 NEG 251 South Red Metal Door Frame 0.3 NEG 251 South Red Metal Door 0.3 NEG 250 North Grey Drywall Wall	8/7/2020 384
0.3NEG251WestDark GreyDrywallWall0.3NEG251EastDark GreyDrywallWall0.3NEG251SouthRedMetalDoor Frame0.3NEG251SouthRedMetalDoor	8/7/2020 383
0.3NEG251WestDark GreyDrywallWall0.3NEG251EastDark GreyDrywallWall0.3NEG251SouthRedMetalDoor Frame	8/7/2020 382
0.3 NEG 251 West Dark Grey Drywall Wall 0.3 NEG 251 East Dark Grey Drywall Wall	8/7/2020 381
0.3 NEG 251 West Dark Grey Drywaii Wali	8/7/2020 380
	8/7/2020 379
0.3 NEG 251 North Dark Grey Drywall Wall	
Pb (mg/cm2) +/- Result Room Direction Color Substrate Component Condition	Date Sample # F





8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	8/7/2020	Date
472	471	470	469	468	467	466	465	464	463	462	461	460	459	458	457	456	455	454	453	452	451	450	449	448	447	446	445	444	Sample #
0.1	0.1	0.1	-0.2	-0.1	29.4	0.2	0.3	23.4	-0.3	17.8	-0.1	0.1	0.3	0	-0.1	0.1	-0.2	-0.2	0.1	0	0	0	-0.1	-0.1	0.4	0.4	0.4	0.4	Pb (mg/cm2)
0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.2	0.2	0.2	0.2	+/-
NEG	NEG	NEG	NEG	NEG	POS	NEG	NEG	POS	NEG	POS	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	NEG	Result
205	205	205	209	209	209	216	Womens Restroom	Womens Restroom	Mens Restroom	Mens Restroom	240	240	240	222	222	222	223	223	223	221	221	221	221	224	224	224	224	224	Room
West	West	West	West	West	West	East	North	North	North	North	North	North	North	North	North	North	North	North	North	East	South	West	North	South	East	South	West	North	Direction
White	Grey	Yellow	Tan	White	White	White	White	Pink	White	Blue	Green	Green	Green	Green	Green	White	White	Green	Green	White	White	White	White	Green	White	White	White	White	Color
VFT	VFT	Drywall	Ceramic	Porcelain	Ceramic	Cast Iron	Porcelain	Ceramic	Porcelain	Ceramic	Wood	Metal	Drywall	Wood	Wood	Drywall	Wood	Wood	Drywall	Drywall	Drywall	Drywall	Drywall	Wood	Drywall	Drywall	Drywall	Drywall	Substrate
Floor	Floor	Wall	Floor	Sink	Tile	Sink	Sink	Tile	Sink	Wall	Door	Door Frame	Wall	Door	Door Frame	Wall	Baseboard	Chair Rail	Wall	Wall	Wall	Wall	Wall	Door Frame	Wall	Wall	Wall	Wall	Component
Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Intact	Condition



-			CALIBRATION			NEG	0.3	-0.2	500	8/7/2020
			CALIBRATION			POS	0.2	1.1	499	8/7/2020
			CALIBRATION			POS	0.2	1.1	498	0202/7/8
-	-		CALIBRATION			POS	0.2	1.1	497	8/7/2020
Intact	Wall	stucco	Tan	South	Exterior	NEG	0.3	-0.3	496	8/7/2020
Intact	Wall	stucco	Tan	North	Exterior	NEG	0.3	-0.4	495	8/7/2020
Intact	door?	Metal	Tan	East	Exterior	NEG	0.3	0	494	8/7/2020
Intact	Wall	stucco	White	North	Exterior	NEG	0.2	0.4	493	8/7/2020
Intact	Wall	stucco	Tan	West	Exterior	NEG	0.1	0.5	492	8/7/2020
Intact	Wall	Brick	Red	East	Exterior	NEG	0.3	0.1	491	8/7/2020
Intact	Stair Hand Rail	Metal		West	Exterior	NEG	0.2	0.4	490	8/7/2020
Intact	Gutter	Metal	Blue	West	Exterior	NEG	0.3	0	489	8/7/2020
Intact	Wall	stucco	Tan	West	Exterior	NEG	0.3	-0.2	488	8/7/2020
Intact	Door	Wood	Green	West	Stairwell	NEG	0.2	0.1	487	8/7/2020
Intact	Door Frame	Metal	Green	South	Stairwell	NEG	0.1	0.7	486	8/7/2020
Intact	Storage	Wood	White	South	Stairwell	NEG	0.3	0	485	8/7/2020
Intact	Floor	VFT	Grey	South	Stairwell	NEG	0.3	0	484	8/7/2020
Intact	Wall	Drywall	White	South	Stairwell	NEG	0.3	0	483	8/7/2020
Intact	Wall	Metal	Tan	South	Exterior Room	NEG	0.3	0.1	482	8/7/2020
Intact	Wall	stucco	Tan	South	Exterior Room	NEG	0.3	-0.1	481	8/7/2020
Intact	Trim	Wood		South	Exterior Room	NEG	0.3	0.1	480	8/7/2020
Intact	Wind barrier	Wood	White	South	Exterior Room	NEG	0.2	-0.1	479	8/7/2020
Intact	Baseboard	Wood	Blue	South	201	NEG	0.3	0.1	478	8/7/2020
Intact	Wall	Drywall	Blue	North	201	NEG	0.3	0	477	8/7/2020
Intact	Baseboard	Wood	Green	North	202	NEG	0.3	0.2	476	8/7/2020
Intact	Wall	Drywall	Green	South	202	NEG	0.3	0.2	475	8/7/2020
Intact	Walli	Drywall	Light Green	West	202	NEG	0.3	-0.1	474	8/7/2020
Intact	Door Frame	Wood	Yellow	North	205	NEG	0.3	0.2	473	8/7/2020
Condition	Component	Substrate	Color	Direction	Room	Result	+/-	Pb (mg/cm2)	Sample #	Date

APPENDIX IV
Personnel Certifications

DEPARTMENT OF INDUSTRIAL RELATIONS
Division of Occupational Safety and Health
Asbestos Certification & Training Unit
2424 Arden Way, Suite 495
Sacramento, CA 95825-2417
(916) 574-2993 Office (916) 483-0572 Fax
http://www.dir.ca.gov/dosh/asbestos.html acru@dir.ca.gov



907074549C

328

EFI Global Benjamin P Curry 5261 West Imperial Highway Los Angeles CA 90045 June 20, 2019

Dear Certified Asbestos Consultant or Technician:

Enclosed is your certification card. To maintain your certification, you must abide by the rules printed on the back of the certification card.

Your certification is valid for a period of one year. If you wish to renew your certification, you must apply for renewal at least 60 days <u>before</u> the expiration date shown on your card. [8 CCR 341.15(h)(1)].

Please hold and do not send copies of your required AHERA refresher renewal certificates to our office until you apply for renewal of your certification.

Certificates must be kept current if you are actively working as a CAC or CSST. The grace period is only for those who are not actively working as an asbestos consultant or site surveillance technician.

Please contact our office at the above address or email with any changes in your contact/mailing information within 15 days of the change.

Sincerely,

Jeff_Ferrell

Senior Safety Engineer

Attachment: Certification Card

cc: File





STATE OF CALIFORNIA DEPARTMENT OF PUBLIC HEALTH



LEAD-RELATED CONSTRUCTION CERTIFICATE

INDIVIDUAL:

CERTIFICATE TYPE:

NUMBER:

EXPIRATION DATE:

Lead Inspector/Assessor Lead Supervisor LRC-00000208 LRC-00000207 4/5/2021 4/5/2021

Benjamin Curry

Disclaimer: This document alone should not be relied upon to confirm certification status. Compare the individual's photo and name to another valid form of government issued photo identification. Verify the individual's certification status by searching for Lead-Related Construction Professionals at www.cdph.ca.gov/programs/clppb or calling (800) 597-LEAD.

DEPARTMENT OF INDUSTRIAL RELATIONS
Division of Occupational Safety and Health
Asbestos Certification & Training Unit
2424 Arden Way, Suite 495
Sacramento, CA 95825-2417
(916) 574-2993 Office http://www.dir.ca.gov/dosh/asbestos.html acru@dir.ca.gov



511255572T

405

409

April 20, 2020

Heriberto Romero 1818 E. 84th Street Los Angeles CA 90001

Dear Certified Asbestos Consultant or Technician:

Enclosed is your certification card. To maintain your certification, you must abide by the rules printed on the back of the certification card.

Your certification is valid for a period of one year. If you wish to renew your certification, you must apply for renewal at least 60 days <u>before</u> the expiration date shown on your card. [8 CCR 341.15(h)(1)].

Please hold and do not send copies of your required AHERA refresher renewal certificates to our office until you apply for renewal of your certification.

Certificates must be kept current if you are actively working as a CAC or CSST. The grace period is only for those who are not actively working as an asbestos consultant or site surveillance technician.

Please notify our office via U.S. Postal Service or other carrier of any changes in your mailing or work address within 15 days of the change.

Sincerely,

Jeff Ferrell

Senior Safety Engineer

Attachment: Certification Card

cc: File





STATE OF CALIFORNIA DEPARTMENT OF PUBLIC HEALTH



LEAD-RELATED CONSTRUCTION CERTIFICATE

INDIVIDUAL:

CERTIFICATE TYPE:

NUMBER:

EXPIRATION DATE:

Lead Supervisor

LRC-00001469 LRC-00001468 6/13/2020 6/13/2020

Jacob Pulliam

Disclaimer: This document alone should not be relied upon to confirm certification status. Compare the individual's photo and name to another valid form of government issued photo identification. Verify the individual's certification status by searching for Lead-Related Construction Professionals at www.cdph.ca.gov/programs/clppb or calling (800) 597-LEAD.

Attachment 9. USFWS IPaC

IPaC

IPaC resource list

This report is an automatically generated list of species and other resources such as critical habitat (collectively referred to as *trust resources*) under the U.S. Fish and Wildlife Service's (USFWS) jurisdiction that are known or expected to be on or near the project area referenced below. The list may also include trust resources that occur outside of the project area, but that could potentially be directly or indirectly affected by activities in the project area. However, determining the likelihood and extent of effects a project may have on trust resources typically requires gathering additional site-specific (e.g., vegetation/species surveys) and project-specific (e.g., magnitude and timing of proposed activities) information.

Below is a summary of the project information you provided and contact information for the USFWS office(s) with jurisdiction in the defined project area. Please read the introduction to each section that follows (Endangered Species, Migratory Birds, USFWS Facilities, and NWI Wetlands) for additional information applicable to the trust resources addressed in that section.

Location

Orange County, California



Local office

Carlsbad Fish And Wildlife Office

\((760) 431-9440

(760) 431-5901

NOT FOR CONSULTATIO

2177 Salk Avenue - Suite 250 Carlsbad, CA 92008-7385

Endangered species

This resource list is for informational purposes only and does not constitute an analysis of project level impacts.

The primary information used to generate this list is the known or expected range of each species. Additional areas of influence (AOI) for species are also considered. An AOI includes areas outside of the species range if the species could be indirectly affected by activities in that area (e.g., placing a dam upstream of a fish population even if that fish does not occur at the dam site, may indirectly impact the species by reducing or eliminating water flow downstream). Because species can move, and site conditions can change, the species on this list are not guaranteed to be found on or near the project area. To fully determine any potential effects to species, additional site-specific and project-specific information is often required.

Section 7 of the Endangered Species Act **requires** Federal agencies to "request of the Secretary information whether any species which is listed or proposed to be listed may be present in the area of such proposed action" for any project that is conducted, permitted, funded, or licensed by any Federal agency. A letter from the local office and a species list which fulfills this requirement can **only** be obtained by requesting an official species list from either the Regulatory Review section in IPaC (see directions below) or from the local field office directly.

For project evaluations that require USFWS concurrence/review, please return to the IPaC website and request an official species list by doing the following:

- 1. Draw the project location and click CONTINUE.
- 2. Click DEFINE PROJECT.
- 3. Log in (if directed to do so).
- 4. Provide a name and description for your project.
- 5. Click REQUEST SPECIES LIST.

Listed species¹ and their critical habitats are managed by the <u>Ecological Services Program</u> of the U.S. Fish and Wildlife Service (USFWS) and the fisheries division of the National Oceanic and Atmospheric Administration (NOAA Fisheries²).

Species and critical habitats under the sole responsibility of NOAA Fisheries are **not** shown on this list. Please contact <u>NOAA Fisheries</u> for <u>species under their jurisdiction</u>.

1. Species listed under the <u>Endangered Species Act</u> are threatened or endangered; IPaC also shows species that are candidates, or proposed, for listing. See the <u>listing status page</u> for more information. IPaC only shows species that are regulated by USFWS (see FAQ).

2. <u>NOAA Fisheries</u>, also known as the National Marine Fisheries Service (NMFS), is an office of the National Oceanic and Atmospheric Administration within the Department of Commerce.

The following species are potentially affected by activities in this location:

Birds

NAME STATUS

Coastal California Gnatcatcher Polioptila californica

Threatened

californica

Wherever found

There is **final** critical habitat for this species. Your location does not overlap the critical habitat.

https://ecos.fws.gov/ecp/species/8178

Least Bell's Vireo Vireo bellii pusillus

Endangered

Wherever found

There is **final** critical habitat for this species. Your location does not overlap the critical habitat.

https://ecos.fws.gov/ecp/species/5945

Southwestern Willow Flycatcher Empidonax traillii extimus

Wherever found

There is **final** critical habitat for this species. Your location does not overlap the critical habitat.

https://ecos.fws.gov/ecp/species/6749

Endangered

Reptiles

NAME STATUS

Southwestern Pond Turtle Actinemys pallida

Proposed Threatened

Wherever found

No critical habitat has been designated for this species.

https://ecos.fws.gov/ecp/species/4768

Fishes

NAME STATUS

Santa Ana Sucker Catostomus santaanae

Threatened

There is **final** critical habitat for this species. Your location does not overlap the critical habitat.

https://ecos.fws.gov/ecp/species/3785

Insects

NAME STATUS

Monarch Butterfly Danaus plexippus

Candidate

Wherever found

No critical habitat has been designated for this species.

https://ecos.fws.gov/ecp/species/9743

Critical habitats

Potential effects to critical habitat(s) in this location must be analyzed along with the endangered species themselves.

There are no critical habitats at this location.

You are still required to determine if your project(s) may have effects on all above listed species.

Bald & Golden Eagles

Bald and golden eagles are protected under the Bald and Golden Eagle Protection Act¹ and the Migratory Bird Treaty Act².

Any person or organization who plans or conducts activities that may result in impacts to bald or golden eagles, or their habitats³, should follow appropriate regulations and consider implementing appropriate conservation measures, as described in the links below. Specifically, please review the "Supplemental Information on Migratory Birds and Eagles".

Additional information can be found using the following links:

- Eagle Management https://www.fws.gov/program/eagle-management
- Measures for avoiding and minimizing impacts to birds
 https://www.fws.gov/library/collections/avoiding-and-minimizing-incidental-take-migratory-birds
- Nationwide conservation measures for birds
 <u>https://www.fws.gov/sites/default/files/documents/nationwide-standard-conservation-measures.pdf</u>
- Supplemental Information for Migratory Birds and Eagles in IPaC <a href="https://www.fws.gov/media/supplemental-information-migratory-birds-and-bald-and-decomposition-migratory-birds-and-bald-and-decomposition-migratory-birds-and-bald-and-decomposition-migratory-birds-and-bald-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-bald-and-decomposition-migratory-birds-and-bald-and-decomposition-migratory-birds-and-bald-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-decomposition-migratory-birds-and-d

golden-eagles-may-occur-project-action

There are bald and/or golden eagles in your project area.

For guidance on when to schedule activities or implement avoidance and minimization measures to reduce impacts to migratory birds on your list, see the PROBABILITY OF PRESENCE SUMMARY below to see when these birds are most likely to be present and breeding in your project area.

NAME BREEDING SEASON

Bald Eagle Haliaeetus leucocephalus

Breeds Jan 1 to Aug 31

This is not a Bird of Conservation Concern (BCC) in this area, but warrants attention because of the Eagle Act or for potential susceptibilities in offshore areas from certain types of development or activities.

Probability of Presence Summary

The graphs below provide our best understanding of when birds of concern are most likely to be present in your project area. This information can be used to tailor and schedule your project activities to avoid or minimize impacts to birds. Please make sure you read "Supplemental Information on Migratory Birds and Eagles", specifically the FAQ section titled "Proper Interpretation and Use of Your Migratory Bird Report" before using or attempting to interpret this report.

Probability of Presence (■)

Each green bar represents the bird's relative probability of presence in the 10km grid cell(s) your project overlaps during a particular week of the year. (A year is represented as 12 4-week months.) A taller bar indicates a higher probability of species presence. The survey effort (see below) can be used to establish a level of confidence in the presence score. One can have higher confidence in the presence score if the corresponding survey effort is also high.

How is the probability of presence score calculated? The calculation is done in three steps:

- 1. The probability of presence for each week is calculated as the number of survey events in the week where the species was detected divided by the total number of survey events for that week. For example, if in week 12 there were 20 survey events and the Spotted Towhee was found in 5 of them, the probability of presence of the Spotted Towhee in week 12 is 0.25.
- 2. To properly present the pattern of presence across the year, the relative probability of presence is calculated. This is the probability of presence divided by the maximum probability of presence across all weeks. For example, imagine the probability of presence in week 20 for the Spotted Towhee is 0.05, and that the probability of presence at week

- 12 (0.25) is the maximum of any week of the year. The relative probability of presence on week 12 is 0.25/0.25 = 1; at week 20 it is 0.05/0.25 = 0.2.
- 3. The relative probability of presence calculated in the previous step undergoes a statistical conversion so that all possible values fall between 0 and 10, inclusive. This is the probability of presence score.

To see a bar's probability of presence score, simply hover your mouse cursor over the bar.

Breeding Season (-)

Yellow bars denote a very liberal estimate of the time-frame inside which the bird breeds across its entire range. If there are no yellow bars shown for a bird, it does not breed in your project area.

Survey Effort (|)

Vertical black lines superimposed on probability of presence bars indicate the number of surveys performed for that species in the 10km grid cell(s) your project area overlaps. The number of surveys is expressed as a range, for example, 33 to 64 surveys.


To see a bar's survey effort range, simply hover your mouse cursor over the bar.

No Data (-)

A week is marked as having no data if there were no survey events for that week.

Survey Timeframe

Surveys from only the last 10 years are used in order to ensure delivery of currently relevant information. The exception to this is areas off the Atlantic coast, where bird returns are based on all years of available data, since data in these areas is currently much more sparse.



What does IPaC use to generate the potential presence of bald and golden eagles in my specified location?

The potential for eagle presence is derived from data provided by the <u>Avian Knowledge Network (AKN)</u>. The AKN data is based on a growing collection of <u>survey</u>, <u>banding</u>, <u>and citizen science datasets</u> and is queried and filtered to return a list of those birds reported as occurring in the 10km grid cell(s) which your project intersects, and that have been identified as warranting special attention because they are a BCC species in that area, an eagle (<u>Eagle Act</u> requirements may apply). To see a list of all birds potentially present in your project area, please visit the <u>Rapid Avian Information Locator (RAIL) Tool</u>.

What does IPaC use to generate the probability of presence graphs of bald and golden eagles in my specified location?

The Migratory Bird Resource List is comprised of USFWS <u>Birds of Conservation Concern (BCC)</u> and other species that may warrant special attention in your project location.

The migratory bird list generated for your project is derived from data provided by the <u>Avian Knowledge Network (AKN)</u>. The AKN data is based on a growing collection of <u>survey</u>, <u>banding</u>, <u>and citizen science datasets</u> and is queried and filtered to return a list of those birds reported as occurring in the 10km grid cell(s) which your project intersects, and that have been identified as warranting special attention because they are a BCC species in that area, an eagle (<u>Eagle Act</u> requirements may apply), or a species that has a particular vulnerability to offshore activities or development.

Again, the Migratory Bird Resource list includes only a subset of birds that may occur in your project area. It is not representative of all birds that may occur in your project area. To get a list of all birds potentially present in your project area, please visit the <u>Rapid Avian Information Locator (RAIL) Tool</u>.

What if I have eagles on my list?

If your project has the potential to disturb or kill eagles, you may need to obtain a permit to avoid violating the <u>Eagle Act</u> should such impacts occur. Please contact your local Fish and Wildlife Service Field Office if you have questions.

Migratory birds

Certain birds are protected under the Migratory Bird Treaty Act¹ and the Bald and Golden Eagle Protection Act².

Any person or organization who plans or conducts activities that may result in impacts to migratory birds, eagles, and their habitats³ should follow appropriate regulations and consider implementing appropriate conservation measures, as described in the links below. Specifically, please review the "Supplemental Information on Migratory Birds and Eagles".

- 1. The Migratory Birds Treaty Act of 1918.
- 2. The <u>Bald and Golden Eagle Protection Act</u> of 1940.

Additional information can be found using the following links:

- Eagle Management https://www.fws.gov/program/eagle-management
- Measures for avoiding and minimizing impacts to birds
 https://www.fws.gov/library/collections/avoiding-and-minimizing-incidental-take-migratory-birds
- Nationwide conservation measures for birds https://www.fws.gov/sites/default/files/ documents/nationwide-standard-conservation-measures.pdf
- Supplemental Information for Migratory Birds and Eagles in IPaC https://www.fws.gov/media/supplemental-information-migratory-birds-and-bald-and-golden-eagles-may-occur-project-action

The birds listed below are birds of particular concern either because they occur on the USFWS Birds of Conservation Concern (BCC) list or warrant special attention in your project location. To learn more about the levels of concern for birds on your list and how this list is generated, see the FAQ below. This is not a list of every bird you may find in this location, nor a guarantee that every bird on this list will be found in your project area. To see exact locations of where birders and the general public have sighted birds in and around your project area, visit the E-bird data mapping tool (Tip: enter your location, desired date range and a species on your list). For projects that occur off the Atlantic Coast, additional maps and models detailing the relative occurrence and abundance of bird species on your list are available. Links to additional information about Atlantic Coast birds, and other important information about your migratory bird list, including how to properly interpret and use your migratory bird report, can be found below.

For guidance on when to schedule activities or implement avoidance and minimization measures to reduce impacts to migratory birds on your list, see the PROBABILITY OF PRESENCE SUMMARY below to see when these birds are most likely to be present and breeding in your project area.

NAME	BREEDING SEASON
Allen's Hummingbird Selasphorus sasin This is a Bird of Conservation Concern (BCC) throughout its range in the continental USA and Alaska. https://ecos.fws.gov/ecp/species/9637	Breeds Feb 1 to Jul 15
Bald Eagle Haliaeetus leucocephalus This is not a Bird of Conservation Concern (BCC) in this area, but warrants attention because of the Eagle Act or for potential susceptibilities in offshore areas from certain types of development or activities.	Breeds Jan 1 to Aug 31
Belding's Savannah Sparrow Passerculus sandwichensis beldingi This is a Bird of Conservation Concern (BCC) only in particular Bird Conservation Regions (BCRs) in the continental USA https://ecos.fws.gov/ecp/species/8	Breeds Apr 1 to Aug 15
Bullock's Oriole Icterus bullockii This is a Bird of Conservation Concern (BCC) only in particular Bird Conservation Regions (BCRs) in the continental USA	Breeds Mar 21 to Jul 25
California Gull Larus californicus	Breeds Mar 1 to Jul 31

range in the continental USA and Alaska.

This is a Bird of Conservation Concern (BCC) throughout its

C 1.C		- I	T .	1
(alitor	ทเล	Ihracher	Toxostoma	redivivium

This is a Bird of Conservation Concern (BCC) throughout its range in the continental USA and Alaska.

Breeds Jan 1 to Jul 31

Clark's Grebe Aechmophorus clarkii

This is a Bird of Conservation Concern (BCC) throughout its range in the continental USA and Alaska.

Breeds Jun 1 to Aug 31

Common Yellowthroat Geothlypis trichas sinuosa

This is a Bird of Conservation Concern (BCC) only in particular Bird Conservation Regions (BCRs) in the continental USA https://ecos.fws.gov/ecp/species/2084

Breeds May 20 to Jul 31

Lawrence's Goldfinch Carduelis lawrencei

This is a Bird of Conservation Concern (BCC) throughout its range in the continental USA and Alaska. https://ecos.fws.gov/ecp/species/9464

Breeds Mar 20 to Sep 20

Nuttall's Woodpecker Picoides nuttallii

This is a Bird of Conservation Concern (BCC) only in particular Bird Conservation Regions (BCRs) in the continental USA https://ecos.fws.gov/ecp/species/9410

Breeds Apr 1 to Jul 20

Oak Titmouse Baeolophus inornatus

This is a Bird of Conservation Concern (BCC) throughout its range in the continental USA and Alaska. https://ecos.fws.gov/ecp/species/9656

Breeds Mar 15 to Jul 15

Olive-sided Flycatcher Contopus cooperi

This is a Bird of Conservation Concern (BCC) throughout its range in the continental USA and Alaska. https://ecos.fws.gov/ecp/species/3914

Breeds May 20 to Aug 31

Short-billed Dowitcher Limnodromus griseus

This is a Bird of Conservation Concern (BCC) throughout its range in the continental USA and Alaska. https://ecos.fws.gov/ecp/species/9480

Breeds elsewhere

Tricolored Blackbird Agelaius tricolor

This is a Bird of Conservation Concern (BCC) throughout its range in the continental USA and Alaska. https://ecos.fws.gov/ecp/species/3910

Breeds Mar 15 to Aug 10

Western Grebe aechmophorus occidentalis

This is a Bird of Conservation Concern (BCC) throughout its range in the continental USA and Alaska.

https://ecos.fws.gov/ecp/species/6743

Breeds Jun 1 to Aug 31

Willet Tringa semipalmata

This is a Bird of Conservation Concern (BCC) throughout its range in the continental USA and Alaska.

Breeds elsewhere

Wrentit Chamaea fasciata

This is a Bird of Conservation Concern (BCC) throughout its range in the continental USA and Alaska.

Breeds Mar 15 to Aug 10

Probability of Presence Summary

The graphs below provide our best understanding of when birds of concern are most likely to be present in your project area. This information can be used to tailor and schedule your project activities to avoid or minimize impacts to birds. Please make sure you read "Supplemental Information on Migratory Birds and Eagles", specifically the FAQ section titled "Proper Interpretation and Use of Your Migratory Bird Report" before using or attempting to interpret this report.

Probability of Presence (■)

Each green bar represents the bird's relative probability of presence in the 10km grid cell(s) your project overlaps during a particular week of the year. (A year is represented as 12 4-week months.) A taller bar indicates a higher probability of species presence. The survey effort (see below) can be used to establish a level of confidence in the presence score. One can have higher confidence in the presence score if the corresponding survey effort is also high.

How is the probability of presence score calculated? The calculation is done in three steps:

- 1. The probability of presence for each week is calculated as the number of survey events in the week where the species was detected divided by the total number of survey events for that week. For example, if in week 12 there were 20 survey events and the Spotted Towhee was found in 5 of them, the probability of presence of the Spotted Towhee in week 12 is 0.25.
- 2. To properly present the pattern of presence across the year, the relative probability of presence is calculated. This is the probability of presence divided by the maximum probability of presence across all weeks. For example, imagine the probability of presence in week 20 for the Spotted Towhee is 0.05, and that the probability of presence at week 12 (0.25) is the maximum of any week of the year. The relative probability of presence on week 12 is 0.25/0.25 = 1; at week 20 it is 0.05/0.25 = 0.2.

3. The relative probability of presence calculated in the previous step undergoes a statistical conversion so that all possible values fall between 0 and 10, inclusive. This is the probability of presence score.

To see a bar's probability of presence score, simply hover your mouse cursor over the bar.

Breeding Season (=)

Yellow bars denote a very liberal estimate of the time-frame inside which the bird breeds across its entire range. If there are no yellow bars shown for a bird, it does not breed in your project area.

Survey Effort (1)

Vertical black lines superimposed on probability of presence bars indicate the number of surveys performed for that species in the 10km grid cell(s) your project area overlaps. The number of surveys is expressed as a range, for example, 33 to 64 surveys.


To see a bar's survey effort range, simply hover your mouse cursor over the bar.


No Data (-)

A week is marked as having no data if there were no survey events for that week.

Survey Timeframe

Surveys from only the last 10 years are used in order to ensure delivery of currently relevant information. The exception to this is areas off the Atlantic coast, where bird returns are based on all years of available data, since data in these areas is currently much more sparse.





Tell me more about conservation measures I can implement to avoid or minimize impacts to migratory birds.

Nationwide Conservation Measures describes measures that can help avoid and minimize impacts to all birds at any location year round. Implementation of these measures is particularly important when birds are most likely to occur in the project area. When birds may be breeding in the area, identifying the locations of any active nests and avoiding their destruction is a very helpful impact minimization measure. To see when birds are most likely to occur and be breeding in your project area, view the Probability of Presence Summary. Additional measures or permits may be advisable depending on the type of activity you are conducting and the type of infrastructure or bird species present on your project site.

What does IPaC use to generate the list of migratory birds that potentially occur in my specified location?

The Migratory Bird Resource List is comprised of USFWS <u>Birds of Conservation Concern (BCC)</u> and other species that may warrant special attention in your project location.

The migratory bird list generated for your project is derived from data provided by the <u>Avian Knowledge Network (AKN)</u>. The AKN data is based on a growing collection of <u>survey, banding, and citizen science datasets</u> and is queried and filtered to return a list of those birds reported as occurring in the 10km grid cell(s) which your project intersects, and that have been identified as warranting special attention because they are a BCC species in that area, an eagle (<u>Eagle Act</u> requirements may apply), or a species that has a particular vulnerability to offshore activities or development.

Again, the Migratory Bird Resource list includes only a subset of birds that may occur in your project area. It is not representative of all birds that may occur in your project area. To get a list of all birds potentially present in your project area, please visit the <u>Rapid Avian Information Locator (RAIL) Tool</u>.

What does IPaC use to generate the probability of presence graphs for the migratory birds potentially occurring in my specified location?

The probability of presence graphs associated with your migratory bird list are based on data provided by the <u>Avian Knowledge Network (AKN)</u>. This data is derived from a growing collection of <u>survey</u>, <u>banding</u>, <u>and</u> citizen science datasets.

Probability of presence data is continuously being updated as new and better information becomes available. To learn more about how the probability of presence graphs are produced and how to interpret them, go the Probability of Presence Summary and then click on the "Tell me about these graphs" link.

How do I know if a bird is breeding, wintering or migrating in my area?

To see what part of a particular bird's range your project area falls within (i.e. breeding, wintering, migrating or year-round), you may query your location using the <u>RAIL Tool</u> and look at the range maps provided for birds in your area at the bottom of the profiles provided for each bird in your results. If a bird on your migratory bird species list has a breeding season associated with it, if that bird does occur in your project area, there may be nests present at some point within the timeframe specified. If "Breeds elsewhere" is indicated, then the bird likely does not breed in your project area.

What are the levels of concern for migratory birds?

Migratory birds delivered through IPaC fall into the following distinct categories of concern:

1. "BCC Rangewide" birds are <u>Birds of Conservation Concern</u> (BCC) that are of concern throughout their range anywhere within the USA (including Hawaii, the Pacific Islands, Puerto Rico, and the Virgin Islands);

- 2. "BCC BCR" birds are BCCs that are of concern only in particular Bird Conservation Regions (BCRs) in the continental USA; and
- 3. "Non-BCC Vulnerable" birds are not BCC species in your project area, but appear on your list either because of the <u>Eagle Act</u> requirements (for eagles) or (for non-eagles) potential susceptibilities in offshore areas from certain types of development or activities (e.g. offshore energy development or longline fishing).

Although it is important to try to avoid and minimize impacts to all birds, efforts should be made, in particular, to avoid and minimize impacts to the birds on this list, especially eagles and BCC species of rangewide concern. For more information on conservation measures you can implement to help avoid and minimize migratory bird impacts and requirements for eagles, please see the FAQs for these topics.

Details about birds that are potentially affected by offshore projects

For additional details about the relative occurrence and abundance of both individual bird species and groups of bird species within your project area off the Atlantic Coast, please visit the <u>Northeast Ocean Data Portal</u>. The Portal also offers data and information about other taxa besides birds that may be helpful to you in your project review. Alternately, you may download the bird model results files underlying the portal maps through the <u>NOAA NCCOS Integrative Statistical Modeling and Predictive Mapping of Marine Bird Distributions and Abundance on the Atlantic Outer Continental Shelf project webpage.</u>

Bird tracking data can also provide additional details about occurrence and habitat use throughout the year, including migration. Models relying on survey data may not include this information. For additional information on marine bird tracking data, see the <u>Diving Bird Study</u> and the <u>nanotag studies</u> or contact <u>Caleb Spiegel</u> or <u>Pam Loring</u>.

What if I have eagles on my list?

If your project has the potential to disturb or kill eagles, you may need to <u>obtain a permit</u> to avoid violating the Eagle Act should such impacts occur.

Proper Interpretation and Use of Your Migratory Bird Report

The migratory bird list generated is not a list of all birds in your project area, only a subset of birds of priority concern. To learn more about how your list is generated, and see options for identifying what other birds may be in your project area, please see the FAQ "What does IPaC use to generate the migratory birds potentially occurring in my specified location". Please be aware this report provides the "probability of presence" of birds within the 10 km grid cell(s) that overlap your project; not your exact project footprint. On the graphs provided, please also look carefully at the survey effort (indicated by the black vertical bar) and for the existence of the "no data" indicator (a red horizontal bar). A high survey effort is the key component. If the survey effort is high, then the probability of presence score can be viewed as more dependable. In contrast, a low survey effort bar or no data bar means a lack of data and, therefore, a lack of certainty about presence of the species. This list is not perfect; it is simply a starting point for identifying what birds of concern have the potential to be in your project area, when they might be there, and if they might be breeding (which means nests might be present). The list helps you know what to look for to confirm presence, and helps guide you in knowing when to implement conservation measures to avoid or minimize potential impacts from your project activities, should presence be confirmed. To learn more about conservation measures, visit the FAQ "Tell me about conservation measures I can implement to avoid or minimize impacts to migratory birds" at the bottom of your migratory bird trust resources page.

Facilities

National Wildlife Refuge lands

Any activity proposed on lands managed by the <u>National Wildlife Refuge</u> system must undergo a 'Compatibility Determination' conducted by the Refuge. Please contact the individual Refuges to discuss any questions or concerns.

There are no refuge lands at this location.

Fish hatcheries

There are no fish hatcheries at this location.

Wetlands in the National Wetlands Inventory (NWI)

Impacts to <u>NWI wetlands</u> and other aquatic habitats may be subject to regulation under Section 404 of the Clean Water Act, or other State/Federal statutes.

For more information please contact the Regulatory Program of the local <u>U.S. Army Corps of Engineers District</u>.

This location did not intersect any wetlands mapped by NWI.

NOTE: This initial screening does **not** replace an on-site delineation to determine whether wetlands occur. Additional information on the NWI data is provided below.

Data limitations

The Service's objective of mapping wetlands and deepwater habitats is to produce reconnaissance level information on the location, type and size of these resources. The maps are prepared from the analysis of high altitude imagery. Wetlands are identified based on vegetation, visible hydrology and geography. A margin of error is inherent in the use of imagery; thus, detailed on-the-ground inspection of any particular site may result in revision of the wetland boundaries or classification established through image analysis.

The accuracy of image interpretation depends on the quality of the imagery, the experience of the image analysts, the amount and quality of the collateral data and the amount of ground truth verification work conducted. Metadata should be consulted to determine the date of the source imagery used and any mapping problems.

Wetlands or other mapped features may have changed since the date of the imagery or field work. There may be occasional differences in polygon boundaries or classifications between the information depicted on the map and the actual conditions on site.

Data exclusions

Certain wetland habitats are excluded from the National mapping program because of the limitations of aerial imagery as the primary data source used to detect wetlands. These habitats include seagrasses or submerged aquatic vegetation that are found in the intertidal and subtidal zones of estuaries and nearshore coastal waters. Some deepwater reef communities (coral or tuberficid worm reefs) have also been excluded from the inventory. These habitats, because of their depth, go undetected by aerial imagery.

Data precautions

Federal, state, and local regulatory agencies with jurisdiction over wetlands may define and describe wetlands in a different manner than that used in this inventory. There is no attempt, in either the design or products of this inventory, to define the limits of proprietary jurisdiction of any Federal, state, or local government or to establish the geographical scope of the regulatory programs of government agencies. Persons intending to engage in activities involving modifications within or adjacent to wetland areas should seek the advice of appropriate Federal, state, or local agencies concerning specified agency regulatory programs and proprietary jurisdictions that may affect such activities.

OTFOF

Attachment 10. Explosive and Flammable Hazards ASD Calculations

ID


61

608

610

2042






			Max Daily Amount/Unit	Hazardous According	ASD Calculated	Measured Distance from
Site Name	Site Address	Chemicals Onsite	(CalEPA)	to CFR	Distance (feet)	Project Site
Selman Chevrolet	1800 E CHAPMAN	Offermodis Offske	(Guill H)	10 0111	Distance (reet)	1 Toject one
oeman one note	AVE	Waste Waterborne Paint	60-119 Gallons	No		
	ORANGE CA 92867	Waste Oxygenated Solvents	12-59 Gallons	No		
		Waste Ethylene Glycol	120-599 Gallons	No		
		Waste Diethylene Glycol	60-119 Gallons	No		
		Used Paraffinic Petroleum Distillates	600-1199 Gallons	Yes	298.29	2,787.84
		Solids Containing Paraffinic Petroleum Distillates	1000-4999 Pounds	Yes	540.7	2,787.84
		Parts Washer Waste	60-119 Gallons	No		
		Paraffinic Petroleum Distillates	1200-2999 Gallons	Yes	437.03	2,787.84
		Oxygen	0-2599 Cubic Feet	No		
		Lacquer Thinner or Mineral Spirits	60-119 Gallons	No		
		Cleaners/Soaps	120-599 Gallons	No		
		Argon, Mixed with Carbon Dioxide	0-2599 Cubic Feet	No		
		Acetylene	0-2599 Cubic Feet	No		
Caltrans-Orange	691S TUSTIN ST ORANGE CA 92866	Water Base Paint	1200-2999 Gallons	No		
		Waste Petroleum Distillate	600-1199 Gallons	Yes	298.29	1,261.92
		Waste Ethylene Glycol	60-119 Gallons	No		
		Unleaded Gasoline	6000-8999 Gallons	Yes	690.74	1,261.9
		Strontium Nitrate	25000-49999 Pounds	No		
		Silica Quartz	5000-9999 Pounds	No		
		Propane	120-599 Gallons	Yes	223.4	1,261.93
		Petroleum Distillate	60-119 Gallons	Yes	113.94	1,261.9
		Petroleum Distillate	60-119 Gallons	Yes	113.94	1,261.9
		Oxygen	0-2599 Cubic Feet	No		
		Motor Oil	120-599 Gallons	Yes	223.4	1,261.9
		Modified Asphalt	10000-24999 Pounds	No		
		Limestone	5000-9999 Pounds	No		
		Ethylene Glycol	120-599 Gallons	No		
		Diphenylmethane Diisocyante	12-59 Gallons	No		
		Diesel Fuel No. 2	120-599 Gallons	Yes	223.4	1,261.9
		Diesel Fuel	6000-8999 Gallons	Yes	690.74	1,261.9
		Cement	5000-9999 Pounds	No		
		Acetylene	0-2599 Cubic Feet	No		
California Highway Patrol 675 Santa Ana Area	2031EAST SANTA CLARA AVENUE					
	SANTA ANA CA	Used Oil Filters	60-119 Gallons	Yes	113.94	4,773.1
	92705	Motor Oil	60-119 Gallons	Yes	113.94	4,773.1
		Motor Oil	120-599 Gallons	Yes	223.4	4,773.1
		Liquefied Petroleum Gas	600-1199 Gallons	Yes	298.29	4,773.1
		Gasoline	9000-11999 Gallons	Yes	778.7	4,773.1
		FUSEE TRAFFIC	1000-4999 Pounds	No		
		Ammunition	500-999 Pounds	No		

Selman Chevrolet

Chemicals: Used Paraffinic Petroleum Distillates (600-1199 gallons)



Chemicals: Solids Containing Paraffinic Petroleum Distillates (1000-4999 gallons)

Is the container above ground?	Yes: ✓ No: □
Is the container under pressure?	Yes: ☐ No: ✓
Does the container hold a cryogenic liquified gas?	Yes: No:
Is the container diked?	Yes: ☐ No: ✓
What is the volume (gal) of the container?	4999
What is the Diked Area Length (ft)?	
What is the Diked Area Width (ft)?	
Calculate Acceptable Separation Distance	
Diked Area (sqft)	
ASD for Blast Over Pressure (ASDBOP)	
ASD for Thermal Radiation for People (ASDPPU)	540.70
ASD for Thermal Radiation for Buildings (ASDBPU)	105.80
ASD for Thermal Radiation for People (ASDPNPD)	
ASD for Thermal Radiation for Buildings (ASDBNPD)	

Chemicals: Paraffinic Petroleum Distillates (2999 gallons)

Is the container above ground?	Yes: ✓ No: □
Is the container under pressure?	Yes: ☐ No: ✓
Does the container hold a cryogenic liquified gas?	Yes: No:
Is the container diked?	Yes: ☐ No: ✓
What is the volume (gal) of the container?	2999
What is the Diked Area Length (ft)?	
What is the Diked Area Width (ft)?	
Calculate Acceptable Separation Distance	
Diked Area (sqft)	
ASD for Blast Over Pressure (ASDBOP)	
ASD for Thermal Radiation for People (ASDPPU)	437.03
ASD for Thermal Radiation for Buildings (ASDBPU)	83.54
ASD for Thermal Radiation for People (ASDPNPD)	
ASD for Thermal Radiation for Buildings (ASDBNPD)	

Caltrans-Orange

Chemicals: Waste Petroleum Distillate (600-1199 gallons)

Is the container above ground?	Yes: ☑ No: □
Is the container under pressure?	Yes: ☐ No: ✓
Does the container hold a cryogenic liquified gas?	Yes: No:
Is the container diked?	Yes: ☐ No: ✓
What is the volume (gal) of the container?	1199
What is the Diked Area Length (ft)?	
What is the Diked Area Width (ft)?	
Calculate Acceptable Separation Distance	
Diked Area (sqft)	
ASD for Blast Over Pressure (ASDBOP)	
ASD for Thermal Radiation for People (ASDPPU)	298.29
ASD for Thermal Radiation for Buildings (ASDBPU)	54.68
ASD for Thermal Radiation for People (ASDPNPD)	
ASD for Thermal Radiation for Buildings (ASDBNPD)	

Chemicals: Unleaded Gasoline (6000-8999 gallons)

Is the container above ground?	Yes: ✓ No: □
Is the container under pressure?	Yes: ☐ No: ✓
Does the container hold a cryogenic liquified gas?	Yes: No:
Is the container diked?	Yes: ☐ No: ✓
What is the volume (gal) of the container?	8999
What is the Diked Area Length (ft)?	
What is the Diked Area Width (ft)?	
Calculate Acceptable Separation Distance	
Diked Area (sqft)	
ASD for Blast Over Pressure (ASDBOP)	
ASD for Thermal Radiation for People (ASDPPU)	690.74
ASD for Thermal Radiation for Buildings (ASDBPU)	138.84
ASD for Thermal Radiation for People (ASDPNPD)	
ASD for Thermal Radiation for Buildings (ASDBNPD)	

Chemicals: Propane (120-599 gallons)

Is the container above ground?	Yes: ✓ No: □
Is the container under pressure?	Yes: ☐ No: ✓
Does the container hold a cryogenic liquified gas?	Yes: No:
Is the container diked?	Yes: □ No: ☑
What is the volume (gal) of the container?	599
What is the Diked Area Length (ft)?	
What is the Diked Area Width (ft)?	
Calculate Acceptable Separation Distance	
Diked Area (sqft)	
ASD for Blast Over Pressure (ASDBOP)	
ASD for Thermal Radiation for People (ASDPPU)	223.40
ASD for Thermal Radiation for Buildings (ASDBPU)	39.67
ASD for Thermal Radiation for People (ASDPNPD)	
ASD for Thermal Radiation for Buildings (ASDBNPD)	

Chemicals: Propane Distillate (60-119 gallons)

Is the container above ground?	Yes: ✓ No: □
Is the container under pressure?	Yes: ☐ No: ☑
Does the container hold a cryogenic liquified gas?	Yes: □ No: □
Is the container diked?	Yes: ☐ No: ✓
What is the volume (gal) of the container?	119
What is the Diked Area Length (ft)?	
What is the Diked Area Width (ft)?	
Calculate Acceptable Separation Distance	
Diked Area (sqft)	
ASD for Blast Over Pressure (ASDBOP)	
ASD for Thermal Radiation for People (ASDPPU)	113.94
ASD for Thermal Radiation for Buildings (ASDBPU)	18.79
ASD for Thermal Radiation for People (ASDPNPD)	
ASD for Thermal Radiation for Buildings (ASDBNPD)	

Chemicals: Motor Oil (120-599 gallons)

Is the container above ground?	Yes: ☑ No: □
Is the container under pressure?	Yes: ☐ No: ✓
Does the container hold a cryogenic liquified gas?	Yes: No:
Is the container diked?	Yes: ☐ No: ✓
What is the volume (gal) of the container?	599
What is the Diked Area Length (ft)?	
What is the Diked Area Width (ft)?	
Calculate Acceptable Separation Distance	
Diked Area (sqft)	
ASD for Blast Over Pressure (ASDBOP)	
ASD for Thermal Radiation for People (ASDPPU)	223.40
ASD for Thermal Radiation for Buildings (ASDBPU)	39.67
ASD for Thermal Radiation for People (ASDPNPD)	

Chemicals: Diesel Fuel No.2 (120-599 gallons)

Is the container above ground?	Yes: ☑ No: □
Is the container under pressure?	Yes: ☐ No: ✓
Does the container hold a cryogenic liquified gas?	Yes: ☐ No: ☐
Is the container diked?	Yes: ☐ No: ✓
What is the volume (gal) of the container?	599
What is the Diked Area Length (ft)?	
What is the Diked Area Width (ft)?	
Calculate Acceptable Separation Distance	
Diked Area (sqft)	
ASD for Blast Over Pressure (ASDBOP)	
ASD for Thermal Radiation for People (ASDPPU)	223.40
ASD for Thermal Radiation for Buildings (ASDBPU)	39.67
ASD for Thermal Radiation for People (ASDPNPD)	
ASD for Thermal Radiation for Buildings (ASDBNPD)	

Chemicals: Diesel Fuel (6000-8999 gallons)

Is the container above ground?	Yes: ✓ No: □
Is the container under pressure?	Yes: ☐ No: ☑
Does the container hold a cryogenic liquified gas?	Yes: No:
Is the container diked?	Yes: ☐ No: ☑
What is the volume (gal) of the container?	8999
What is the Diked Area Length (ft)?	
What is the Diked Area Width (ft)?	
Calculate Acceptable Separation Distance	
Diked Area (sqft)	
ASD for Blast Over Pressure (ASDBOP)	
ASD for Thermal Radiation for People (ASDPPU)	690.74
ASD for Thermal Radiation for Buildings (ASDBPU)	138.84
ASD for Thermal Radiation for People (ASDPNPD)	
ASD for Thermal Radiation for Buildings (ASDBNPD)	

California Highway Patrol 675 Santa Ana Area

Chemical: Used Oil Filters (60-119 gallons)

Is the container above ground?	Yes: ☑ No: □
Is the container under pressure?	Yes: ☐ No: ✓
Does the container hold a cryogenic liquified gas?	Yes: ☐ No: ☐
Is the container diked?	Yes: ☐ No: ✓
What is the volume (gal) of the container?	119
What is the Diked Area Length (ft)?	
What is the Diked Area Width (ft)?	
Calculate Acceptable Separation Distance	
Diked Area (sqft)	
ASD for Blast Over Pressure (ASDBOP)	
ASD for Thermal Radiation for People (ASDPPU)	113.94
ASD for Thermal Radiation for Buildings (ASDBPU)	18.79
ASD for Thermal Radiation for People (ASDPNPD)	
ASD for Thermal Radiation for Buildings (ASDBNPD)	

Chemical: Motor Oil (60-119 gallons)

Is the container above ground?	Yes: ✓ No: □
Is the container under pressure?	Yes: ☐ No: ✓
Does the container hold a cryogenic liquified gas?	Yes: ☐ No: ☐
Is the container diked?	Yes: ☐ No: ✓
What is the volume (gal) of the container?	119
What is the Diked Area Length (ft)?	
What is the Diked Area Width (ft)?	
Calculate Acceptable Separation Distance	
Diked Area (sqft)	
ASD for Blast Over Pressure (ASDBOP)	
ASD for Thermal Radiation for People (ASDPPU)	113.94
ASD for Thermal Radiation for Buildings (ASDBPU)	18.79
ASD for Thermal Radiation for People (ASDPNPD)	
ASD for Thermal Radiation for Buildings (ASDBNPD)	

Chemicals: Motor Oil (120-599 gallons)

Is the container above ground?	Yes: ☑ No: □
Is the container under pressure?	Yes: ☐ No: ✓
Does the container hold a cryogenic liquified gas?	Yes: ☐ No: ☐
Is the container diked?	Yes: ☐ No: ✓
What is the volume (gal) of the container?	599
What is the Diked Area Length (ft)?	
What is the Diked Area Width (ft)?	
Calculate Acceptable Separation Distance	
Diked Area (sqft)	
ASD for Blast Over Pressure (ASDBOP)	
ASD for Thermal Radiation for People (ASDPPU)	223.40
ASD for Thermal Radiation for Buildings (ASDBPU)	39.67
ASD for Thermal Radiation for People (ASDPNPD)	
ASD for Thermal Radiation for Buildings (ASDBNPD)	

Is the container above ground?	Yes: ☑ No: □
Is the container under pressure?	Yes: ☐ No: ✓
Does the container hold a cryogenic liquified gas?	Yes: No:
Is the container diked?	Yes: ☐ No: ✓
What is the volume (gal) of the container?	1199
What is the Diked Area Length (ft)?	
What is the Diked Area Width (ft)?	
Calculate Acceptable Separation Distance	
Diked Area (sqft)	
ASD for Blast Over Pressure (ASDBOP)	
ASD for Thermal Radiation for People (ASDPPU)	298.29
ASD for Thermal Radiation for Buildings (ASDBPU)	54.68
ASD for Thermal Radiation for People (ASDPNPD)	
ASD for Thermal Radiation for Buildings (ASDBNPD)	

Gasoline (9000-11999 gallons)

Is the container above ground?	Yes: ✓ No: □
Is the container under pressure?	Yes: ☐ No: <
Does the container hold a cryogenic liquified gas?	Yes: No:
Is the container diked?	Yes: ☐ No: ☑
What is the volume (gal) of the container?	11999
What is the Diked Area Length (ft)?	
What is the Diked Area Width (ft)?	
Calculate Acceptable Separation Distance	
Diked Area (sqft)	
ASD for Blast Over Pressure (ASDBOP)	
ASD for Thermal Radiation for People (ASDPPU)	778.70
ASD for Thermal Radiation for Buildings (ASDBPU)	158.59
ASD for Thermal Radiation for People (ASDPNPD)	
ASD for Thermal Radiation for Buildings (ASDBNPD)	

Attachment 11. California Important Farmland Finder











1800 E La Veta Ave, Orange, CA X


Show search results for 1800 E La Vet...


















Other Land











Attachment 12. Orange County SHPO Consultation Letter



DYLAN WRIGHT
DIRECTOR
OC COMMUNITY RESOURCES

CYMANTHA ATKINSON
ASSISTANT DIRECTOR
OC COMMUNITY RESOURCES

JOANNE VEEDOR
DIRECTOR
ADMINISTRATIVE SERVICES

MONICA SCHMIDT INTERIM DIRECTOR OC ANIMAL CARE

JULIA BIDWELL
DIRECTOR
OC HOUSING & COMMUNITY
DEVELOPMENT

RENEE RAMIREZ
DIRECTOR
OC COMMUNITY SERVICES

PAMELA PASSOW DIRECTOR OC PARKS

JULIE QUILLMAN
COUNTY LIBRARIAN
OC PUBLIC LIBRARIES



February 13, 2024

Via Email: calshpo.hud@parks.ca.gov and susan.negrete@parks.ca.gov

California Department of Parks and Recreation Office of Historic Preservation 1725 23rd St., Suite 100 Sacramento, CA 95816

Request for SHPO Concurrence: The Orion Project, 1800 E. La Veta Avenue, City of Orange, Orange County, California

To Whom it May Concern,

In accordance with Section 106 of the National Historic Preservation Act (NHPA) of 1966 as amended (16 U.S.C 470f), and as required by the U.S. Department of Housing and Urban Development (HUD), we are requesting your review and comments on the determination of no effect that Project implementation would have on historic properties within the Project Area of Potential Effects (APE) for the Orion Project (Project).

The Orion Project 1800 E. La Veta Avenue City of Orange, Orange County, California

Project Objective

The proposed Project (Project) includes the redevelopment of the existing campus for the Rehabilitation Institute of Southern California located at 1800 E. La Veta, in the City of Orange, Orange County, California. The redevelopment will include 166 affordable senior apartment units on 3.85-acres. The community consists of two 4-story elevator served buildings and one 2-4-story elevator served building with surface parking (Exhibit 4.02).

Area of Potential effects (APE)

The Area of potential effects (APE) for the Project includes the APE for direct effects (direct APE) which encompasses 3.85-acres and is located at 1800 East La Veta Avenue, in the City of Orange and is bound by East La Veta Avenue to the north, South Tustin Street to the west, and East Fairway Drive to the south and east. The direct APE encompasses Accessors Parcel Number (APN) 390-322-15. The direct APE falls within Township 4 South and Range 9 West of the *Orange, California* U.S Geological Survey (USGS) 7.5-minute Series Quadrangle Map. The direct APE includes areas of potential ground disturbances and where the project will be altered. Ground disturbance would encompass the entire 3.85-acre direct APE,



1501 E. ST. ANDREW PLACE, 1ST FLOOR SANTA ANA, CA 92705 PHONE: 714.480.6534 FAX: 714.480.2978 represented as the maximum depth of excavation, will be approximately 18 feet below the existing ground surface (Exhibit 4.25).

The APE also includes the APE for indirect effects (indirect APE) which is defined by the area in which there is potential for the proposed Project to have an adverse effect on historic properties. The indirect APE encompasses 15.7-acres which includes the addition of one parcel in all directions of the undertaking.

Historic Property Identification Effort

Orange County Housing & Community Development staff reviewed the cultural resource documents prepared by Architectural Resources Group (2020), ASM Affiliates (Andrews 2021), and Kleinfelder (Neals and Castells 2023).

Architectural Resources Group staff consulted archives and repositories as part of their research methodologies for this assessment including Orange County Public Library; Orange County Assessor; Orange County Archives; newspapers.com and California Digital Newspaper Collection databases; historic aerials accessed online through historicaerials.com and UCSB Frame Finder; and Architectural Resources Group in-house library collection.

ASM Affiliates did not evaluate built environmental resources during the cultural resources study in 2021.

To comply with Section 800.4(b) for the Project, the tasks listed below were also completed:

- On October 16, 2020, Architectural Resources Group staff conducted a site visit of the direct APE and identified two historic-era properties.
- On November 5, 2020, Architectural Resources Group conducted built environment evaluations recommending 1800 E. La Veta Avenue, 585 S. Tustin Street, ineligible for listing on the National Register of Historic Places (NRHP) and the California Register of Historical Resources (CRHR).
- On November 1, 2021, ASM Affiliates conducted background research indicating past disturbances within the direct APE.
- On November 3, 2021, ASM Affiliates conducted a records search at the SCCIC. The results indicated that no previously recorded cultural resources are within the direct APE.
- On November 31, 2021, ASM Affiliates conducted a negative archaeological resources pedestrian survey of the direct APE.
- On March 9, 2023, Kleinfelder conducted a review of the APE for indirect effects. The indirect APE includes the addition of one parcel in all directions of the undertaking. During the site visit, two historic-era properties were identified within the indirect APE.
- In April 2023, Kleinfelder conducted built environment evaluations recommending the Castilian Park Apartments (1622 and 1625 East Fairway Drive) and the Fairway Park Apartments (1844 E. Fairway Drive) ineligible for listing on the NRHP and the CRHR.

Native American Correspondence and Participation

ASM Affiliates contacted the Native American Heritage Commission (NAHC) to request a search of the Sacred Lands Files on October 31, 2021. The NAHC responded on November 17, 2023, with positive results and recommended that the Juaneño Band of Mission Indians Acjachemen Nation – Belardes be contacted for more information. Additionally, the NAHC provided a contact list of 17 Native American representatives who may have more information

about the cultural resources within the APE. Outreach letters were sent to the contacts identified by the NAHC, and one response was received. The Gabrieleño Band of Mission Indians - Kizh Nation responded on November 30, 2021, stating that the area is very important to their community and requested the lead agency's contact information (Andrews 2021). To date, no additional Native American correspondence or outreach has been conducted by Orange County.

South Central Coastal Information Center Records Search Results

ASM Affiliates conducted a records search at the California Historic Resources Information System (CHRIS) SCCIC on November 3, 2021, for the Project. The records search indicated that 22 previous cultural resources studies were conducted within one mile of the direct APE, none of which intersect the direct APE. Additionally, the records search identified 16 previously recorded cultural resources within one mile of the direct APE, none of which intersect the direct APE. The large majority (14) of these resources are historic era-built environment resources associated with the historical development of Orange County over the 20th Century. The remaining (2) previously recorded resources are prehistoric isolates (Andrews 2021).

Archival Research

In addition to the SCCIC records search, ASM Affiliates conducted an online review of historic aerial imagery (historic aerials) and historic topographic maps of the direct APE (NETR 2021). Historic aerial photographs of the APE are available from 1946 and 2018. Historic topographic maps of the APE are available from 1896 and 2018. The earliest topographic map from 1932 reveals a single structure along the southwestern portion of the parcel near S. Tustin Street and E. Fairway Drive. The earliest aerial image from 1946 shows the entire parcel utilized for agriculture. Overall, it appears that the entire APE has been subject to past disturbances associated with the development of several structures and associated infrastructure over the past century (NETR 2021).

Description of Findings

Architectural Resources Group conducted an historic resources assessment of the direct APE in 2020. The assessment included a search of California's Built Environment Resource Directory and Historic Resources Inventory and a built environment site visit. The study identified and evaluated two historic-era properties built between 1960 and 1987 within the direct APE. These properties include a single-family residence (585 S. Tustin Street) and a rehabilitation center (1800 E. La Veta Avenue). Both resources were evaluated and recommended ineligible for inclusion in the NRHP and the CRHR (Architectural Resources Group 2020).

ASM Affiliates conducted a cultural resources study of the direct APE in 2021. The study included a Native American Heritage Commission (NAHC) Sacred Lands File (SLF) search, a records search at the South-Central Coastal Information Center (SCCIC), a review of historic aerial and topographic imagery, and a pedestrian survey. These cultural resources study did not identify any archaeological resources within the direct APE. No built environmental resources were evaluated (Andrews 2021).

In 2023, Kleinfelder conducted a review of the proposed Project for indirect effects, extending the APE to include an indirect APE that consisted of one parcel in all directions of the undertaking. Two additional historic-era properties were identified. These include the Castilian Park Apartments (1622 and 1625 East Fairway Drive) and the Fairway Park Apartments (1844).

E. Fairway Drive). Both resources were evaluated and recommended ineligible for inclusion in the NRHP and the CRHR (Neals and Castells 2023).

Effects Determination

Orange County Housing & Community Development reviewed the documentation for the Project and the potential for Project implementation to affect historic properties within the APE and determined that no historic properties will be affected in the APE for the subject undertaking.

Therefore, Orange County Housing & Community Development has reached a determination of "No Historic Properties Affected" by the project. Pursuant to 36 CFR Part 800, regulations implementing Section 106, we are requesting your concurrence on our determination of "No Historic Properties Affected."

We kindly request review and comments on our determination of no historic properties affected. Please provide us with your response on or before 30 days of receipt of this letter. To assist in your review, included in this packet is the referenced cultural resources studies (with confidential SCCIC records search results and DPR 523 Forms) prepared by Architectural Resources Group (2020), Sherri Andrews of ASM Affiliates (2021), and Jessica Neals and Justin Castells of Kleinfelder (2023). Also included in this packet are the undertaking descriptions, photographs, and maps for the proposed Project. Should you need further information, please contact me via email at Suzanne.harder@occr.ocgov.com.

Sincerely,

Sue Harder

Cura Handan Cananawaita Davi

Sue Harder, Community Development Compliance and Environmental Coordinator Orange County Housing & Community Development

Description of Undertaking

Address: 1800 E. La Veta Avenue

City of Orange, California 92866

Census Tract: 4004

APNs: 390-322-15

Agency Official Determination:

Based on our review, it is our determination that no historic properties or archaeological resources will be affected by this Project. We base these findings on:

- On October 16, 2020, Architectural Resources Group staff conducted a site visit of the direct APE and identified two historic-era properties.
- On November 5, 2020, Architectural Resources Group conducted built environment evaluations recommending 1800 E. La Veta Avenue, 585 S. Tustin Street, ineligible for listing on the National Register of Historic Places (NRHP) and the California Register of Historical Resources (CRHR).
- On November 1, 2021, ASM Affiliates conducted background research indicating past disturbances within the direct APE.
- On November 3, 2021, ASM Affiliates conducted a records search at the SCCIC. The results indicated that no previously recorded cultural resources are within the direct APE.
- On November 31, 2021, ASM Affiliates conducted a negative archaeological resources pedestrian survey of the direct APE.
- On March 9, 2023, Kleinfelder conducted a review of the APE for indirect effects. The indirect APE includes the addition of one parcel in all directions of the undertaking. During the site visit, two historic-era properties were identified within the indirect APE.
- In April 2023, Kleinfelder conducted built environment evaluations recommending the Castilian Park Apartments (1622 and 1625 East Fairway Drive) and the Fairway Park Apartments (1844 E. Fairway Drive) ineligible for listing on the NRHP and the CRHR.

Project Description:

The proposed Project includes the redevelopment of 1800 E. La Veta, the existing campus for the Rehabilitation Institute of Southern California. The redevelopment will include 166 affordable senior apartment units on 3.85-acres.

Site Information:

- **Zoning Designation:** Residential Multi-family (R-3)
- **General Plan Land Use Designation:** Residential Multi-family (R-3)
- Existing Use: Vacant
- **Prior Use(s)/Development(s):** Residential and commercial

Existing Conditions and Trends: The property is currently developed and includes a main building (1800 E. La Veta Avenue) formerly used as a rehabilitation center. The additional structure previously recorded on the property (585 S. Tustin Street) was recently demolished due to a fire. The rest of the property is occupied by landscape, hardscape, and surface parking that serves the rehabilitation center. The property is bounded by E. La Veta Avenue to the north, E. Fairway Drive to the south, and S. Tustin Street to the west, and multifamily housing to the east. It is bordered on the south by commercial and residential development and the north, east, and west by residential development.

References

Andrews, Sherri. 2021. Cultural Resources Assessment Findings Memo for the 1800 East La Veta Avenue Project, Orange, Orange County, California. On file with ASM Affiliates.

Architectural Resources Group. 2020. Historic Resources Assessment for the 1800 E. La Veta Avenue/585 S. Tustin Street, City of Orange, California. On file with Architectural Resources Group.

Neals, Jessica and Justin Castells. 2023. Cultural Resources Technical Report for the East La Veta Avenue Senior Apartment Community Project, Orange County, California. On file with Kleinfelder.

NETR (Nationwide Environmental Title Research LLC). 2021. Address search for 1800 La Veta Avenue City of Orange, California. Accessed 2021. http://www.historicaerials.com/

Suzanne Harder		
	2/13/24	
Suzanne Harder, County of Orange	Date	

Attachment 13. SHPO Response



DYLAN WRIGHT
DIRECTOR
OC COMMUNITY RESOURCES

CYMANTHA ATKINSON ASSISTANT DIRECTOR OC COMMUNITY RESOURCES

JOANNE VEEDOR DIRECTOR ADMINISTRATIVE SERVICES

MONICA SCHMIDT INTERIM DIRECTOR OC ANIMAL CARE

JULIA BIDWELL
DIRECTOR
OC HOUSING & COMMUNITY
DEVELOPMENT

RENEE RAMIREZ
DIRECTOR
OC COMMUNITY SERVICES

PAMELA PASSOW DIRECTOR OC PARKS

JULIE QUILLMAN
COUNTY LIBRARIAN
OC PUBLIC LIBRARIES

CCCommunity Resources

Note to File-The Orion New Affordable Housing Complex

A request for Concurrence from CalSHPO was emailed on 2/14/24, as of 3/15/24 no response has been received.

Since CalSHPO did not respond within the 30 day time period, the County will proceed with completion of the Environmental Assessment.

Craig Fee	3/19/24
Signature	Date

Enclosures: (optional)

OC HOUSING & COMMUNITY DEVELOPMENT 1501 E. ST. ANDREW PLACE, $\mathbf{1}^{\text{ST}}$ FLOOR

SANTA ANA, CA 92705 PHONE: 714.480.6534 FAX: 714.480.2978

Attachment 14. Noise Memorandum



MEMORANDUM

To: Kristin Arakawa, Dudek
From: Mike Greene, Dudek

Subject: The Orion Apartments HUD EA Noise Assessment

Date: 02/22/2024

cc: Jonathan Rigg, Dudek

Attachment(s): Figure 1, Project Location

Figure 2, Noise Model Receiver Locations

Attachment A; Traffic Noise Model Input/Output Data

This technical noise memo summarizes the results of the noise analysis conducted for onsite uses of The Orion Apartments Project; Orange County Public Works On-Call Master Services Agreement Contract MA-080-21010547 Project in the City of Orange, California.

1 Background

1.1 Project Description

The proposed project would involve the construction of a new apartment community consisting of 166 affordable senior apartment units on the 3.85 gross acre (3.85 net acres) site located at 1800 E. La Veta Avenue in the city of Orange, Ca. The community consists of two 4-story elevator served buildings and one 2-4-story elevator served building with surface parking. The proposed total gross building area is approximately 145,716 SF, including apartments and resident-serving amenity uses, and common area.

The community will be restricted to seniors age 62+ with unit sizes range between 537 square feet (sf) to 700 net sf and include 111 one-bedroom units and 55 two-bedroom units (166 units total). The site is bounded by E. La Veta Avenue to the north, E. Fairway Drive to the south, S. Tustin Street to the west, and multi-family housing to the east.

1.2 Noise Fundamentals and Terminology

Vibrations, traveling as waves through air from a source, exert a force perceived by the human ear as sound. Sound pressure level (referred to as sound level) is measured on a logarithmic scale in decibels (dB) that represent the fluctuation of air pressure above and below atmospheric pressure. Frequency, or pitch, is a physical characteristic of sound and is expressed in units of cycles per second or hertz (Hz). The normal frequency range of hearing for most people extends from about 20 to 20,000 Hz. The human ear is more sensitive to middle and high frequencies, especially when the noise levels are quieter. As noise levels get



louder, the human ear starts to hear the frequency spectrum more evenly. To accommodate for this phenomenon, a weighting system to evaluate how loud a noise level is to a human was developed. The frequency weighting called "A" weighting is typically used for quieter noise levels, which de-emphasizes the low-frequency components of the sound in a manner similar to the response of a human ear. This A-weighted sound level is called the "noise level" and is referenced in units of dBA.

Because sound is measured on a logarithmic scale, a doubling of sound energy results in a 3 dBA increase in the noise level. Changes in a community noise level of less than 3 dB are not typically noticed by the human ear (Caltrans 2013). Changes from 3 to 5 dB may be noticed by some individuals who are extremely sensitive to changes in noise. A 5 dB increase is readily noticeable. The human ear perceives a 10 dB increase in sound level as a doubling of the sound level (i.e., 65 dBA sounds twice as loud as 55 dBA to a human ear).

An individual's noise exposure occurs over a period of time; however, noise level is a measure of noise at a given instant in time. The equivalent continuous sound level (L_{eq}), also referred to as the average sound level, is a single number representing the fluctuating sound level in A-weighted decibels (dBA) over a specified period of time. It is a sound-energy average of the fluctuating level and is equal to a constant unchanging sound of that dB level. Community noise sources vary continuously, being the product of many noise sources at various distances, all of which constitute a relatively stable background or ambient noise environment.

Noise levels are generally higher during the daytime and early evening when traffic (including airplanes), commercial, and industrial activity is the greatest. However, noise sources experienced during nighttime hours when background levels are generally lower can be potentially more conspicuous and irritating to the receiver. In order to evaluate noise in a way that considers periodic fluctuations experienced throughout the day and night, a concept termed "community noise equivalent level" (CNEL) was developed, The CNEL scale represents a time-weighted 24-hour average noise level based on the A-weighted sound level. CNEL accounts for the increased noise sensitivity during the evening hours (7 p.m. to 10 p.m.) and nighttime hours (10 p.m. to 7 a.m.) by adding 5 dB to the average sound levels occurring during the evening hours and 10 dB to the sound levels occurring during nighttime hours. Additional noise definitions are provided below.

Ambient Noise Level. The composite of noise from all sources near and far. The normal or existing level of environmental noise at a given location.

A-Weighted Sound Level (dBA). The sound pressure level in decibels as measured on a sound level meter using the A-weighted filter network. The A-weighting filter deemphasizes the very low and very high frequency components of the sound in a manner similar to the frequency response of the human ear and correlates well with community equivalent sound level.

Community Noise Equivalent Level (CNEL). CNEL is the A-weighted equivalent continuous sound exposure level for a 24-hour period with a 10 dB adjustment added to sound levels occurring during the nighttime hours (10 p.m.–7 a.m.) and 5 dB added to the sound during the evening hours (7 p.m.–10 p.m.).



Day Night Average Sound Level (DNL or L_{dn}). Similar to the CNEL noise metric, except that no penalty is added during the evening hours (7 p.m.-10 p.m.). Typically, the CNEL and L_{dn} noise metrics vary by approximately 1 decibel or less and are often considered to be functionally equivalent.

Decibel (dB). The decibel is a unit for measuring sound pressure level and is equal to 10 times the logarithm to the base 10 of the ratio of the measured sound pressure squared to a reference pressure, which is 20 micropascals.

2 Noise Analysis Methodology

2.1 Applicable Noise Standards

Because the proposed project may receive funding from the U.S. Department of Housing and Urban Development (HUD), the noise standards specified by HUD were used for this analysis. HUD's noise standards may be found in 24 CFR Part 51, Subpart B (CFR 2013). Exterior uses with a day night average sound level (DNL) of 65 dBA or less are considered normally acceptable. Sites at which the environmental or community noise exposure exceeds 65 decibels DNL are considered noise-impacted areas. For new construction proposed in high noise areas, grantees shall incorporate noise attenuation features to the extent required by HUD environmental criteria and standards contained in Subpart B (Noise Abatement and Control) of 24 CFR Part 51.

The "Normally Unacceptable" noise zone includes community noise levels from above 65 decibels to 75 decibels. Approvals in this noise zone require a minimum of 5 dB additional sound attenuation for buildings having noise-sensitive uses if the day-night average sound level is greater than 65 dBA but does not exceed 70 dBA, or a minimum of 10 decibels of additional sound attenuation if the day-night average sound level is greater than 70 dBA but does not exceed 75 dBA.

The interior noise standard is 45 dBA DNL.

2.2 Preliminary Noise Modeling

The primary noise source in the project vicinity is motor vehicle traffic. The eastern façades of the proposed residential units would face the southbound lanes of the SR-55 freeway, while the southern façades face the SR-22 freeway. Both the eastern and the southern facades are separated from these two freeways by several rows of residential homes and an existing noise barrier (i.e., a soundwall) approximately 14 feet in height constructed at the Caltrans right-of-way (ROW). In addition, the northern façades of the proposed residential units face La Veta Avenue and the western facades face South Tustin Street. The other nearby roads are minor "feeder" streets which would have a negligible contribution to the on-site noise environment. The nearest active rail line is located approximately 1.25 miles away and the nearest airport, Santa Ana/John Wayne Airport, is located approximately 6.8 miles away. Based upon the Airport Environs Land Use Plan for John Wayne Airport (AELUP 2008), the airport's 60 dB CNEL noise contour is located approximately 4.7 miles from the project site. Thus, noise from the airport would have a negligible contribution to the on-site noise environment.



An initial noise analysis of traffic noise from the SR-55, the SR-22, La Veta Avenue and South Tustin Street carried out using HUD's DNL Calculator¹ indicated that worst-case exterior building façade noise levels would be approximately 73 dBA DNL. However, because the DNL Calculator does not account for site conditions such as the intervening building rows and the existing freeway soundwall, in addition to the proposed upper-floor residential units, this modeled noise level was determined to likely be an overestimate and a more detailed traffic noise model was used.

2.3 Detailed Noise Modeling

The proposed project site has several receiver locations of interest including multiple building exposures (i.e., rooms with exterior windows and doors facing north, south, east and west each four (4) stories high, with varying traffic noise exposures. Common use outdoor amenities areas are proposed as part of this projectat varying locations throughout the project site, each with differing exposures to the nearby major roadways. Because of these factors, it was determined that the Federal Highway Administration's (FHWA) Traffic Noise Model (TNM) version 2.5 (FHWA 2004) would be ideal for a more detailed analysis. The TNM traffic noise prediction model calculates the noise levels based on specific information including traffic volumes, vehicle fleet mix, speed limits, roadway geometrics, receiver elevations, intervening structures and lateral distances between the noise receivers and the roadways.

Project site, surrounding structures and roadway geometry were input using aerial photography information upon which the project's site plan was overlain; this was subsequently digitized into the TNM model.

Modeled receiver locations (shown in Figure 2) consisted of the following:

- Proposed building façade exteriors with windows and doors perpendicular to and facing SR-55, SR-22. La Veta Avenue and Tustin Street
- Outdoor amenity areas (specifically the central courtyard; the community garden near the southwest corner of the project site; the entertainment courtyard along the east side of Building 3; and the onsite dog park.

In order to accurately estimate the project site's noise levels in terms of the 24-hour weighted DNL noise metric, the TNM model was run for three 1-hour traffic volume cases: AM/PM peak-hour (assumed to be approximately 10% of the roadways' Average Daily Traffic (ADT); off-peak daytime (assumed to be approximately 6% of ADT), and nighttime volumes (assumed to be approximately 15% of ADT over the 9-hour period from 10 PM to 7 AM, per HUD noise modeling guidance) The 15% of ADT was then divided by 9, to arrive at the hourly average level suitable for input into TNM. The resultant traffic noise levels for each of these cases was then averaged in the energy (i.e., the logarithmic) domain after applying the 10-decibel noise "penalty" to the nighttime noise levels.

ADT volumes and truck mix percentages used for the analysis for the freeways were from the Caltrans Traffic Operations Census Website (Caltrans 2024). The most recent traffic volume forecast available (Year 2021) was used as the basis to estimate future traffic volumes (10 years out from the Year 2025, the assumed year of occupancy). This was accomplished using an assumed increase rate of 1% per year. Thus,

¹ https://www.hudexchange.info/programs/environmental-review/dnl-calculator/



13230.50

for example, the Year 2021 forecast average daily traffic volume of 215,000 for the relevant segment of SR-55 was calculated to be 247137 by Year 2035. The modeled ADTs are shown in Table 1 below. Modeled traffic speeds were used based upon the posted roadway speed limits using Google Earth Street View.

Table 1 - Modeled Traffic Volumes				
Modeled Roadway	Average Daily Traffic (ADT) Volume (Year 2035)			
SR-55	247,137			
SR-22	160,926			
South Tustin Street	29,297			
La Veta Avenue	10,141			

Source: Caltrans (SR-55 and SR-22) and OCTA volumes, adjusted to Year 2035.

3 Traffic Noise Analysis Results

The results of the traffic noise analysis for the modeled on-site receivers (shown in Figure 2) are summarized in Table 2. The modeled input and output data are provided in Attachment A. As shown in Table 2, the highest noise levels would occur at receivers M6 and M7, which is representative of the habitable rooms in Building 3 facing west, and closest to the SR-22 freeway and South Tustin Street. At receivers M6 and M7, the traffic noise levels at the building façade are predicted to range from 70 to 71 dBA DNL. Thus, the exposure from traffic noise would exceed the HUD exterior noise standard of 65 dBA DNL by up to 6 dB at the façade of units nearest these roadways, putting these receivers in the "normally unacceptable" noise range. The noise levels at the other modeled building facade receivers (except for M10) would also exceed the HUD exterior noise standard of 65 dBA DNL to varying degrees. At the modeled outdoor use areas (M11 through M14), the modeled traffic noise levels would not exceed the HUD exterior noise standard of 65 dBA DNL.

Table 2 – Traffic Noise Level Results Summary (DNL (dBA))				
Receiver #	1st-Floor	2nd-Floor	3rd-Floor	4th-Floor
M1 - Building 1, northeast corner	65	67	67	68
M2 - Building 1, southeast corner	60	64	66	67
M3 - Building 2, eastern façade	60	65	67	68
M4 - Building 2, southeast corner	61	66	67	68
M5 - Building 3, southeast corner	63	65	66	67
M6 - Building 3, southwest corner	70	71	70	70



FEBRUARY 2024

M7 - Building 3, northwest corner	71	70	70	70
M8 - Building 3, northern corner	66	67	67	66
M9 - Building 2, northeast corner	60	64	65	67
M10 - Building 1, northern façade	64	65	64	65
M11 - Central courtyard	60	n/a	n/a	n/a
M12 - Community garden	61	n/a	n/a	n/a
M13 - Entertainment courtyard	59	n/a	n/a	n/a
M14 - Dog park	65	n/a	n/a	n/a

Source: Attachment A.

Note: Bolded numbers indicate that the noise levels exceed the HUD noise standard of 65 dBA DNL.

As detailed in Section 2.1, 24 CFR Part 51, Subpart B states that sites at which environmental or community noise exposure exceeds the day night average sound level (DNL) of 65 dBA are considered to be noise-impacted. For new construction proposed in high noise areas, grantees shall incorporate noise attenuation features to the extent required. Approvals in the "normally unacceptable" noise zone require a minimum of 5 dB additional sound attenuation for buildings having noise-sensitive uses if the day-night average sound level is greater than 65 dBA but does not exceed 70 dBA, or a minimum of 10 decibels of additional sound attenuation if the day-night average sound level is greater than 70 dBA but does not exceed 75 dBA.

Typical new construction of multi-family homes with windows closed provides a minimum of 25 dB exterior to interior noise reduction. All residential units will be equipped with a forced air heating ventilation air conditioning (HVAC) unit that allows for a "windows closed" condition (i.e., windows do not need to be left open for ventilation). As such, the interiors of the proposed habitable rooms with doors or windows facing west, toward South Tustin Street and SR-22 are anticipated to have noise levels of approximately 46 dBA DNL (i.e. 71 dBA exterior – 25 dBA attenuation = 46 dBA interior). The interiors of the other modeled receivers are anticipated to have noise levels of 43 dBA DNL (i.e. 68 dBA exterior – 25 dBA attenuation = 43 dBA interior) or less. Nonetheless, in order to ensure compliance with 24 CFR Part 51, Subpart B and that the HUD noise standard of 45 dBA DNL is not exceeded, the detailed architectural design plans (when these are prepared) shall provide the following specification for upgraded windows:

- All windows and exterior doors in the east-facing residential units on floors 2-4 of Building 1 shall have a Sound Transmission Class (STC) rating of 30 or greater.
- All windows and exterior doors in the south- and east-facing residential units on floors 2-4 of Building 2 shall have a Sound Transmission Class (STC) rating of 30 or greater.
- All windows and exterior doors in the west-facing residential units on floors 1-4 of Building 3 shall have a Sound Transmission Class (STC) rating of 35 or greater.
- All windows and exterior doors in the north- and south-facing residential units on floors 1-4 of Building 3 shall have a Sound Transmission Class (STC) rating of 30 or greater.

Please see Table 3. With implementation of this requirement the proposed project would not exceed the HUD interior noise standard of 45 dBA DNL and would be within the "normally acceptable" noise range for



interior noise. Additionally, as shown in Table 2, the outdoor amenity areas (as represented by receivers M11 – M14) would not exceed the permitted exterior noise standard of 65 dBA DNL, and thus would be in the "normally acceptable" category as proposed.

	Table 3. Interior Noise Levels (DNL (dBA))					
Receivers / Location	Maximum Noise Level at Façade ¹	Required Interior Noise Reduction ²	Minimum Anticipated Interior Noise Reduction ³	Upgraded Windows? ⁴	Interior Noise Level ⁵	Exceedance of Interior Noise Standard?
M1 (Building 1), floors 2 - 4	68	23	29	Yes	39	No
M2 (Building 1), floors 3 - 4	67	22	29	Yes	38	No
M3 and M4 (Building 2), floors 3 - 4	68	23	29	Yes	39	No
M5 (Building 3), floors 2 - 4	67	22	29	Yes	38	No
M6 and M7 (Building 3), floors 1 - 4	71	26	34	Yes	37	No
M8 and M9 (Building 3), floors 2 - 4	67	22	29	Yes	38	No

^{1 -} Estimated exterior noise level at the building façade based upon Table 2.

References

AELUP (Airport Environmental Land Use Plan). 2008. Airport Environs Land Use Plan for John Wayne Airport. Amended April 2008

Caltrans (California Department of Transportation). 2013. Technical Noise Supplement to the Caltrans Traffic Noise Analysis Protocol. Division of Environmental Analysis, Environmental Engineering, Hazardous Waste, Air, Noise, Paleontology Office. September 2013

Caltrans. 2024. Caltrans Traffic Census Program webpage. Accessed 2/16/2024. https://dot.ca.gov/programs/traffic-operations/census



^{2 -} Noise reduction required to satisfy the interior noise standards.

^{3 -} Minimum interior noise reduction with windows closed and upgraded windows at indicated locations, standard windows elsewhere.

⁴ - Does the required interior noise reduction trigger upgraded windows based on a standard reduction of 25 dBA?

^{5 -} Estimated noise level based upon minimum anticipated noise reduction.

CFR (United States Code of Federal Regulations). 2013. Title 24, Volume 1, Title 51 Subpart B. Accessed 4/22/21: https://www.govinfo.gov/content/pkg/CFR-2013-title24-vol1-part51-subpartB.pdf

Federal Highway Administration (FHWA). 2004. FHWA Traffic Noise Model, Version 2.5. Office of Environment and Planning. Washington, DC. February 2004.





Attachment A

Noise Model Input/Output Data

Home (/) > Programs (/programs/) > Environmental Review (/programs/environmental-review/) > DNL Calculator

DNL Calculator

The Day/Night Noise Level Calculator is an electronic assessment tool that calculates the Day/Night Noise Level (DNL) from roadway and railway traffic. For more information on using the DNL calculator, view the Day/Night Noise Level Calculator Electronic Assessment Tool Overview (/programs/environmental-review/daynight-noise-level-electronic-assessment-tool/).

Guidelines

- To display the Road and/or Rail DNL calculator(s), click on the "Add Road Source" and/or "Add Rail Source" button(s) below.
- All Road and Rail input values must be positive non-decimal numbers.
- All Road and/or Rail DNL value(s) must be calculated separately before calculating the Site DNL.
- All checkboxes that apply must be checked for vehicles and trains in the tables' headers.
- **Note #1:** Tooltips, containing field specific information, have been added in this tool and may be accessed by hovering over all the respective data fields (site identification, roadway and railway assessment, DNL calculation results, roadway and railway input variables) with the mouse.
- **Note #2:** DNL Calculator assumes roadway data is always entered.

DNL Calculator

Site ID	The Orion HUD Project - Rcvr at SE Corner
Record Date	02/14/2024
User's Name	Mike Greene

SR22 Freeway	
	1
	SR22 Freeway

Road #1

Vehicle Type	Cars 🔽	Medium Trucks 🗹	Heavy Trucks 🗸
Effective Distance	450	450	450
Distance to Stop Sign			
Average Speed	65	65	60
Average Daily Trips (ADT)	157172	3088	2275
Night Fraction of ADT	15	15	15
Road Gradient (%)			0
Vehicle DNI	67	60	64

Terricio DITE	· ·		<u> </u>
Calculate Road #1 DNL	69	Reset	
Road # 2 Name:	SR55 Freeway		
Road #2			
Vehicle Type	Cars 🔽	Medium Trucks 🗹	Heavy Trucks 🗸
Effective Distance	870	870	870
Distance to Stop Sign			
Average Speed	65	65	60
Average Daily Trips (ADT)	234881	8736	5991
Night Fraction of ADT	15	15	15
Road Gradient (%)			0
Vehicle DNL	64	60	64
Calculate Road #2 DNL	68	Reset	
Road # 3 Name:	South Tustin Ave		

Road #3

Vehicle Type	Cars 🗹	Medium Trucks 🗹	Heavy Trucks 🗸
Effective Distance	560	560	560
Distance to Stop Sign			
Average Speed	40	40	35
Average Daily Trips (ADT)	28990	598	299
Night Fraction of ADT	15	15	15
Road Gradient (%)			0
Vehicle DNL	54	47	52
Calculate Road #3 DNL	57	Reset	
Road # 4 Name:	La Veta Ave		

Road #4

Vehicle Type	Cars 🗹	Medium Trucks 🗸	Heavy Trucks 🗹
Effective Distance	370	370	370
Distance to Stop Sign			
Average Sneed	40	40	35

Average speed			
Average Daily Trips (ADT)	10035	207	103
Night Fraction of ADT	15	15	15
Road Gradient (%)			0
Vehicle DNL	52	45	50
Calculate Road #4 DNL	55	Reset	
Add Road Source Add Rail	Source		
Airport Noise Level			
Loud Impulse Sounds?		○Yes ○No	
Combined DNL for all Road and Rail sources		72	
Combined DNL including Airp	port	N/A	
Site DNL with Loud Impulse S	ound		
Calculate Reset			

Talcalace || Neset

Mitigation Options

If your site DNL is in Excess of 65 decibels, your options are:

- **No Action Alternative**: Cancel the project at this location
- Other Reasonable Alternatives: Choose an alternate site
- Mitigation
 - Contact your Field or Regional Environmental Officer (/programs/environmental-review/hudenvironmental-staff-contacts/)
 - Increase mitigation in the building walls (only effective if no outdoor, noise sensitive areas)
 - Reconfigure the site plan to increase the distance between the noise source and noise-sensitive uses
 - Incorporate natural or man-made barriers. See *The Noise Guidebook (/resource/313/hud-noise-guidebook/*)
 - Construct noise barrier. See the Barrier Performance Module (/programs/environmental-review/bpm-calculator/)

Tools and Guidance

Day/Night Noise Level Assessment Tool User Guide (/resource/3822/day-night-noise-level-assessment-tool-user-guide/)

Day/Night Noise Level Assessment Tool Flowcharts (/resource/3823/day-night-noise-level-assessment-tool-flowcharts/)

Home (/) > Programs (/programs/) > Environmental Review (/programs/environmental-review/) > DNL Calculator

DNL Calculator

The Day/Night Noise Level Calculator is an electronic assessment tool that calculates the Day/Night Noise Level (DNL) from roadway and railway traffic. For more information on using the DNL calculator, view the Day/Night Noise Level Calculator Electronic Assessment Tool Overview (/programs/environmental-review/daynight-noise-level-electronic-assessment-tool/).

Guidelines

- To display the Road and/or Rail DNL calculator(s), click on the "Add Road Source" and/or "Add Rail Source" button(s) below.
- All Road and Rail input values must be positive non-decimal numbers.
- All Road and/or Rail DNL value(s) must be calculated separately before calculating the Site DNL.
- All checkboxes that apply must be checked for vehicles and trains in the tables' headers.
- **Note #1:** Tooltips, containing field specific information, have been added in this tool and may be accessed by hovering over all the respective data fields (site identification, roadway and railway assessment, DNL calculation results, roadway and railway input variables) with the mouse.
- **Note #2:** DNL Calculator assumes roadway data is always entered.

DNL Calculator

Site ID	The Orion HUD Project - Rcvr at SW Corner
Record Date	02/14/2024
User's Name	Mike Greene

Road # 1 Name:	SR22 Freeway

Road #1

Vehicle Type	Cars 🔽	Medium Trucks 🗸	Heavy Trucks 🗹		
Effective Distance	500	500	500		
Distance to Stop Sign					
Average Speed	65	65	60		
Average Daily Trips (ADT)	157172	3088	2275		
Night Fraction of ADT	15	15	15		
Road Gradient (%)			0		
Vehicle DNI	66	59	63		

TOTALICE DITE			
Calculate Road #1 DNL	68	Reset	
Road # 2 Name:	SR55 Freeway		
Road #2			
Vehicle Type	Cars 🔽	Medium Trucks 🗸	Heavy Trucks 🗹
Effective Distance	1370	1370	1370
Distance to Stop Sign			
Average Speed	65	65	60
Average Daily Trips (ADT)	234881	8736	5991
Night Fraction of ADT	15	15	15
Road Gradient (%)			0
Vehicle DNL	61	57	61
Calculate Road #2 DNL	65	Reset	
Road # 3 Name:	South Tustin Ave		

Road #3

Vehicle Type	Cars 🗸	Medium Trucks 🗹	Heavy Trucks 🗹
Effective Distance	65	65	65
Distance to Stop Sign			
Average Speed	40	40	35
Average Daily Trips (ADT)	28990	598	299
Night Fraction of ADT	15	15	15
Road Gradient (%)			0
Vehicle DNL	68	61	66
Calculate Road #3 DNL	71	Reset	

Road # 4 Name:	La Veta Ave	

Road #4

Vehicle Type	Cars 🗹	Medium Trucks 🗹	Heavy Trucks 🗹
Effective Distance	280	280	280
Distance to Stop Sign			
Average Sneed	40	40	35

A Wellage Speed				
Average Daily Trips (ADT)	10035	207	103	
Night Fraction of ADT	15	15	15	
Road Gradient (%)			0	
Vehicle DNL	54	47	52	
Calculate Road #4 DNL	56	Reset		
Add Road Source Add Rail	Source			
Airport Noise Level				
Loud Impulse Sounds?		○Yes ○No		
Combined DNL for all Road and Rail sources		73		
Combined DNL including Airp	oort	N/A		
Site DNL with Loud Impulse S	Sound			
Calculate Reset				

Carcarace || Neset

Mitigation Options

If your site DNL is in Excess of 65 decibels, your options are:

- **No Action Alternative**: Cancel the project at this location
- Other Reasonable Alternatives: Choose an alternate site
- Mitigation
 - Contact your Field or Regional Environmental Officer (/programs/environmental-review/hudenvironmental-staff-contacts/)
 - Increase mitigation in the building walls (only effective if no outdoor, noise sensitive areas)
 - Reconfigure the site plan to increase the distance between the noise source and noise-sensitive uses
 - Incorporate natural or man-made barriers. See *The Noise Guidebook (/resource/313/hud-noise-guidebook/*)
 - Construct noise barrier. See the Barrier Performance Module (/programs/environmental-review/bpm-calculator/)

Tools and Guidance

Day/Night Noise Level Assessment Tool User Guide (/resource/3822/day-night-noise-level-assessment-tool-user-guide/)

<u>Day/Night Noise Level Assessment Tool Flowcharts (/resource/3823/day-night-noise-level-assessment-tool-flowcharts/)</u>

Dudek					20 February	2024					
M Greene					TNM 2.5						
INPUT: ROADWAYS							_	pavement typ			
PROJECT/CONTRACT:	13230							ighway agend	-		
RUN:	Orion HU	D Project	- Fut with	Project Pk-F	lr		of a diffe	rent type with	the appro	val of FHW	A
Roadway		Points									
Name	Width	Name	No.	Coordinates	(pavement)		Flow Co	ntrol		Segment	
				X	Y	Z	Control	Speed	Percent	Pvmt	On
							Device	Constraint	Vehicles	Туре	Struct?
									Affected		
	ft			ft	ft	ft		mph	%		
La Veta Ave	55.0	point1	1	2,346.0	2,236.2	255.00				Average	
		point3	3	2,111.6	2,250.2	254.00				Average	
		point4	4	1,980.3	2,248.1	250.00				Average	
		point5	5	1,837.0	2,234.5	245.00				Average	
		point6	6	1,703.0	2,209.9	240.00				Average	
		point7	7	1,526.6	2,166.1	230.00				Average	
		point8	8	1,350.3	2,098.9	222.00				Average	
		point9	9	1,211.2	2,036.3					Average	
		point10	10	990.8	1,929.5					Average	
		point11	11	829.8	1,856.0					Average	
		point12	12	705.9	1,810.0						
SR55NB	80.0	•	51	2,144.8	748.2					Average	
		point20	20	2,141.8	1,364.8					Average	
		point21	21	2,127.9	2,095.2					Average	
		point57	57	2,129.6	2,234.9						
SR22 WB - 1	35.0	•	52	1,992.9	2,195.8					Average	
		point24	24	1,985.9	1,970.1					Average	
		point25	25	1,938.6	1,771.5					Average	
		point26	26	1,878.3	1,634.2					Average	
		point27	27	1,786.4	1,502.9					Average	
		point28	28	1,680.2	1,389.8					Average	
		point29	29	1,528.1	1,287.7					Average	
		point30	30	1,333.9	1,214.2					Average	
		point31	31	767.4	1,043.4					Average	
		point32	32	731.6	1,030.8	190.00					

INPUT: ROADWAYS 13230

III O II INOADIIAI O							
S Tustin Avenue	85.0	point53	53	674.9	960.9	213.00	Average
		point14	14	672.8	1,004.7	215.00	Average
		point15	15	674.2	1,297.0	218.00	Average
		point16	16	678.4	1,610.8	220.00	Average
		point17	17	688.9	1,815.5	224.00	Average
		point18	18	671.4	2,672.9	220.00	
SR22 EB - 2	35.0	point54	54	414.8	907.2	0.00	Average
		point2	2	632.1	971.1	0.00	
SR22 EB - 1	35.0	point55	55	731.6	1,005.8	189.00	Average
		point34	34	776.2	1,020.3	190.00	Average
		point35	35	1,225.4	1,136.2	190.00	Average
		point36	36	1,335.6	1,149.3	190.00	Average
		point37	37	1,457.2	1,156.3	190.00	Average
		point38	38	1,604.2	1,135.3	190.00	Average
		point39	39	1,805.4	1,056.6	190.00	Average
		point40	40	1,946.3	956.8	190.00	Average
		point41	41	2,019.8	858.0	190.00	
SR22 WB - 2	35.0	point56	56	630.0	997.5	192.00	Average
		point43	43	406.5	933.0	192.00	
SR55-2NB	80.0	point59	59	2,130.8	2,298.5	230.00	Average
		point58	58	2,133.3	2,573.6	234.00	Average
		point22	22	2,135.2	2,806.9	236.00	
SR55SB	80.0	point62	62	2,058.4	748.2	216.00	Average
		point63	63	2,052.8	1,364.8	222.00	Average
		point64	64	2,038.9	2,095.2	227.00	Average
		point65	65	2,043.1	2,234.9	229.00	
SR55-2SB	80.0	point66	66	2,039.3	2,295.3	230.00	Average
		point67	67	2,041.8	2,570.4	234.00	Average
		point68	68	2,043.7	2,803.7	236.00	

•												Т
Dudek				20 Fab		0.4						
					ruary 20	24						
M Greene				TNM 2	.5							
INPUT: TRAFFIC FOR LAeq1h Vo	lumes											
PROJECT/CONTRACT:	13230			1								
RUN:	Orion HUD	Project - I	ut with I	Project	Pk-Hr							
Roadway	Points											
Name	Name	No.	Segmen	t								
			Autos		MTrucks	5	HTrucks	;	Buses		Motorcy	cles
			V	S	V	S	V	S	V	S	V	S
			veh/hr	mph	veh/hr	mph	veh/hr	mph	veh/hr	mph	veh/hr	mph
La Veta Ave	point1	1	984	40	20	40	10	35	0	0	0	0
	point3	3	984	40	20	40	10	35	0	0	0	0
	point4	4	984	40	20	40	10	35	0	0	0	0
	point5	5	984	40	20	40	10	35	0	0	0	0
	point6	6	984	40	20	40	10	35	0	0	0	0
	point7	7	984	40	20	40	10	35	0	0	0	0
	point8	8	984	40						0	0	0
	point9	9	984	40	20					0	0	0
	point10	10			20							
	point11	11	984	40	20	40	10	35	0	0	0	0
	point12	12										
SR55NB	point51	51	11628	65	432			60				
	point20	20						60		0	0	0
	point21	21	11628	65	432	65	297	60	0	0	0	0
	point57	57										
SR22 WB - 1	point52	52		65								
	point24	24	7781	65						0		
	point25	25		65								
	point26	26		65								
	point27	27	7781	65							·	_
	point28	28		65	153							
	point29	29		65	153							
	point30	30	7781	65	153	65	113	60	0	0	0	0

NPUT: TRAFFIC FOR LAeq1h Volumes						132	30					
	point31	31	7781	65	153	65	113	60	0	0	0	(
	point32	32										
S Tustin Avenue	point53	53	2842	40	59	40	29	35	0	0	0	(
	point14	14	2842	40	59	40	29	35	0	0	0	(
	point15	15	2842	40	59	40	29	35	0	0	0	(
	point16	16	2842	40	59	40	29	35	0	0	0	(
	point17	17	2842	40	59	40	29	35	0	0	0	(
	point18	18										
SR22 EB - 2	point54	54	7781	65	153	65	113	60	0	0	0	(
	point2	2										
SR22 EB - 1	point55	55	7781	65	153	65	113	60	0	0	0	(
	point34	34	7781	65	153	65	113	60	0	0	0	(
	point35	35	7781	65	153	65	113	60	0	0	0	(
	point36	36	7781	65	153	65	113	60	0	0	0	(
	point37	37	7781	65	153	65	113	60	0	0	0	(
	point38	38	7781	65	153	65	113	60	0	0	0	
	point39	39	7781	65	153	65	113	60	0	0	0	(
	point40	40	7781	65	153	65	113	60	0	0	0	(
	point41	41										
SR22 WB - 2	point56	56	7781	65	153	65	113	60	0	0	0	
	point43	43										
SR55-2NB	point59	59	11628	65	432	65	297	60	0	0	0	(
	point58	58	11628	65	432	65	297	60	0	0	0	(
	point22	22										
SR55SB	point62	62	11628	65	432	65	297	60	0	0	0	(
	point63	0	11628	65	432	65	297	60	0	0	0	(
	point64	64	11628	65	432	65	297	60	0	0	0	(
	point65	65										
SR55-2SB	point66	66	11628	65	432	65	297	60	0	0	0	(
	point67	67	11628	65	432	65	297	60	0	0	0	(

point68

Dudek							20 Februa	ry 2024				
M Greene							TNM 2.5					
INPUT: RECEIVERS												
PROJECT/CONTRACT:	13230											
RUN:	Orion	HUD Pr	oject - Fut w	ith Project Pk	k-Hr							
Receiver												
Name	No.	#DUs	Coordinates	(ground)			Height	Input Sou	nd Levels a	and Criteri	a	Active
			X	Y	Z		above	Existing	Impact Cr	iteria	NR	in
							Ground	LAeq1h	LAeq1h	Sub'l	Goal	Calc.
			ft	ft	ft		ft	dBA	dBA	dB	dB	
M1-1	1	1	1,267.7	1,981.3		220.00	5.00	0.00	66	10.0	8.0	0
M2-1	2	1	1,273.4	1,850.1		220.00	5.00	0.00	66	10.0	8.0	0
M3-1	3	1	1,230.3	1,669.0)	220.00	5.00	0.00	66	10.0	8.0	0
M4-1	4	1	1,212.9	1,614.5	,	220.00	5.00	0.00	66	10.0	8.0	0
M5-1	5	1	853.7	1,515.0)	220.00	5.00	0.00	66	10.0	8.0	0
M6-1	6	1	742.4	1,514.7	'	220.00	5.00	0.00	66	10.0	8.0	0
M7-1	7	1	732.9	1,658.0		220.00	5.00	0.00	66	10.0	8.0	0
M8-1	8	1	767.4	1,671.8	3	220.00	5.00	0.00	66	10.0	8.0	0
M9-1	9	1	1,168.3	1,725.5	5	220.00	5.00	0.00	66	10.0	8.0	0
M10-1	10	1	1,157.2	1,921.1		220.00	5.00	0.00	66	10.0	8.0	0
M1-2	12	1	1,267.7	1,981.3	3	220.00	15.00	0.00	66	10.0	8.0	0
M2-2	13	1	1,273.4	1,850.1		220.00	15.00	0.00	66	10.0	8.0	0
M3-2	14	1	1,230.3	1,669.0)	220.00	15.00	0.00	66	10.0	8.0	0
M4-2	15		1,212.9			220.00		0.00				
M5-2	16	1	853.7	,		220.00		0.00				
M6-2	17	1	742.4	1,514.7		220.00		0.00				
M7-2	18		732.9	,		220.00		0.00				
M8-2	19		767.4	,		220.00		0.00				
M9-2	20	1	1,168.3	,		220.00		0.00				
M10-2	21	1	1,157.2	· · · · · · · · · · · · · · · · · · ·		220.00		0.00				
M1-3	22	1	1,267.7	· ·		220.00		0.00				
M2-3	24	1	1,273.4	1,850.1		220.00	25.00	0.00	66	10.0	8.0	0

INPUT: RECEIVERS							132	230			
M3-3	25	1	1,230.3	1,669.0	220.00	25.00	0.00	66	10.0	8.0	
M4-3	26	1	1,212.9	1,614.5	220.00	25.00	0.00	66	10.0	8.0	
M5-3	27	1	853.7	1,515.0	220.00	25.00	0.00	66	10.0	8.0	
M6-3	28	1	742.4	1,514.7	220.00	25.00	0.00	66	10.0	8.0	
M7-3	29	1	732.9	1,658.0	220.00	25.00	0.00	66	10.0	8.0	
M8-3	30	1	767.4	1,671.8	220.00	25.00	0.00	66	10.0	8.0	
M9-3	31	1	1,168.3	1,725.5	220.00	25.00	0.00	66	10.0	8.0	
M10-3	32	1	1,157.2	1,921.1	220.00	25.00	0.00	66	10.0	8.0	
M1-4	33	1	1,267.7	1,981.3	220.00	35.00	0.00	66	10.0	8.0	
M2-4	34	1	1,273.4	1,850.1	220.00	35.00	0.00	66	10.0	8.0	
M3-4	35	1	1,230.3	1,669.0	220.00	35.00	0.00	66	10.0	8.0	
M4-4	36	1	1,212.9	1,614.5	220.00	35.00	0.00	66	10.0	8.0	
M5-4	38	1	853.7	1,515.0	220.00	35.00	0.00	66	10.0	8.0	
M6-4	39	1	742.4	1,514.7	220.00	35.00	0.00	66	10.0	8.0	
M7-4	41	1	732.9	1,658.0	220.00	35.00	0.00	66	10.0	8.0	
M8-4	42	1	767.4	1,671.8	220.00	35.00	0.00	66	10.0	8.0	
M9-4	43	1	1,168.3	1,725.5	220.00	35.00	0.00	66	10.0	8.0	
M10-4	44	1	1,157.2	1,921.1	220.00	35.00	0.00	66	10.0	8.0	
M11	46	1	1,154.7	1,818.0	220.00	5.00	0.00	66	10.0	8.0	
M12	47	1	1,212.5	1,592.0	220.00	5.00	0.00	66	10.0	8.0	
M13	48	1	811.2	1,603.0	220.00	5.00	0.00	66	10.0	8.0	
M14	49	1	876.3	1,743.0	220.00	5.00	0.00	66	10.0	8.0	Υ

Dudek					20 Febr	⊔arv 2∩	24											
M Greene					TNM 2.5	•	- 											
m Graefie					114181 2.5	, 												
INPUT: BARRIERS																		
PROJECT/CONTRACT:	13230)																
RUN:	Orion	HUD Pr	oject - F	ut with P	roject Pl	c-Hr												
Barrier									Points									
Name	Туре	Height		If Wall	If Berm			Add'tnl	Name	No.	Coordinates	(bottom)		Height	Segment			
		Min	Max	\$ per	\$ per	Тор	Run:Rise	\$ per			x	Υ	Z	at	Seg Ht Per	turbs	On	Important
				Unit	Unit	Width		Unit						Point	Incre- #Up	#Dn	Struct?	Reflec-
				Area	Vol.			Length							ment			tions?
		ft	ft	\$/sq ft	\$/cu yd	ft	ft:ft	\$/ft			ft	ft	ft	ft	ft			
Terrain Line - top of slope wall	W	0.00	99.99	0.00				0.00	point1	1	730.5	1,101.0	211.00	14.00	0.00) ()	
									point3	3	1,080.4	1,209.3	212.00	14.00	0.00) ()	
									point4	4	1,386.0	1,311.4	212.00	14.00	0.00) ()	
									point5	5	1,533.2	1,361.4	213.00	14.00	0.00) ()	
									point6	6	,	1,424.2	215.00	14.00				
									point7	7		-	218.00	14.00) (
									point8	8			220.00	14.00) ()	
									point9	9	, , , , , , , , , , , , , , , , , , ,		220.00	14.00				
Barrier1-2-2-2	W	0.00	99.99	0.00				0.00		47		1,644.5	220.00	45.00) (
									point27	27		1,644.5	220.00	45.00				
									point28	28		1,618.6	220.00) (
									point29	29	, , , , , , , , , , , , , , , , , , ,	1,618.2	220.00	45.00				
									point30	30	,	1,632.7	220.00	45.00				
									point31 point32	31 32	,	1,632.2 1,679.9	220.00 220.00	45.00 45.00) (,	
Barrier1-2-2	W	0.00	99.99	0.00				0.00		48			220.00	45.00) (`	
Dairiei 1-2-2	VV	0.00	99.98	0.00				0.00	point20	20		1,669.1	220.00	45.00				
									point21	21		,	220.00	45.00) (
									point21	22		1,570.5	220.00	45.00				
									point23	23		1,515.9	220.00	45.00		1	1	
									point24	24		1,516.4	220.00	45.00				
									point25	25		1,666.9	220.00	45.00			,	
Barrier1-2-2-2-2	W	0.00	99.99	0.00				0.00	H .	50		1,979.3	220.00	45.00) ()	
									point34	34		1,848.0	220.00	45.00) (+
									point35	35	1,102.6	1,855.0	220.00	45.00	0.00) ()	
									point36	36	,	1,914.5	220.00	45.00				
Barrier12	W	0.00	99.99	0.00				0.00	-	52	1,925.6	1,804.8	220.00	14.00	0.00) ()	
									point53	53	1,965.4	1,970.1	225.00	14.00	0.00) ()	
									point54	54	1,971.1	2,211.0	226.00	14.00				
Barrier13	W	0.00	99.99	0.00				0.00	point55	55	1,998.1	2,726.9	254.00	10.00	0.00) ()	
_									point56	56	1,998.2	2,295.6	250.00	10.00	0.00) ()	
									point57	57	1,854.9	2,282.0	245.00	10.00	0.00) ()	
									point58	58		2,257.4	240.00	10.00	0.00) ()	
									point59	59			230.00	10.00) ()	
									point60	60	1,368.2	2,146.4	222.00	10.00				

Barrier14	W	0.00	99.99	0.00		0.00	point61	61	1,373.3	2,052.9	222.00	0.00	0.00	0	0	
							point62	62	1,234.2	1,990.3	222.00	0.00	0.00	0	0	
							point63	63	1,013.8	1,883.5	222.00	0.00	0.00	0	0	
							point64	64	852.8	1,810.0	221.00	0.00	0.00	0	0	
							point65	65	728.9	1,764.0	220.00	0.00	0.00	0	0	
							point66	66	728.7	1,587.9	220.00	0.00				
Barrier15	W	0.00	99.99	0.00		0.00	point67	67	602.2	1,085.9	211.00	14.00	0.00	0	0	
							point68	68	383.8	997.8	211.00	14.00				

INPUT: BUILDING ROWS					13	3230	
Dudek					20 February 2	024	
M Greene					TNM 2.5		
INPUT: BUILDING ROWS							
PROJECT/CONTRACT:	13230	1					
RUN:	Orion HUD	Project - Fut	t with P	ri			
Building Row			Points	3			
Name	Average	Building	No.	Coordinates (ground)		
	Height	Percent		X	Υ	Z	
	ft	%		ft	ft	ft	
Building2	12.00	80	1	1,341.8	1,549.7		220.00
			2	1,368.3	1,561.9		220.00
			3	1,500.6	1,622.6	i	220.00
			4	1,635.1	1,763.6	;	220.00
			5				220.00
			6	· · · · · · · · · · · · · · · · · · ·			220.00
Building4	12.00	80	9		,		220.00
			10		· ·		220.00
			11		,		220.00
			12	· · · · · · · · · · · · · · · · · · ·			220.00
			13	,			220.00
			14	, , , , , , , , , , , , , , , , , , ,	1		220.00
			15		,		220.00
			16	· · · · · · · · · · · · · · · · · · ·			220.00
			17	,			220.00
Building5	12.00	80	18	598.4	1,718.1		220.00

19

598.4

220.00

1,093.6

RESOLIS. SOCIAD ELVEES		1				'	3230				T.	
Dudek							20 Februa	m, 2024				
M Greene							TNM 2.5	ily 2024				
W Greene								d with TNN	125			
RESULTS: SOUND LEVELS							Guiodiato	u 171011 11101	. 2.0			
PROJECT/CONTRACT:		13230										
RUN:			HUD Proied	t - Fut with P	roiect Pk-H	r						
BARRIER DESIGN:			HEIGHTS					Average r	pavement type	shall be use	d unless	
										y substantiate		
ATMOSPHERICS:		68 deg	F, 50% RH	ł						approval of F		
Receiver												
Name	No.	#DUs	Existing	No Barrier			-		With Barrier			
			LAeq1h	LAeq1h		Increase over	existing	Туре	Calculated	Noise Reduc	tion	
				Calculated	Crit'n	Calculated	Crit'n	Impact	LAeq1h	Calculated	Goal	Calculated
							Sub'l Inc					minus
												Goal
			dBA	dBA	dBA	dB	dB		dBA	dB	dB	dB
M1-1	1		0.0	65.0) 66	65.0	10		65.0	0.0		8 -8.0
M2-1	2		0.0	60.1	66	60.1	10		60.1	0.0		-8.0
M3-1	3		0.0	59.9	66	59.9) 10		59.9	0.0		8 -8.0
M4-1	4		0.0	60.6	66	60.6	3 10		60.6	0.0		8 -8.0
M5-1	5		0.0	62.5	66	62.5	5 10		62.5	0.0		8 -8.0
M6-1	6		0.0	69.6	66	69.6	3 10	Snd Lvl	69.6	0.0		-8.0
M7-1	7		0.0	70.4	66	70.4	10	Snd Lvl	70.4	0.0		-8.0
M8-1	8		0.0	66.0	66	66.0) 10	Snd Lvl	66.0	0.0		-8.0
M9-1	9		0.0			59.9) 10		59.9	0.0		-8.0
M10-1	10		0.0	63.6			3 10		63.6	0.0		-8.0
M1-2	12								66.4			8 -8.0
M2-2	13		0.0						63.5			8 -8.0
M3-2	14		0.0						64.8			8 -8.0
M4-2	15		0.0						65.4			-8.0
M5-2	16		0.0						65.2			8 -8.0
M6-2	17		0.0						70.3		-	8 -8.0
M7-2	18		0.0						70.2			8 -8.0
M8-2	19		0.0						66.4			8 -8.0
M9-2	20		0.0						63.3			8 -8.0
M10-2	21		0.0			-			64.2			8 -8.0
M1-3	22		0.0						67.1			8 -8.0
M2-3	24		0.0						65.7			8 -8.0
M3-3	25		0.0						66.7			-8.0
M4-3	26	1	0.0	67.1	66	67.1	10	Snd Lvl	67.1	0.0	1	-8.0

RESULTS: SOUND LEVELS							13	230					
M5-3	27	1	0.0)	65.9	66	65.9	10		65.9	0.0	8	-8.0
M6-3	28	1	0.0)	70.2	66	70.2	10	Snd Lvl	70.2	0.0	8	-8.0
M7-3	29	1	0.0)	69.9	66	69.9	10	Snd Lvl	69.9	0.0	8	-8.0
M8-3	30	1	0.0)	66.2	66	66.2	10	Snd Lvl	66.2	0.0	8	-8.0
M9-3	31	1	0.0)	65.2	66	65.2	10		65.2	0.0	8	-8.0
M10-3	32	1	0.0)	64.2	66	64.2	10		64.2	0.0	8	-8.0
M1-4	33	1	0.0)	68.1	66	68.1	10	Snd Lvl	68.1	0.0	8	-8.0
M2-4	34	1	0.0)	67.2	66	67.2	10	Snd Lvl	67.2	0.0	8	-8.0
M3-4	35	1	0.0)	67.9	66	67.9	10	Snd Lvl	67.9	0.0	8	-8.0
M4-4	36	1	0.0)	68.2	66	68.2	10	Snd Lvl	68.2	0.0	8	-8.0
M5-4	38	1	0.0)	66.8	66	66.8	10	Snd Lvl	66.8	0.0	8	-8.0
M6-4	39	1	0.0)	70.0	66	70.0	10	Snd Lvl	70.0	0.0	8	-8.0
M7-4	41	1	0.0)	69.7	66	69.7	10	Snd Lvl	69.7	0.0	8	-8.0
M8-4	42	1	0.0)	66.2	66	66.2	10	Snd Lvl	66.2	0.0	8	-8.0
M9-4	43	1	0.0)	66.4	66	66.4	10	Snd Lvl	66.4	0.0	8	-8.0
M10-4	44	1	0.0)	64.2	66	64.2	10		64.2	0.0	8	-8.0
M11	46	1	0.0)	59.9	66	59.9	10		59.9	0.0	8	-8.0
M12	47	1	0.0)	61.0	66	61.0	10		61.0	0.0	8	-8.0
M13	48	1	0.0)	58.5	66	58.5	10		58.5	0.0	8	-8.0
M14	49	1	0.0)	64.7	66	64.7	10		64.7	0.0	8	-8.0
Dwelling Units		# DUs	Noise Re	duction			·						
			Min	Avg	Max								
			dB	dB	dB								
All Selected		44	0.0)	0.0	0.0							
All Impacted		22	0.0)	0.0	0.0							

0.0

0.0

0.0

All that meet NR Goal

Dudek					20 February	2024					
M Greene					TNM 2.5						
INPUT: ROADWAYS							Average	pavement typ	e shall be i	used unles	s
PROJECT/CONTRACT:	13230							ighway agend			
RUN:		D Project	- Fut with	Proj Off-Pk				rent type with			
Roadway		Points					7	7,1			
Name	Width	Name	No.	Coordinates	(pavement)		Flow Cor	itrol		Segment	
				X	Ϋ́	Z	Control	Speed	Percent	Pvmt	On
							Device	Constraint	Vehicles	Туре	Struct?
									Affected	7,7,7	
	ft			ft	ft	ft		mph	%		
La Veta Ave	55.0	point1	1	2,346.0	2,236.2	255.00)			Average	
		point3	3	2,111.6	2,250.2	254.00)			Average	
		point4	4	1,980.3	2,248.1	250.00)			Average	
		point5	5	1,837.0	2,234.5	245.00)			Average	
		point6	6	1,703.0	2,209.9	240.00)			Average	
		point7	7	1,526.6	2,166.1	230.00)			Average	
		point8	8	1,350.3	2,098.9	222.00)			Average	
		point9	9	1,211.2	2,036.3	3 222.00)			Average	
		point10	10	990.8	1,929.5	222.00)			Average	
		point11	11	829.8	1,856.0	221.00)			Average	
		point12	12	705.9	· ·						
SR55NB	80.0	point51	51	2,144.8						Average	
		point20	20	2,141.8	1,364.8					Average	
		point21	21	2,127.9						Average	
		point57	57	2,129.6	•)				
SR22 WB - 1	35.0	point52	52	,						Average	
		point24	24							Average	
		point25	25	1,938.6						Average	
		point26	26	1,878.3						Average	
		point27	27	1,786.4	· ·					Average	
		point28	28							Average	
		point29	29		-					Average	
		point30	30	•						Average	
		point31	31	767.4	,					Average	
		point32	32	731.6	1,030.8	190.00)				

INPUT: ROADWAYS 13230

S Tustin Avenue	85.0	point53	53	674.9	960.9	213.00	Average
		point14	14	672.8	1,004.7	215.00	Average
		point15	15	674.2	1,297.0	218.00	Average
		point16	16	678.4	1,610.8	220.00	Average
		point17	17	688.9	1,815.5	224.00	Average
		point18	18	671.4	2,672.9	220.00	
SR22 EB - 2	35.0	point54	54	414.8	907.2	0.00	Average
		point2	2	632.1	971.1	0.00	
SR22 EB - 1	35.0	point55	55	731.6	1,005.8	189.00	Average
		point34	34	776.2	1,020.3	190.00	Average
		point35	35	1,225.4	1,136.2	190.00	Average
		point36	36	1,335.6	1,149.3	190.00	Average
		point37	37	1,457.2	1,156.3	190.00	Average
		point38	38	1,604.2	1,135.3	190.00	Average
		point39	39	1,805.4	1,056.6	190.00	Average
		point40	40	1,946.3	956.8	190.00	Average
		point41	41	2,019.8	858.0	190.00	
SR22 WB - 2	35.0	point56	56	630.0	997.5	192.00	Average
		point43	43	406.5	933.0	192.00	
SR55-2NB	80.0	point59	59	2,130.8	2,298.5	230.00	Average
		point58	58	2,133.3	2,573.6	234.00	Average
		point22	22	2,135.2	2,806.9	236.00	
SR55SB	80.0	point62	62	2,058.4	748.2	216.00	Average
		point63	63	2,052.8	1,364.8	222.00	Average
		point64	64	2,038.9	2,095.2	227.00	Average
		point65	65	2,043.1	2,234.9	229.00	
SR55-2SB	80.0	point66	66	2,039.3	2,295.3	230.00	Average
		point67	67	2,041.8	2,570.4	234.00	Average
		point68	68	2,043.7	2,803.7	236.00	

•				1				1				T
Dudek				20 Eab	ruary 20	24						
M Greene				TNM 2	-							
W Oreene				1 14171 2								
INPUT: TRAFFIC FOR LAeq1h Volu	umes											
PROJECT/CONTRACT:	13230			1								
RUN:	Orion HUD	Project - I	Fut with I	Proj Off	-Pk							
Roadway	Points											
Name	Name	No.	Segmen	t								
			Autos		MTrucks	6	HTrucks		Buses		Motorcy	cles
			V	S	V	S	V	S	V	S	V	S
			veh/hr	mph	veh/hr	mph	veh/hr	mph	veh/hr	mph	veh/hr	mph
La Veta Ave	point1	1	590	40	12	40	6	35	0	0	0	0
	point3	3	590	40	12	40	6	35	0	0	0	0
	point4	4	590	40	12	40	6	35	0	0	0	0
	point5	5	590	40	12	40	6	35	0	0	0	0
	point6	6	590	40	12	40	6	35	0	0	0	0
	point7	7	590	40	12	40	6	35	0	0	0	0
	point8	8	590	40						0	0	0
	point9	9	590	40	12	40				0	0	0
	point10	10	590	40	12							
	point11	11	590	40	12	40	6	35	0	0	0	0
	point12	12										
SR55NB	point51	51	6977	65	259							
	point20	20		65								
	point21	21	6977	65	259	65	178	60	0	0	0	0
	point57	57										
SR22 WB - 1	point52	52										
	point24	24		65								
	point25	25		65								
	point26	26		65	92							
	point27	27		65	92							
	point28	28			92							
	point29	29		65	92	65						
	point30	30	4668	65	92	65	68	60	0	0	0	0

INPUT: TRAFFIC FOR LAeq1h Volumes						132	230					
•	point31	31	4668	65	92	65	68	60	0	0	0	(
	point32	32										
S Tustin Avenue	point53	53	1705	40	35	40	18	35	0	0	0	(
	point14	14	1705	40	35	40	18	35	0	0	0	(
	point15	15	1705	40	35	40	18	35	0	0	0	(
	point16	16	1705	40	35	40	18	35	0	0	0	(
	point17	17	1705	40	35	40	18	35	0	0	0	(
	point18	18										
SR22 EB - 2	point54	54	4668	65	92	65	68	60	0	0	0	(
	point2	2										
SR22 EB - 1	point55	55	4668	65	92	65	68	60	0	0	0	(
	point34	34	4668	65	92	65	68	60	0	0	0	(
	point35	35	4668	65	92	65	68	60	0	0	0	(
	point36	36	4668	65	92	65	68	60	0	0	0	(
	point37	37	4668	65	92	65	68	60	0	0	0	(
	point38	38	4668	65	92	65	68	60	0	0	0	(
	point39	39	4668	65	92	65	68	60	0	0	0	(
	point40	40	4668	65	92	65	68	60	0	0	0	(
	point41	41										
SR22 WB - 2	point56	56	4668	65	92	65	68	60	0	0	0	(
	point43	43										
SR55-2NB	point59	59	6977	65	259	65	178	60	0	0	0	(
	point58	58	6977	65	259	65	178	60	0	0	0	(
	point22	22										
SR55SB	point62	62	6977	65	259	65	178	60	0	0	0	(
									l		1	

SR55-2SB

point63

point64

point65

point66

point67

point68

INPUT: RECEIVERS	13230
------------------	-------

INPUI: RECEIVERS									13230			
Dudek M Greene							20 Februa TNM 2.5	ry 2024				
INPUT: RECEIVERS												
PROJECT/CONTRACT:	13230			:41 B . : Off B	-							
RUN:	Orion	HUD P	roject - Fut w	ith Proj Off-P	K							
Receiver			-									
Name	No.	#DUs	Coordinates				Height		nd Levels a			Active
			X	Υ	Z		above		Impact Cr		NR	in
							Ground	LAeq1h	LAeq1h	Sub'l	Goal	Calc.
			ft	ft	ft		ft	dBA	dBA	dB	dB	
M1-1	1	1	1,267.7	1,981.3	22	20.00	5.00	0.00	66	10.0	8.	.0 Y
M2-1	2	1	1,273.4	1,850.1	22	20.00	5.00	0.00	66	10.0	8.	.0 Y
M3-1	3	1	1,230.3	1,669.0	22	20.00	5.00	0.00	66	10.0	8.	.0 Y
M4-1	4	1	1,212.9	1,614.5	22	20.00	5.00	0.00	66	10.0	8.	.0 Y
M5-1	5	1	853.7	1,515.0	22	20.00	5.00	0.00	66	10.0	8.	.0 Y
M6-1	6	1	742.4	1,514.7	22	20.00	5.00	0.00	66	10.0	8.	
M7-1	7	1	732.9	1,658.0	22	20.00	5.00	0.00	66	10.0	8.	.0 Y
M8-1	8	1	767.4	1,671.8	22	20.00	5.00	0.00	66	10.0	8.	
M9-1	9	1	1,168.3	1,725.5	22	20.00	5.00	0.00	66	10.0	8.	
M10-1	10	1	1,157.2	1,921.1	22	20.00	5.00	0.00	66	10.0	8.	.0 Y
M1-2	12	1	1,267.7	1,981.3	22	20.00	15.00	0.00	66	10.0	8.	
M2-2	13		1,273.4	1,850.1		20.00						
M3-2	14		,			20.00						
M4-2	15					20.00						
M5-2	16	1		,		20.00						
M6-2	17					20.00						
M7-2	18			1,658.0		20.00						
M8-2	19			·		20.00						
M9-2	20	1	•			20.00						
M10-2	21	1	-,			20.00						
M1-3	22		-,			20.00						
M2-3	24	1	1,273.4	1,850.1	22	20.00	25.00	0.00	66	10.0	8.	.0 Y

INPUT: RECEIVERS							132	30			
M3-3	25	1	1,230.3	1,669.0	220.00	25.00	0.00	66	10.0	8.0	Υ
M4-3	26	1	1,212.9	1,614.5	220.00	25.00	0.00	66	10.0	8.0	Υ
M5-3	27	1	853.7	1,515.0	220.00	25.00	0.00	66	10.0	8.0	Υ
M6-3	28	1	742.4	1,514.7	220.00	25.00	0.00	66	10.0	8.0	Υ
M7-3	29	1	732.9	1,658.0	220.00	25.00	0.00	66	10.0	8.0	Υ
M8-3	30	1	767.4	1,671.8	220.00	25.00	0.00	66	10.0	8.0	Υ
M9-3	31	1	1,168.3	1,725.5	220.00	25.00	0.00	66	10.0	8.0	Υ
M10-3	32	1	1,157.2	1,921.1	220.00	25.00	0.00	66	10.0	8.0	Υ
M1-4	33	1	1,267.7	1,981.3	220.00	35.00	0.00	66	10.0	8.0	Υ
M2-4	34	1	1,273.4	1,850.1	220.00	35.00	0.00	66	10.0	8.0	Υ
M3-4	35	1	1,230.3	1,669.0	220.00	35.00	0.00	66	10.0	8.0	Υ
M4-4	36	1	1,212.9	1,614.5	220.00	35.00	0.00	66	10.0	8.0	Υ
M5-4	38	1	853.7	1,515.0	220.00	35.00	0.00	66	10.0	8.0	Υ
M6-4	39	1	742.4	1,514.7	220.00	35.00	0.00	66	10.0	8.0	Υ
M7-4	41	1	732.9	1,658.0	220.00	35.00	0.00	66	10.0	8.0	Υ
M8-4	42	1	767.4	1,671.8	220.00	35.00	0.00	66	10.0	8.0	Υ
M9-4	43	1	1,168.3	1,725.5	220.00	35.00	0.00	66	10.0	8.0	Υ
M10-4	44	1	1,157.2	1,921.1	220.00	35.00	0.00	66	10.0	8.0	Υ
M11	46	1	1,154.7	1,818.0	220.00	5.00	0.00	66	10.0	8.0	
M12	47	1	1,212.5	1,592.0	220.00	5.00	0.00	66	10.0	8.0	
M13	48	1	811.2	1,603.0	220.00	5.00	0.00	66	10.0	8.0	
M14	49	1	876.2	1,743.0	220.00	5.00	0.00	66	10.0	8.0	Υ

Dudek					20 Febr	uary 20	24											
M Greene					TNM 2.5	•	- 											
in Greene					. IVIVI 2.0	,												
INPUT: BARRIERS																		
PROJECT/CONTRACT:	13230) <u> </u>																
RUN:	Orion	HUD Pr	oject - F	ut with P	roj Off-P	k												
Barrier									Points									
Name	Туре	Height		If Wall	If Berm			Add'tnl	Name	No.	Coordinates	(bottom)		Height	Segment			
		Min	Max	\$ per	\$ per	Тор	Run:Rise	\$ per			x	Υ	Z	at	Seg Ht Per	turbs	On	Important
				Unit	Unit	Width		Unit						Point	Incre- #Up	#Dn	Struct?	Reflec-
				Area	Vol.			Length							ment			tions?
		ft	ft	\$/sq ft	\$/cu yd	ft	ft:ft	\$/ft			ft	ft	ft	ft	ft			
Terrain Line - top of slope wall	W	0.00	99.99	0.00				0.00	point1	1	730.5	1,101.0	211.00	14.00	0.00) ()	
									point3	3	1,080.4	1,209.3	212.00	14.00	0.00) ()	
									point4	4	1,386.0	1,311.4	212.00	14.00	0.00) C)	
									point5	5	1,533.2	1,361.4	213.00		0.00) ()	
									point6	6	,	1,424.2	215.00					
									point7	7		-	218.00					
									point8	8			220.00) ()	
									point9	9			220.00					
Barrier1-2-2-2	W	0.00	99.99	0.00	1			0.00	point47	47		1,644.5	220.00					
									point27	27	·	1,644.5	220.00					
									point28	28	· ·	1,618.6	220.00					
									point29	29		1,618.2	220.00					
									point30	30		1,632.7	220.00					
									point31 point32	31 32		1,632.2 1,679.9	220.00 220.00) (,	
Barrier1-2-2	W	0.00	99.99	0.00				0.00	point48	48			220.00) C	`	
Dairiei 1-2-2	VV	0.00	99.98	0.00	1			0.00	point20	20		1,669.1	220.00					
									point21	21		,	220.00					
									point21	22		1,570.5	220.00					
									point23	23		1,515.9	220.00				1	
									point24	24		1,516.4	220.00					
									point25	25		1,666.9	220.00			, ,	,	
Barrier1-2-2-2-2	W	0.00	99.99	0.00)			0.00		50		1,979.3	220.00) ()	
									point34	34		1,848.0	220.00					
									point35	35	1,102.6	1,855.0	220.00	45.00	0.00) ()	
									point36	36	, , , , , , , , , , , , , , , , , , ,	1,914.5	220.00					
Barrier12	W	0.00	99.99	0.00				0.00		52	1,925.6	1,804.8	220.00	14.00	0.00) ()	1
									point53	53	1,965.4	1,970.1	225.00	14.00	0.00) ()	
									point54	54	1,971.1	2,211.0	226.00	14.00				
Barrier13	W	0.00	99.99	0.00				0.00	point55	55	1,998.1	2,726.9	254.00	10.00	0.00) ()	
_									point56	56	1,998.2	2,295.6	250.00	10.00	0.00) ()	
									point57	57	1,854.9	2,282.0	245.00	10.00	0.00) ()	
									point58	58		2,257.4	240.00	10.00	0.00) ()	
									point59	59			230.00	10.00) ()	
									point60	60	1,368.2	2,146.4	222.00	10.00				

Barrier14	W	0.00	99.99	0.00		0.00	point61	61	1.373.3	2,052.9	222.00	0.00	0.00	0	0	
Ja		0.00	00.00	0.00		0.00	point62	62	1,234.2	1,990.3	222.00	0.00		0	0	
							point63	63	1,013.8	1,883.5	222.00	0.00	0.00	0	0	
							point64	64	852.8	1,810.0	221.00	0.00	0.00	0	0	
							point65	65	728.9	1,764.0	220.00	0.00	0.00	0	0	
							point66	66	728.7	1,587.9	220.00	0.00				
Barrier16	W	0.00	99.99	0.00		0.00	point67	67	602.2	1,085.9	211.00	14.00	0.00	0	0	
							point68	68	383.8	997.8	211.00	14.00				

INPUT: BUILDING ROWS			77	1	13	230	
Dudek M Greene					20 February 2 TNM 2.5	024	
INPUT: BUILDING ROWS PROJECT/CONTRACT: RUN:	13230 Orion HUD	Project - Fut	t with D				
Building Row	OHOH HOD	Froject - rui	Points				
Name	Average	Building	No.	Coordinates (ground)		
	Height	Percent		X	Υ	Z	
	ft	%		ft	ft	ft	
Building2	12.00	80	1	1,341.8	1,549.7		220.00
			2	1,368.3	1,561.9		220.00
			3	1,500.6	1,622.6		220.00
			4	1,635.1	1,763.6		220.00
			5	1,705.6	1,901.4		220.00
			6	1,729.9	2,066.7		220.00
Building4	12.00	80	9	731.5	1,300.3		220.00
			10	876.0	1,297.6		220.00
			11	898.2	1,379.5		220.00
			12	1,185.7	1,393.4		220.00
			13	1,462.0	1,443.4		220.00
			14		•		220.00
			15	1,781.4	1,723.9		220.00
			16	· ·	· ·		220.00
			17	,	· ·		220.00
Building5	12.00	80	18	598.4	1,718.1		220.00

19

598.4

1,093.6

220.00

		1				-						
Dudek							20 Februa	m, 2024				
M Greene							TNM 2.5	ii y 2024				
W Greene								d with TNN	125			
RESULTS: SOUND LEVELS							Calculate	u with Hill	2.3			
PROJECT/CONTRACT:		13230										
RUN:			IIID Projec	t - Fut with Pi	roi Off Pk							
BARRIER DESIGN:			HEIGHTS	t - Fut With Pi	oj Oli-PK			Avorago r	avoment type	e shall be use	d unloce	
BARRIER DESIGN.		INFOI	IILIGIIIG							y substantiate)
ATMOSPHERICS:		68 deg	F, 50% RH							approval of F		
Receiver				-			-					
Name	No.	#DUs	Existing	No Barrier					With Barrier			
			LAeq1h	LAeq1h		Increase over	existing	Туре	Calculated	Noise Reduc	tion	
			-	Calculated	Crit'n	Calculated	Crit'n	Impact	LAeq1h	Calculated	Goal	Calculated
							Sub'l Inc	-	-			minus
												Goal
			dBA	dBA	dBA	dB	dB		dBA	dB	dB	dB
M1-1	1	1	0.0	62.7	66	62.7	10		62.7	0.0		8 -8.0
M2-1	2	1	0.0	57.9	66	57.9	10		57.9	0.0		8 -8.0
M3-1	3	1	0.0	57.7	66	57.7	' 10		57.7	0.0		8 -8.0
M4-1	4	1	0.0	58.4	66	58.4	10		58.4	0.0		8 -8.0
M5-1	5	1	0.0	60.3	66	60.3	3 10		60.3	0.0		8 -8.0
M6-1	6	1	0.0	67.4	66	67.4	10	Snd Lvl	67.4	0.0		8 -8.0
M7-1	7	1	0.0	68.2	66	68.2	2 10	Snd Lvl	68.2	0.0		8 -8.0
M8-1	8	1	0.0	63.8	66	63.8	3 10		63.8	0.0		8 -8.0
M9-1	9	1	0.0	57.7	66	57.7	' 10		57.7	0.0		8 -8.0
M10-1	10	1	0.0	61.4	66	61.4	10		61.4	0.0		8 -8.0
M1-2	12	1	0.0			64.2	2 10		64.2	0.0		-8.0
M2-2	13		0.0	61.2	66	61.2	2 10		61.2			8 -8.0
M3-2	14	1	0.0	62.5	66	62.5	5 10		62.5	0.0		-8.0
M4-2	15	1	0.0	63.2	66	63.2	2 10		63.2	0.0		-8.0
M5-2	16	1	0.0	62.9					62.9	0.0		8 -8.0
M6-2	17	1	0.0	68.1			10		68.1	0.0		8 -8.0
M7-2	18		0.0					Snd Lvl	68.0	0.0		8 -8.0
M8-2	19								64.2			8 -8.0
M9-2	20								61.1			8 -8.0
M10-2	21	1							62.0			8 -8.0
M1-3	22								64.9			8 -8.0
M2-3	24								63.5			8 -8.0
M3-3	25								64.5			-8.0
M4-3	26	1	0.0	64.9	66	64.9	10		64.9	0.0		-8.0

RESULTS: SOUND LEVELS							13	3230					
M5-3	27	1	0.	0	63.7	66	63.7	10		63.7	0.0	8	-8.0
M6-3	28	1	0.	0	68.0	66	68.0	10	Snd Lvl	68.0	0.0	8	- 8.0
M7-3	29	1	0.	0	67.7	66	67.7	10	Snd Lvl	67.7	0.0	8	-8.0
M8-3	30	1	0.	0	64.0	66	64.0	10		64.0	0.0	8	-8.0
M9-3	31	1	0.	0	63.0	66	63.0	10		63.0	0.0	8	-8.0
M10-3	32	1	0.	0	62.0	66	62.0	10		62.0	0.0	8	-8.0
M1-4	33	1	0.	0	65.9	66	65.9	10		65.9	0.0	8	-8.0
M2-4	34	1	0.	0	65.0	66	65.0	10		65.0	0.0	8	-8.0
M3-4	35	1	0.	0	65.7	66	65.7	10		65.7	0.0	8	-8.0
M4-4	36	1	0.	0	66.0	66	66.0	10	Snd Lvl	66.0	0.0	8	-8.0
M5-4	38	1	0.	0	64.6	66	64.6	10		64.6	0.0	8	-8.0
M6-4	39	1	0.	0	67.8	66	67.8	10	Snd Lvl	67.8	0.0	8	-8.0
M7-4	41	1	0.	0	67.4	66	67.4	10	Snd Lvl	67.4	0.0	8	-8.0
M8-4	42	1	0.	0	64.0	66	64.0	10		64.0	0.0	8	-8.0
M9-4	43	1	0.	0	64.2	66	64.2	10		64.2	0.0	8	-8.0
M10-4	44	1	0.	0	62.0	66	62.0	10		62.0	0.0	8	- 8.0
M11	46	1	0.	0	57.7	66	57.7	10		57.7	0.0	8	- 8.0
M12	47	1	0.	0	58.8	66	58.8	10		58.8	0.0	8	-8.0
M13	48	1	0.	0	56.3	66	56.3	10		56.3	0.0	8	- 8.0
M14	49	1	0.	0	62.5	66	62.5	10		62.5	0.0	8	-8.0
Dwelling Units		# DUs	Noise R	eduction									
			Min	Avg		Max							
			dB	dB		dB							
All Selected		44	0.	0	0.0	0.0							
All Impacted		9	0.	0	0.0	0.0							

0.0

0.0

0.0

All that meet NR Goal

Dudek												
M Greene					TNM 2	5						
INPUT: ROADWAYS PROJECT/CONTRACT:	13230							_	pavement typ			
RUN:		D Project	- Fut w Pro	j Nighttime	•				rent type with			
Roadway		Points										
Name	Width	Name	No. Co	oordinates	y (paver	-	Z	Flow Cor Control Device	Speed Constraint	Percent Vehicles Affected	Segment Pvmt Type	On Struct?
	ft		ft		ft		ft		mph	%		
La Veta Ave	55.0	point1	1	2,346.0) :	2,236.2	255.00)			Average	
Lu void / Wo	00.0	point3	3	2,111.6		2,250.2					Average	
		point4	4	1,980.3		2,248.1	250.00				Average	
		point5	5	1,837.0		2,234.5					Average	
		point6	6	1,703.0		2,209.9					Average	
		point7	7	1,526.6		2,166.1	230.00)			Average	
		point8	8	1,350.3		2,098.9	222.00)			Average	
		point9	9	1,211.2	2 2	2,036.3	222.00)			Average	
		point10	10	990.8	3	,929.5	222.00)			Average	
		point11	11	829.8	3	,856.0	221.00)			Average	
		point12	12	705.9	9	1,810.0	220.00)				
SR55NB	80.0	point51	51	2,144.8	3	748.2	216.00)			Average	
		point20	20	2,141.8	3	,364.8	222.00)			Average	
		point21	21	2,127.9	9 2	2,095.2	227.00)			Average	
		point57	57	2,129.6	3 2	2,234.9	229.00)				
SR22 WB - 1	35.0		52	1,992.9		2,195.8					Average	
		point24	24	1,985.9		1,970.1	225.00				Average	
		point25	25	1,938.6		1,771.5					Average	
		point26	26	1,878.3		1,634.2					Average	
		point27	27	1,786.4		,502.9					Average	
		point28	28	1,680.2		1,389.8					Average	
		point29	29	1,528.1		1,287.7					Average	
		point30	30	1,333.9		1,214.2					Average	
		point31	31	767.4		1,043.4					Average	
		point32	32	731.6	6	8.080,1	190.00)				

INPUT: ROADWAYS 13230

S Tustin Avenue	85.0	point53	53	674.9	960.9	213.00	Average
		point14	14	672.8	1,004.7	215.00	Average
		point15	15	674.2	1,297.0	218.00	Average
		point16	16	678.4	1,610.8	220.00	Average
		point17	17	688.9	1,815.5	224.00	Average
		point18	18	671.4	2,672.9	220.00	
SR22 EB - 2	35.0	point54	54	414.8	907.2	0.00	Average
		point2	2	632.1	971.1	0.00	
SR22 EB - 1	35.0	point55	55	731.6	1,005.8	189.00	Average
		point34	34	776.2	1,020.3	190.00	Average
		point35	35	1,225.4	1,136.2	190.00	Average
		point36	36	1,335.6	1,149.3	190.00	Average
		point37	37	1,457.2	1,156.3	190.00	Average
		point38	38	1,604.2	1,135.3	190.00	Average
		point39	39	1,805.4	1,056.6	190.00	Average
		point40	40	1,946.3	956.8	190.00	Average
		point41	41	2,019.8	858.0	190.00	
SR22 WB - 2	35.0	point56	56	630.0	997.5	192.00	Average
		point43	43	406.5	933.0	192.00	
SR55-2NB	80.0	point59	59	2,130.8	2,298.5	230.00	Average
		point58	58	2,133.3	2,573.6	234.00	Average
		point22	22	2,135.2	2,806.9	236.00	
SR55SB	80.0	point62	62	2,058.4	748.2	216.00	Average
		point63	63	2,052.8	1,364.8	222.00	Average
		point64	64	2,038.9	2,095.2	227.00	Average
		point65	65	2,043.1	2,234.9	229.00	
SR55-2SB	80.0	point66	66	2,039.3	2,295.3	230.00	Average
		point67	67	2,041.8	2,570.4	234.00	Average
		point68	68	2,043.7	2,803.7	236.00	

Dudek M Greene				20 Feb	ruary 20	24						
W Greene				I INIVI 2								
INPUT: TRAFFIC FOR LAeq1h Volumes PROJECT/CONTRACT: RUN:	13230 Orion HUD	Project - I	Fut w Pro	oj Night	ttime							
Roadway	Points											
Name	Name	No.	Segmen	it								
			Autos		MTruck	S	HTrucks	5	Buses		Motorcy	cles
			V	S	V	S	V	S	V	S	V	S
			veh/hr	mph	veh/hr	mph	veh/hr	mph	veh/hr	mph	veh/hr	mph
La Veta Ave	point1	1	164	40	3	4			0) () (0
	point3	3	164	40	3	4	0 2	35	0) () (0
	point4	4	164	40	3	4		1	0	(0	0
	point5	5	164	40	3	4	0 2	35	0	(0	0
	point6	6	164	40	3	4	0 2	35	0) () (0
	point7	7	164	40	3	4	0 2	35	0) () (0
	point8	8	164	40	3	4		1	0) (0	0
	point9	9	164	40	3	4	0 2	35	0	(0	0
	point10	10	164	40	3	4	0 2	35	0) () (0
	point11	11	164	40	3	4	0 2	35	0) () (0
	point12	12										
SR55NB	point51	51	1938	65	72	6	5 49	60	0	(0	0
	point20	20	1938	65	72	6	5 49	60	0) (0	0
	point21	21	1938	65	72	6	5 49	60	0	(0	0
	point57	57										
SR22 WB - 1	point52	52	1297	65	25	6	5 19	60	0	(0	0
	point24	24	1297	65			5 19	60	0) (0 0	0
	point25	25	1297	65	25	6	5 19	60	0) (0	0
	point26	26	1297	65	25	6	5 19	60	0	(0	0
	point27	27	1297	65	25	6	5 19	60	0) (0	0
	point28	28	1297	65	25	6	5 19	60	0) () (0
	point29	29	1297	65	25	6	5 19	60	0) () (0
	point30	30	1297	65	25	6	5 19	60	0) () (0 0

NPUT: TRAFFIC FOR LAeq1h	Volumes					13230)					
•	point31	31	1297	65	25	65	19	60	0	0	0	0
	point32	32										
S Tustin Avenue	point53	53	474	40	10	40	5	35	0	0	0	C
	point14	14	474	40	10	40	5	35	0	0	0	0
	point15	15	474	40	10	40	5	35	0	0	0	0
	point16	16	474	40	10	40	5	35	0	0	0	0
	point17	17	474	40	10	40	5	35	0	0	0	0
	point18	18										
SR22 EB - 2	point54	54	1297	65	25	65	19	60	0	0	0	0
	point2	2										
SR22 EB - 1	point55	55	1297	65	25	65	19	60	0	0	0	0
	point34	34	1297	65	25	65	19	60	0	0	0	0
	point35	35	1297	65	25	65	19	60	0	0	0	0
	point36	36	1297	65	25	65	19	60	0	0	0	0
	point37	37	1297	65	25	65	19	60	0	0	0	0
	point38	38	1297	65	25	65	19	60	0	0	0	0
	point39	39	1297	65	25	65	19	60	0	0	0	0
	point40	40	1297	65	25	65	19	60	0	0	0	0
	point41	41										
SR22 WB - 2	point56	56	1297	65	25	65	19	60	0	0	0	0
	point43	43										
SR55-2NB	point59	59	1938	65	72	65	49	60	0	0	0	0
	point58	58	1938	65	72	65	49	60	0	0	0	0
	point22	22										
SR55SB	point62	62	1938	65	72	65	49	60	0	0	0	0
	point63	63	1938	65	72	65	49	60	0	0	0	0
	point64	64	1938	65	72	65	49	60	0	0	0	0
	point65	65										
SR55-2SB	point66	66	1938	65	72	65	49	60	0	0	0	0
	point67	67	1938	65	72	65	49	60	0	0	0	0
	point68	68										

INPUT: RECEIVERS	13230
------------------	-------

INPUT: RECEIVERS								1	3230			
Dudek							20 Februa	ry 2024				
M Greene							TNM 2.5					
INPUT: RECEIVERS												
PROJECT/CONTRACT:	13230											
RUN:	Orion Hl	JD Pro	ject - Fut w	Proj Nighttin	ne							
Receiver												
Name	No. #[OUs C	oordinates	(ground)			Height	Input Soul	nd Levels a	and Criteria	a	Active
		X		Y	Z		above	-	Impact Cr		NR	in
							Ground	LAeq1h	LAeq1h	Sub'l	Goal	Calc.
								-	-			
		ft		ft	ft		ft	dBA	dBA	dB	dB	
M1-1	1	1	1,267.7	1,981.3		220.00	5.00	0.00	66	10.0	8.0	0 Y
M2-1	2	1	1,273.4	1,850.1		220.00	5.00	0.00	66	10.0	8.0	0 Y
M3-1	3	1	1,230.3	1,669.0		220.00	5.00	0.00	66	10.0	8.0	0 Y
M4-1	4	1	1,212.9	1,614.5		220.00	5.00	0.00	66	10.0	8.0	0 Y
M5-1	5	1	853.7	1,515.0		220.00	5.00	0.00	66	10.0	8.0	0 Y
M6-1	6	1	742.4	1,514.7		220.00	5.00	0.00	66	10.0	8.0	0 Y
M7-1	7	1	732.9	1,658.0		220.00	5.00	0.00	66	10.0	8.0	0 Y
M8-1	8	1	767.4	1,671.8		220.00	5.00	0.00	66	10.0	8.0	0 Y
M9-1	9	1	1,168.3	1,725.5		220.00	5.00	0.00	66	10.0	8.0	0 Y
M10-1	10	1	1,157.2	1,921.1		220.00	5.00	0.00	66	10.0	8.0	0 Y
M1-2	12	1	1,267.7	1,981.3		220.00	15.00	0.00	66	10.0	8.0	0 Y
M2-2	13	1	1,273.4	1,850.1		220.00	15.00	0.00	66	10.0	8.0	0 Y
M3-2	14	1	1,230.3	1,669.0		220.00	15.00	0.00	66	10.0	8.0	
M4-2	15	1	1,212.9	1,614.5		220.00	15.00	0.00	66	10.0	8.0	0 Y
M5-2	16	1	853.7			220.00	15.00	0.00	66	10.0	8.0	
M6-2	17	1	742.4			220.00		0.00				
M7-2	18	1	732.9	· ·		220.00		0.00				
M8-2	19	1	767.4	· ·		220.00		0.00	66	10.0	8.0	
M9-2	20	1	1,168.3	1,725.5		220.00	15.00	0.00	66	10.0	8.0	0 Y
M10-2	21	1	1,157.2			220.00		0.00				
M1-3	22	1	1,267.7	1,981.3		220.00	25.00	0.00	66	10.0	8.0	
M2-3	24	1	1,273.4	1,850.1		220.00	25.00	0.00	66	10.0	8.0	0 Y

INPUT: RECEIVERS							133	230			
M3-3	25	1	1,230.3	1,669.0	220.00	25.00	0.00	66	10.0	8.0	Υ
M4-3	26	1	1,212.9	1,614.5	220.00	25.00	0.00	66	10.0	8.0	Υ
M5-3	27	1	853.7	1,515.0	220.00	25.00	0.00	66	10.0	8.0	Υ
M6-3	28	1	742.4	1,514.7	220.00	25.00	0.00	66	10.0	8.0	Υ
M7-3	29	1	732.9	1,658.0	220.00	25.00	0.00	66	10.0	8.0	Υ
M8-3	30	1	767.4	1,671.8	220.00	25.00	0.00	66	10.0	8.0	Υ
M9-3	31	1	1,168.3	1,725.5	220.00	25.00	0.00	66	10.0	8.0	Υ
M10-3	32	1	1,157.2	1,921.1	220.00	25.00	0.00	66	10.0	8.0	Υ
M1-4	33	1	1,267.7	1,981.3	220.00	35.00	0.00	66	10.0	8.0	Υ
M2-4	34	1	1,273.4	1,850.1	220.00	35.00	0.00	66	10.0	8.0	Υ
M3-4	35	1	1,230.3	1,669.0	220.00	35.00	0.00	66	10.0	8.0	Υ
M4-4	36	1	1,212.9	1,614.5	220.00	35.00	0.00	66	10.0	8.0	Υ
M5-4	38	1	853.7	1,515.0	220.00	35.00	0.00	66	10.0	8.0	Υ
M6-4	39	1	742.4	1,514.7	220.00	35.00	0.00	66	10.0	8.0	Υ
M7-4	41	1	732.9	1,658.0	220.00	35.00	0.00	66	10.0	8.0	Υ
M8-4	42	1	767.4	1,671.8	220.00	35.00	0.00	66	10.0	8.0	Υ
M9-4	43	1	1,168.3	1,725.5	220.00	35.00	0.00	66	10.0	8.0	Υ
M10-4	44	1	1,157.2	1,921.1	220.00	35.00	0.00	66	10.0	8.0	Υ
M11	46	1	1,154.7	1,818.0	220.00	5.00	0.00	66	10.0	8.0	
M12	47	1	1,212.5	1,592.0	220.00	5.00	0.00	66	10.0	8.0	
M13	48	1	811.2	1,603.0	220.00	5.00	0.00	66	10.0	8.0	
M14	49	1	876.2	1,743.0	220.00	5.00	0.00	66	10.0	8.0	Υ

INPUT: BARRIERS 13230

Dudek					20 Febr		24											
M Greene					TNM 2.5	•	24											
M Greene					I INIVI 2.5	,												
INPUT: BARRIERS																		
PROJECT/CONTRACT:	13230)																
RUN:	Orion	HUD Pr	oject - F	ut w Pro	j Nighttin	ne												
Barrier									Points									
Name	Type	Height		If Wall	If Berm			Add'tnl	Name	No.	Coordinates	(bottom)		Height	Segment			
		Min	Max	\$ per	\$ per	Тор	Run:Rise	\$ per			x		Z	at	Seg Ht Peri	turbs	On	Important
				Unit	Unit	Width		Unit						Point	Incre- #Up			Reflec-
				Area	Vol.			Length							ment			tions?
		ft	ft	\$/sq ft	\$/cu yd	ft	ft:ft	\$/ft			ft	ft	ft	ft	ft			
Terrain Line - top of slope wall	W	0.00	99.99	0.00				0.00	point1	1	730.5	1,101.0	211.00	14.00	0.00) ()	
									point3	3	1,080.4	1,209.3	212.00	14.00	0.00) ()	
									point4	4	1,386.0	1,311.4	212.00	14.00	0.00) ()	
									point5	5	1,533.2	1,361.4	213.00	14.00	0.00) ()	
									point6	6	1,648.9	1,424.2	215.00	14.00	0.00) ()	
									point7	7	1,787.8	1,552.0	218.00	14.00	0.00) ()	
									point8	8	1,877.5	1,695.5	220.00	14.00	0.00) ()	
									point9	9	1,925.6	1,804.8	220.00	14.00				
Barrier1-2-2-2	W	0.00	99.99	0.00				0.00	point47	47	1,104.9	1,644.5	220.00	45.00	0.00) ()	
									point27	27	1,135.1	1,644.5	220.00	45.00	0.00) C)	
									point28	28	1,135.5	1,618.6	220.00	45.00	0.00) ()	
									point29	29	1,214.7	1,618.2	220.00	45.00	0.00) ()	
									point30	30	1,215.1	1,632.7	220.00	45.00	0.00) ()	
									point31	31	,	1,632.2	220.00	45.00) ()	
									point32	32		1,679.9	220.00	45.00				
Barrier1-2-2	W	0.00	99.99	0.00				0.00	point48	48	737.9	1,669.7	220.00	45.00	0.00) ()	
									point20	20		1,669.1	220.00	45.00)	
									point21	21			220.00	45.00) ()	
									point22	22		1,570.5	220.00	45.00			1	
									point23	23		1,515.9	220.00	45.00				
									point24	24		1,516.4	220.00	45.00) ()	
									point25	25		1,666.9	220.00	45.00				
Barrier1-2-2-2-2	W	0.00	99.99	0.00				0.00		50		1,979.3	220.00	45.00				
									point34	34	,	1,848.0	220.00	45.00				
									point35	35	,	1,855.0	220.00	45.00) ()	
									point36	36	,	1,914.5	220.00	45.00				
Barrier12	W	0.00	99.99	0.00				0.00		52	·	1,804.8	220.00	14.00			1	
									point53	53	ļ	1,970.1	225.00	14.00) ()	
Demi-n42	14.	0.00	00.00	0.00				0.00	point54	54		2,211.0	226.00	14.00		, ,		
Barrier13	W	0.00	99.99	0.00				0.00	· ·	55		2,726.9	254.00	10.00				
									point56	56		2,295.6	250.00	10.00				
									point57	57		2,282.0	245.00	10.00				
									point58	58		2,257.4	240.00	10.00				
									point59	59			230.00	10.00		, (J	
									point60	60	1,368.2	2,146.4	222.00	10.00				

INPUT: BARRIERS 13230


Barrier14	W	0.00	99.99	0.00		0.00 point6	l 61	1,373.3	2,052.9	222.00	0.00	0.00	0	0	
						point6	2 62	1,234.2	1,990.3	222.00	0.00	0.00	0	0	
						point6	3 63	1,013.8	1,883.5	222.00	0.00	0.00	0	0	
						point6	4 64	852.8	1,810.0	221.00	0.00	0.00	0	0	
						point6	5 65	728.9	1,764.0	220.00	0.00	0.00	0	0	
						point6	66	728.7	1,587.9	220.00	0.00				
Barrier15	W	0.00	99.99	0.00		0.00 point6	7 67	602.2	1,085.9	211.00	14.00	0.00	0	0	
						point6	3 68	383.8	997.8	211.00	14.00				

INPUT: BUILDING ROWS					13	230
Dudek M Greene					20 February 2 TNM 2.5	024
INPUT: BUILDING ROWS PROJECT/CONTRACT: RUN:	13230 Orion HUD	Project - Fut	tw Pro	i		
	Onon Hob	Project - Ful	Points			
Building Row Name	Average	Building	No.	s Coordinates (around)	
Ivaille	Height	Percent	140.	X	Y	z
	ft	%		ft	ft	ft
Building2	12.00	80	1	1,341.8	1,549.7	220.00
			2		· ·	
			3	3 1,500.6	1,622.6	220.00
			4	1,635.1	1,763.6	220.00
			5	1,705.6	1,901.4	220.00
			6	1,729.9	2,066.7	220.00
Building4	12.00	80	9	731.5	1,300.3	220.00
			10	876.0	1,297.6	220.00
			11	898.2	1,379.5	220.00
			12	1,185.7	1,393.4	220.00
			13	1,462.0	1,443.4	220.00
			14	1,667.6	1,567.0	220.00
			15	•	1	
			16		1	
			17	,	*	220.00
Building5	12.00	80			,	
			19	598.4	1,093.6	220.00

		1				•						
Dudek							20 Februa	rv 2024				
M Greene							TNM 2.5	.y 2024				
in Greene							Calculated	l with TN	M 2 5			
RESULTS: SOUND LEVELS							Guiodiatot		1111 2.0			
PROJECT/CONTRACT:		13230										
RUN:			HIID Projec	t - Fut w Proj	Nighttime							
BARRIER DESIGN:			HEIGHTS		itigiittiiio			Average	pavement type	e shall he use	d unless	
BARRIER BEGIGIT.			IILIGIIIG					_	nighway agenc			
ATMOSPHERICS:		68 deg	F, 50% RH	<u> </u>					erent type with			
Receiver		<u> </u>	, ,				-		J .	1.	+	
Name	No.	#DUs	Existing	No Barrier			-		With Barrier			
Truine	110.	# D 03	LAeq1h	LAeq1h		Increase over	evisting	Туре	Calculated	Noise Reduc	tion	
			LACGIII	Calculated	Crit'n	Calculated	Crit'n	Impact	LAeq1h	Calculated	Goal	Calculated
				Galculatea	Ontin	Galculatea	Sub'l Inc	IIIIpact	LACGIII	Galculatea	Joan	minus
							Oub i iiic					Goal
			dBA	dBA	dBA	dB	dB		dBA	dB	dB	dB
M1-1	1		1 0.0						57.2			
M2-1	2								52.4		1	
M3-1	3		1 0.0						52.1			
M4-1	4		1 0.0						52.8			
M5-1	5		1 0.0						54.8			
M6-1	6								61.9			
M7-1	7								62.6			
M8-1	8		1 0.0						58.2			
M9-1	9		1 0.0						52.1			
M10-1	10								55.8			
M1-2	12								58.7		1	
M2-2	13		1 0.0						55.7	7 0.0	8	
M3-2	14		0.0			57.0) 10		57.0	0.0	8	
M4-2	15		0.0	57.6	66	57.6	5 10		57.6	0.0	8	-8.0
M5-2	16		0.0	57.4	66	57.4	10		57.4	0.0	8	-8.0
M6-2	17		0.0	62.6	66	62.6	5 10		62.6	0.0	8	-8.0
M7-2	18		0.0	62.4	66	62.4	10		62.4	1 0.0	8	-8.0
M8-2	19		0.0	58.6	66	58.6	5 10		58.6	0.0	8	-8.0
M9-2	20		0.0	55.5	66	55.5	5 10		55.5	0.0	8	-8.0
M10-2	21	•	0.0	56.5	66	56.5	5 10		56.5	0.0	8	-8.0
M1-3	22		0.0	59.4	66	59.4	10		59.4	1 0.0	8	-8.0
M2-3	24	•	0.0	57.9	66	57.9	10		57.9	0.0	8	-8.0
M3-3	25	•	0.0	58.9	66	58.9	10		58.9	0.0	8	
M4-3	26	1	0.0	59.3	66	59.3	3 10		59.3	0.0	8	-8.0

RESULTS: SOUND LEVELS							13	3230				
M5-3	27	1	0.) 5	58.2	66	58.2	10	 58.2	0.0	8	-8.0
M6-3	28	1	0.) 6	62.4	66	62.4	10	 62.4	0.0	8	-8.0
M7-3	29	1	0.) 6	62.2	66	62.2	10	 62.2	0.0	8	-8.0
M8-3	30	1	0.) 5	58.5	66	58.5	10	 58.5	0.0	8	-8.0
M9-3	31	1	0.) 5	57.4	66	57.4	10	 57.4	0.0	8	-8.0
M10-3	32	1	0.) 5	56.4	66	56.4	10	 56.4	0.0	8	-8.0
M1-4	33	1	0.) 6	60.3	66	60.3	10	 60.3	0.0	8	-8.0
M2-4	34	1	0.) 5	59.4	66	59.4	10	 59.4	0.0	8	-8.0
M3-4	35	1	0.) 6	60.1	66	60.1	10	 60.1	0.0	8	-8.0
M4-4	36	1	0.) 6	60.4	66	60.4	10	 60.4	0.0	8	-8.0
M5-4	38	1	0.) 5	59.0	66	59.0	10	 59.0	0.0	8	-8.0
M6-4	39	1	0.) 6	62.2	66	62.2	10	 62.2	0.0	8	-8.0
M7-4	41	1	0.) 6	61.9	66	61.9	10	 61.9	0.0	8	-8.0
M8-4	42	1	0.) 5	58.4	66	58.4	10	 58.4	0.0	8	-8.0
M9-4	43	1	0.) 5	58.7	66	58.7	10	 58.7	0.0	8	-8.0
M10-4	44	1	0.) 5	56.5	66	56.5	10	 56.5	0.0	8	-8.0
M11	46	1	0.) 5	52.1	66	52.1	10	 52.1	0.0	8	-8.0
M12	47	1	0.) 5	53.2	66	53.2	10	 53.2	0.0	8	-8.0
M13	48	1	0.) 5	50.7	66	50.7	10	 50.7	0.0	8	-8.0
M14	49	1	0.) 5	57.0	66	57.0	10	 57.0	0.0	8	-8.0
Dwelling Units		# DUs	Noise Re	duction								
			Min	Avg		Мах						
			dB	dB		dB						
All Selected		44	0.)	0.0	0.0						
All Impacted		0	0.)	0.0	0.0						
All that meet NR Goal		0	0.)	0.0	0.0						

Attachment 15. Sole Source Aquifer Map



Attachment 16. National Wetlands Inventory Map



☐ Riparian Mapping Areas

O Source Type

O Image Scale


O Image Year

☑ Data Source

☐ Areas of Interest

☐ FWS Managed Lands


☐ Historic Wetland Data



Q FIND LOCATION

Attachment 17. Wild and Scenic Rivers Map





Attachment 18. EJScreen Community Report

\$EPA

EJScreen Community Report


This report provides environmental and socioeconomic information for user-defined areas, and combines that data into environmental justice and supplemental indexes.

Orange, CA


0.125 miles Ring Centered at 33.779390,-117.833980

Population: 722

Area in square miles: 0.05




COMMUNITY INFORMATION



LANGUAGES SPOKEN AT HOME

LANGUAGE	PERCENT
No language data available.	

BREAKDOWN BY RACE



BREAKDOWN BY AGE

From Ages 1 to 4	9%
From Ages 1 to 18	25%
From Ages 18 and up	75%
From Ages 65 and up	14%

LIMITED ENGLISH SPEAKING BREAKDOWN



Notes: Numbers may not sum to totals due to rounding. Hispanic population can be of any race. Source: U.S. Census Bureau, American Community Survey (ACS) 2017-2021. Life expectancy data comes from the Centers for Disease Control.


Environmental Justice & Supplemental Indexes

The environmental justice and supplemental indexes are a combination of environmental and socioeconomic information. There are thirteen EJ indexes and supplemental indexes in EJScreen reflecting the 13 environmental indicators. The indexes for a selected area are compared to those for all other locations in the state or nation. For more information and calculation details on the EJ and supplemental indexes, please visit the EJScreen website.

EJ INDEXES

The EJ indexes help users screen for potential EJ concerns. To do this, the EJ index combines data on low income and people of color populations with a single environmental indicator.


EJ INDEXES FOR THE SELECTED LOCATION



SUPPLEMENTAL INDEXES

The supplemental indexes offer a different perspective on community-level vulnerability. They combine data on percent low-income, percent linguistically isolated, percent less than high

SUPPLEMENTAL INDEXES FOR THE SELECTED LOCATION



 $These \ percentiles \ provide \ perspective \ on \ how \ the \ selected \ block \ group \ or \ buffer \ area \ compares \ to \ the \ entire \ state \ or \ nation.$

Report for 0.125 miles Ring Centered at 33.779390,-117.833980

 \equiv

EJScreen Environmental and Socioeconomic Indicators Data

SELECTED VARIABLES	VALUE	STATE AVERAGE	PERCENTILE IN STATE	USA AVERAGE	PERCENTILE IN USA
POLLUTION AND SOURCES					
Particulate Matter (µg/m³)	10.5	8.65	79	8.08	97
Ozone (ppb)	69.9	65.9	69	61.6	93
Diesel Particulate Matter (µg/m³)	0.353	0.26	73	0.261	77
Air Toxics Cancer Risk* (lifetime risk per million)	30	27	42	25	52
Air Toxics Respiratory HI*	0.4	0.34	58	0.31	70
Toxic Releases to Air	2,000	780	89	4,600	73
Traffic Proximity (daily traffic count/distance to road)	4,800	510	99	210	99
Lead Paint (% Pre-1960 Housing)	0	0.31	0	0.3	0
Superfund Proximity (site count/km distance)	0.082	0.17	49	0.13	60
RMP Facility Proximity (facility count/km distance)	0.19	0.57	45	0.43	55
Hazardous Waste Proximity (facility count/km distance)	7.8	5.9	71	1.9	94
Underground Storage Tanks (count/km²)	0	1.5	0	3.9	0
Wastewater Discharge (toxicity-weighted concentration/m distance)	0.22	4	72	22	86
SOCIOECONOMIC INDICATORS					
Demographic Index	56%	45%	69	35%	80
Supplemental Demographic Index	17%	15%	64	14%	68
People of Color	61%	61%	47	39%	73
Low Income	52%	28%	85	31%	82
Unemployment Rate	2%	7%	20	6%	29
Limited English Speaking Households	0%	9%	0	5%	0
Less Than High School Education	14%	16%	57	12%	68
Under Age 5	9%	6%	83	6%	83
Over Age 64	14%	16%	51	17%	42
Low Life Expectancy	17%	18%	48	20%	30

*Diesel particulate matter, air toxics cancer risk, and air toxics respiratory has air dinds are from the EPA's Air Toxics Data Update, which is the Agency's ongoing, comprehensive evaluation of a triance is the United States. This effort aims to prioritize air toxics, emission sources, and locations of health risks over geographic areas of the country, not definitive risks to specific individuals or locations. Cancer risks and hazard indices from the Air Toxics Data Update are reported to one significant figure and any additional significant figures here are due to rounding. More information on the Air Toxics Data Update found at: https://www.epa.gov/haps/air-toxics-data-update.

Sites reporting to EPA within defined area:

Superfund	0
Hazardous Waste, Treatment, Storage, and Disposal Facilities	0
Water Dischargers	0
Air Pollution	0
Brownfields	0
Toxic Release Inventory	0

Other community features within defined area:

Schools 0	
Hospitals 0	
Places of Worship	

Other environmental data:

Air Non-attainment	Yes
Impaired Waters	Yes

Selected location contains American Indian Reservation Lands*	No
Selected location contains a "Justice40 (CEJST)" disadvantaged community	No
Selected location contains an EPA IRA disadvantaged community	No

Report for 0.125 miles Ring Centered at 33.779390,-117.833980

EJScreen Environmental and Socioeconomic Indicators Data

HEALTH INDICATORS								
INDICATOR	VALUE	STATE AVERAGE	STATE PERCENTILE	US AVERAGE	US PERCENTILE			
Low Life Expectancy	17%	18%	48	20%	30			
Heart Disease	5.3	5.2	59	6.1	35			
Asthma	9.7	9.5	56	10	46			
Cancer	5.5	5.3	59	6.1	35			
Persons with Disabilities	8.1%	10.9%	29	13.4%	19			

CLIMATE INDICATORS						
INDICATOR	VALUE	STATE AVERAGE	STATE PERCENTILE	US AVERAGE	US PERCENTILE	
Flood Risk	6%	13%	51	12%	48	
Wildfire Risk	0%	30%	0	14%	0	

CRITICAL SERVICE GAPS								
INDICATOR	VALUE	STATE AVERAGE	STATE PERCENTILE	US AVERAGE	US PERCENTILE			
Broadband Internet	10%	10%	62	14%	48			
Lack of Health Insurance	17%	7%	94	9%	87			
Housing Burden	No	N/A	N/A	N/A	N/A			
Transportation Access	No	N/A	N/A	N/A	N/A			
Food Desert	No	N/A	N/A	N/A	N/A			

Report for 0.125 miles Ring Centered at 33.779390,-117.833980

Attachment 19. Preliminary Traffic Analysis



To: Doug Keys, Transportation Analyst, City of Orange

From: Daniel Hendricks, Associate Transportation Planner, Crain & Associates

Subject: Preliminary Traffic Analysis for the Senior Affordable Housing Project at 1800 E. La Veta

Avenue, City of Orange, CA

USA Properties (the "Client") is preparing a formal entitlement application for the proposed affordable senior housing community (the "Project") located at 1800 E. La Veta Avenue in the City of Orange, California, (the "City"). The Project consists of the development of 166 senior affordable residential housing units and ancillary amenity space across three buildings. The site is currently occupied by the main campus of the Rehabilitation Institute of Southern California (RIO). The RIO is relocating their main campus, and the existing RIO buildings will be removed to accommodate the Project. As a development project consisting entirely of affordable housing and located within a one-half mile of fixed route bus service, the Project will provide reduced on-site parking below the amount required by the City's Zoning Code. As part of the formal entitlement package, the City's Public Works department has requested that a preliminary traffic analysis be prepared for the Project. Crain & Associates is assisting the Client by providing transportation planning services to prepare and process the Project's preliminary traffic analysis with the City. Outlined below are an estimate of the Project trip generation and trip distribution percentages to assist in the determination of whether additional transportation analysis will be required of the proposed Project.

PRELIMINARY TRAFFIC ANALYSIS

PROJECT DESCRIPTION

The Project site is an approximately 3.85 acre parcel located at the southeast corner of Tustin Street & La Veta Avenue. The site is located immediately northwest of the interchange between the Costa Mesa Freeway (State Route 55 [SR-55]) and Garden Grove Freeway (SR-22). The site is bounded by La Veta Avenue to the north, Tustin Street to the west, Fairway Drive and a multifamily residential building to the south, and a multifamily housing development to the east. The Project consists of the development of three mid-rise residential building spread across the Project site, which will house 166 senior affordable housing units along with residential amenity spaces, including a clubroom, computer area, and fitness room. The site currently houses the RIO main campus, which consists of the 34,300 square-foot main building and a 2,110 square-foot ancillary outhouse. Both of these existing buildings will be removed in conjunction with the development of the Project. The Project site also contains a 40-unit senior affordable housing development that will remain after the completion of the Project. Since the Project consists entirely of affordable housing and is located with a one-half mile of fixed route bus service, the Project will provide 169 surface automobile spaces, which is less than the amount required by the City's Zoning Code. Of these 169 spaces, three will be set aside for the community leasing office and 166 will be reserved for community residents and guests.

PROJECT SITE PLAN AND ACCESS

Figure 1 shows the Project site plan. The Project site would be accessed via La Veta Avenue and Fairway Drive. The Project proposes to maintain the existing western driveway along La Veta Avenue as the primary site driveway. The existing middle driveway along Fairway Drive, which currently provides access to a small parking and loading area, will be maintained and will provide secondary access to the Project site. The



existing driveways at the northeast, southwest, and southeast corners of the Project site will be removed as part of the Project. All parking areas on the Project site can be accessed via both the La Veta Avenue and Fairway Drive driveways.

PROJECT TRIP GENERATION

Trip generation rates from Institute of Transportation Engineers (ITE) *Trip Generation Manual* (10th Edition, 2017) and empirical driveway counts collected at the Project site driveways in January 2019 were utilized to determine the Project trip generation. The trip generation equations and rates in the ITE manual are nationally recognized and are used as the basis for most transportation-related studies conducted in the City and the surrounding region. Information was obtained from the *Trip Generation Manual* for ITE Land Use Code (LUC) 252 – Senior Housing (Attached). The General Urban/Suburban rates were used, which are based on data collected at sites with little, if any, transit and other alternative mode availability. To be conservative, the Project trip generation does not include transit/walk-in or pass-by adjustments.

To determine the trip generation of the existing rehabilitation center use, comprehensive trip generation surveys of vehicle traffic entering and exiting the parking and loading areas of the Project site were used. The surveys were conducted on Tuesday, January 7 and Wednesday, January 8, 2020 between the hours of 6:00 AM (one hour before the facility opens at 7:00 AM) and 7:00 PM (one hour after the facility closes at 6:00 PM). The timing of these counts permitted the observation of vehicles entering the facility prior to opening, and exiting the facility after closing. Therefore, it is assumed that all trips generated by the rehabilitation center are captured within the count data. The driveway count data sheets are provided in Attachment B.

Inbound and outbound vehicular traffic volumes were collected at the five driveways during 15-minute intervals. Using the 15-minute count data, the hourly trip generation was determined by combining 15-minutes volumes for each 60 minute period during the count period (6:00 AM – 7:00 PM). The hourly volumes for the two count days were averaged and the two-day average hourly volumes were then reviewed to determine the peak hour trip generation occurring during the AM and PM peak periods. Per the City's Circulation Element, the AM and PM peak periods occur between 7:00 AM and 9:00 AM and 4:00 PM and 6:00 PM, respectively. The AM and PM peak hour trip generation for the existing uses on the Project site are shown in Table 1 and the two-day average hourly trip generation for the Project site is provided in Attachment B. As shown, the existing uses on the Project site generate an average of 125 trips (83 inbound, 42 outbound) during the AM peak and 48 trips (10 inbound, 38 outbound) during the PM peak hour. Between the hours of 6:00 AM and 7:00 PM, the existing uses generate an average of 876 trips.

Table 1
Existing Site Empirical Trip Generation

	Daily	AM Pe	AM Peak Hour (8:00 -9:00 AM)			PM Peak Hour (4:00- 5:00 PM)		
	(6:00 AM -							
	7:00 PM)	In	Out	Total	In	Out	Total	
Trips	876	83	42	125	10	38	48	

As the existing senior affordable housing development on the Project site is accessed by the same driveways as the rehabilitation center use, the trip generation estimates from the empirical counts had to be adjusted to remove trips associated with the existing senior housing development. The ITE trip generation rates from



the *Trip Generation Manual* for LUC 252 were applied to the existing senior affordable housing use. Since the empirical driveway counts were taken between 6:00 AM and 7:00 PM, the existing senior housing use daily trip generation, based on ITE rates, had to be adjusted to account only for trips during the count period. The adjustment of daily trips was applied based on the percentage of daily trips occurring during each hour of the day for LUC 252 provided in Appendix A of the Residential Use section of the *Trip Generation Manual*. Based on these percentages, 18.5 percent of daily trips associated with a senior housing development occur between the hours of 7:00 PM and 6:00 AM. With this adjustment, the existing senior affordable housing development is estimated to generate 121 vehicle trips between 6:00 AM and 7:00 PM; 8 trips during the AM peak hour; and 10 trips during the PM peak hour.

The trips associated with the existing senior affordable housing use were then subtracted from the daily and peak hour empirical trip generation for the existing uses on the Project site to determine the trips associated with the existing rehabilitation center use. The rehabilitation center use is estimated to generate 755 daily trips, with 177 and 38 trips during the AM and PM peak hours, respectively.

The trip generation rates and calculated Project trip generation are shown in Table 1 below. Applying these unadjusted General Urban/Suburban trip rates and existing use credit for the rehabilitation center use, the Project is anticipated to generate -141 net daily trips, including -84 net AM peak hour trips and 5 net PM peak hour trips.

Table 1 – Trip Generation Rates and Calculations

	ITE		Average	AN	/I Peak He	our	PI	VI Peak Ho	our
Land Use	Code	Intensity ²	Weekday	In	Out	Total	In	Out	Total
Trip Generation Rates									
Senior Adult Housing - Attached	252	1 du	3.70	35%	65%	0.20	55%	45%	0.26
Trip Generation Summary									
			Average	AN	/I Peak H	our	PI	VI Peak H	our
Description		Size	Weekday	In	Out	Total	In	Out	Total
PROPOSED USES									
Residential									
Senior Adult Housing (Attached)		166 du	614	12	21	33	24	19	43
Proposed Project Trips			614	12	21	33	24	19	43
EXISTING USES									
Existing Site Driveway Counts ³			876	83	42	125	10	38	48
Residential									
Senior Adult Housing (Attached)		40 du	148	3	5	8	6	4	10
Adjustment for Trips Occuring Outside Count Period ⁴			-27	0	0	0	0	0	0
Senior Adult Housing (Attached) for Trips Occurring during Driveway	/ Count	Period	121	3	5	8	6	4	10
Medical									
Rehabilitation Center ³		36,410 sf	755	80	37	117	4	34	38
Existing Project Trips			755	80	37	117	4	34	38
Net Project Trips			-141	-68	-16	-84	20	-15	5

Notes:

- 1) ITE *Trip Generation Manual* (10th Edition, 2017) trip generation rates and directional distributions applied for Land Use Codes 252 (Senior Housing [Attached]) The General Urban/Suburban setting was selected as most appropriate for the Project location.
- 2) du = Dwelling Units; ksf = Thousands of Square Feet of Gross Leasable Floor Area or Gross Floor Area.
- 3) Driveway counts collected at the Project site driveway locations were used to develop the trip generation of the existing rehabilitation center which will be removed as part of the Project. The site is presently occupied by an approimately 36,410 square feet rehabilitation center and a 40 unit senior affordable housing development, which will remain on-site. Adjustments were made to the driveway counts to isolate only trips associated with the rehabilitation center use. It is assumed that all rehabilitation center trips occur within the count window between 6 AM to 7 PM.
- 4) Adjustments made to the daily trip generation estimate for the existing senior housing development to account for trips occuring outside of the empirical driveway count time period (6 AM to 7 PM). Appendix A of the Residential Use section of the ITE *Trip Genation Manual* (10th Edition, 2017) presents the percentage of daily trips that occur during each hour of the day. Based on these percenteages, an 18.5% reduction was applied to account for trips occuring between 7 PM and 6AM.



TRIP DISTRIBUTION AND ASSIGNMENT

The Project trip distribution is based on are the nature of the Project uses, existing traffic patterns, characteristics of the surrounding roadway system, geographic location of the Project site and its proximity to freeways and major travel routes, employment centers to which residents would likely be attracted, and the various regions generating visitors. The resulting Project distribution percentages are shown in Attachment C.

PRELIMINARY TRAFFIC ANALYSIS CONCLUSIONS

As demonstrated by the Project trip generation and the Project distribution percentages, it is anticipated that the Project will not generate in excess of 100 net vehicle trips during the AM and PM peak hours and the Project will not add 1,600 daily trips to the arterial network. Additionally, the Project will not add 51 or more trips to nearby intersections during the peak hours. Thus, per the *City of Orange Traffic Impact Analysis Guidelines for Vehicle Miles Traveled and Level of Service Assessment* (July 2020), the Project is not anticipated to require further level of service (LOS) analysis. Additionally, since the Project consists entirely of affordable housing, the Project is expected to result in a less-than-significant vehicle miles traveled (VMT) impact and is screened from conducting further VMT analysis.

SIGNATURES

Recommended by:

The above preliminary traffic analysis was prepared to determine the level of additional analysis required for the Project. Should you have any questions, please call (310) 473-6508.

Daniel Hendrick	January 11, 2021
Consultants Representative	Date
Approved by:	
City of Orange	Date



ATTACHMENT A CONCEPTUAL PROJECT SITE PLAN



FN: LaVeta(1800 E)RehabOrange\SITE-PLAN





ATTACHMENT B EMPIRICAL DRIVEWAY COUNT DATA SHEETS AND EXISTING USE TWO-DAY AVERAGE HOURLY TRIP GENERATION



Location: Western Driveway on La Veta Avenue

Date: Tuesady 1/7/2020

Count Type: Driveway

City: Orange

Location: Eastern Driveway on La Veta Avenue

Date: Tuesady 1/7/2020

Count Type: Driveway

ſ			
	Entering	Exiting	Total
6:00	0	0	0
6:15	1	0	1
6:30	3	0	3
6:45	3	0	3
7:00	11	0	11
7:15	27	0	27
7:30	17	0	17
7:45	5	0	5
8:00	14	1	15
8:15	22	0	22
8:30	23	0	23
8:45	16	0	16
9:00	14	0	14
9:15	15	1	16
9:30	5	0	5
9:45	12	0	12
10:00	11	2	13
10:15	7	1	8
10:30	1	0	1
10:45	2	0	2
11:00	2	0	2
11:15	1	2	3
11:30	0	0	0
11:45	2	1	3
12:00	2	0	2
12:15	8	1	9
12:30	6	1	7
12:45	8	0	8
13:00	7	0	7
13:15	8	1	9
13:30	8	2	10
13:45	9	0	9
14:00	9	0	9
14:15	6	0	6
14:30	10	0	10
14:45	12	0	12
15:00	12	0	12
15:15	9	0	9
15:30	19	2	21
15:45	3	1	4
16:00	3	2	5
16:15	3	0	3
16:30	0	0	0
16:45	2	0	2
17:00	4	0	4
17:15	1	0	1
17:30	0	0	0
17:45	2	0	2
18:00	0	0	0
18:15	2	0	2
18:30	0	0	0
18:45	0	0	0
TOTAL	367	18	385
IOIAL	307	10	303

Entering Exiting Total				
6:00 0 0 0 0 0 0 6:15 0 1 1 1 1 1 6:30 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		Entering	Exiting	Total
6:15	6:00	_		
6:30 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		0		
6:45 0 0 7:00 1 5 6 7:15 1 5 6 7:30 3 4 7 7:45 0 4 4 8:00 3 6 9 8:15 2 4 6 8:30 0 8 8 9:00 2 7 9 9:15 0 4 4 9:30 0 7 7 9:45 0 7 7 9:45 0 7 7 9:45 0 7 7 10:00 0 8 8 10:15 0 6 6 10:30 0 6 6 10:45 1 4 5 11:00 0 7 7 11:15 1 5 6 11:30 0 1 1 <td></td> <td>0</td> <td>0</td> <td>0</td>		0	0	0
7:00 1 5 6 7:15 1 5 6 7:30 3 4 7 7:45 0 4 4 8:00 3 6 9 8:15 2 4 6 8:30 0 8 8 8:45 3 5 8 9:00 2 7 9 9:15 0 4 4 9:30 0 7 7 9:45 0 7 7 10:00 0 8 8 10:15 0 6 6 10:30 0 6 6 10:45 1 4 5 11:00 0 7 7 11:15 1 5 6 11:30 0 1 1 11:45 0 4 4 12:00 0 6				
7:15 1 5 6 7:30 3 4 7 7:45 0 4 4 8:00 3 6 9 8:15 2 4 6 8:30 0 8 8 8:45 3 5 8 9:00 2 7 9 9:15 0 4 4 9:30 0 7 7 10:00 0 8 8 10:15 0 6 6 10:30 0 6 6 10:45 1 4 5 11:00 0 7 7 11:15 1 5 6 11:30 0 1 1 11:45 0 4 4 12:00 0 6 6 12:15 0 2 2 12:30 2 3				
7:30 3 4 7 7:45 0 4 4 8:00 3 6 9 8:15 2 4 6 8:30 0 8 8 8:45 3 5 8 9:00 2 7 9 9:15 0 4 4 9:30 0 7 7 10:00 0 8 8 10:15 0 6 6 10:30 0 6 6 10:30 0 6 6 10:45 1 4 5 11:00 0 7 7 11:15 1 5 6 11:30 0 1 1 11:45 0 4 4 12:15 0 2 2 12:30 2 3 3 13:30 0 7				
7:45 0 4 4 8:00 3 6 9 8:15 2 4 6 8:30 0 8 8 8:45 3 5 8 9:00 2 7 9 9:15 0 4 4 9:30 0 7 7 10:00 0 8 8 10:15 0 6 6 10:30 0 6 6 10:45 1 4 5 11:00 0 7 7 11:15 1 5 6 11:30 0 1 1 11:45 0 4 4 12:00 0 6 6 12:15 0 2 2 12:30 2 3 3 13:00 0 7 7 13:30 0 7				
8:00 3 6 9 8:15 2 4 6 8:30 0 8 8 8:45 3 5 8 9:00 2 7 9 9:15 0 4 4 9:30 0 7 7 10:00 0 8 8 10:15 0 6 6 10:30 0 6 6 10:30 0 6 6 10:45 1 4 5 11:00 0 7 7 11:15 1 5 6 11:30 0 1 1 11:45 0 4 4 12:00 0 6 6 12:15 0 2 2 12:30 2 3 3 13:00 0 7 7 13:30 0 7 7 13:15 0 4 4 13:30 <td< td=""><td></td><td></td><td></td><td></td></td<>				
8:15 2 4 6 8:30 0 8 8 8:45 3 5 8 9:00 2 7 9 9:15 0 4 4 9:30 0 7 7 10:00 0 8 8 10:15 0 6 6 10:30 0 6 6 10:30 0 6 6 10:45 1 4 5 11:00 0 7 7 11:15 1 5 6 11:30 0 1 1 11:45 0 4 4 12:00 0 6 6 12:15 0 2 2 12:30 2 3 3 12:45 0 3 3 13:30 0 7 7 13:15 0 4 4 13:30 0 4 4 13:30 <t< td=""><td></td><td></td><td></td><td></td></t<>				
8:30 0 8 8 8:45 3 5 8 9:00 2 7 9 9:15 0 4 4 9:30 0 7 7 10:00 0 8 8 10:15 0 6 6 10:30 0 6 6 10:45 1 4 5 11:00 0 7 7 11:15 1 5 6 11:30 0 1 1 11:45 0 4 4 12:00 0 6 6 12:15 0 2 2 12:30 2 3 5 12:45 0 3 3 13:00 0 7 7 13:15 0 4 4 13:30 0 7 7 14:00 1 11 12 14:30 3 16 19 14:45				
8:45 3 5 8 9:00 2 7 9 9:15 0 4 4 9:30 0 7 7 10:00 0 8 8 10:15 0 6 6 10:30 0 6 6 10:45 1 4 5 11:00 0 7 7 11:15 1 5 6 11:30 0 1 1 11:45 0 4 4 12:00 0 6 6 12:15 0 2 2 12:30 2 3 5 12:45 0 3 3 13:00 0 7 7 13:15 0 4 4 13:30 0 7 7 14:00 1 11 12 14:00 1 11 12 14:30 3 16 19 14:45				
9:00 2 7 9 9:15 0 4 4 9:30 0 7 7 9:45 0 7 7 10:00 0 8 8 10:15 0 6 6 10:30 0 6 6 10:45 1 4 5 11:00 0 7 7 11:15 1 5 6 11:30 0 1 1 11:45 0 4 4 12:00 0 6 6 12:15 0 2 2 12:30 2 3 5 12:45 0 3 3 13:00 0 7 7 13:15 0 4 4 13:30 0 4 4 13:30 0 4 4 13:45 0 7 7 14:00 1 11 12 14:45				
9:15 0 4 4 9:30 0 7 7 9:45 0 7 7 10:00 0 8 8 10:15 0 6 6 10:30 0 6 6 10:45 1 4 5 11:00 0 7 7 11:15 1 5 6 11:30 0 1 1 11:45 0 4 4 12:00 0 6 6 12:15 0 2 2 12:30 2 3 5 12:45 0 3 3 13:00 0 7 7 13:15 0 4 4 13:30 0 4 4 13:45 0 7 7 14:00 1 11 12 14:40 11 1				
9:30 0 7 7 9:45 0 7 7 10:00 0 8 8 10:15 0 6 6 10:30 0 6 6 10:45 1 4 5 11:00 0 7 7 11:15 1 5 6 11:30 0 1 1 11:45 0 4 4 12:00 0 6 6 12:15 0 2 2 12:30 2 3 5 12:45 0 3 3 13:00 0 7 7 13:15 0 4 4 13:30 0 4 4 13:30 0 4 4 13:45 0 7 7 14:00 1 11 12 14:00 1 1				
9:45 0 7 7 10:00 0 8 8 10:15 0 6 6 10:30 0 6 6 10:30 0 6 6 11:00 0 7 7 11:15 1 5 6 11:30 0 1 1 11:45 0 4 4 12:00 0 6 6 12:15 0 2 2 12:30 2 3 5 12:45 0 3 3 13:00 0 7 7 13:15 0 4 4 13:30 0 4 4 13:45 0 7 7 14:00 1 11 12 14:15 1 12 13 14:45 1 12 13 15:00 3				
10:00 0 8 8 10:15 0 6 6 10:30 0 6 6 10:45 1 4 5 11:00 0 7 7 11:15 1 5 6 11:30 0 1 1 11:45 0 4 4 12:00 0 6 6 12:15 0 2 2 12:30 2 3 5 12:45 0 3 3 13:00 0 7 7 13:15 0 4 4 13:30 0 4 4 13:30 0 4 4 13:45 0 7 7 14:00 1 11 12 14:30 3 16 19 14:45 0 8 8 15:00 3 <				
10:15 0 6 6 10:30 0 6 6 10:45 1 4 5 11:00 0 7 7 11:15 1 5 6 11:30 0 1 1 11:45 0 4 4 12:00 0 6 6 12:15 0 2 2 12:30 2 3 5 12:45 0 3 3 13:00 0 7 7 13:15 0 4 4 13:30 0 4 4 13:30 0 4 4 13:45 0 7 7 14:00 1 11 12 14:30 3 16 19 14:45 1 12 13 14:45 0 8 8 15:00 3 29 32 15:30 0 14 14 15:				
10:30 0 6 6 10:45 1 4 5 11:00 0 7 7 11:15 1 5 6 11:30 0 1 1 11:45 0 4 4 12:00 0 6 6 12:15 0 2 2 12:30 2 3 5 12:45 0 3 3 13:00 0 7 7 13:15 0 4 4 13:30 0 4 4 13:45 0 7 7 14:00 1 11 12 14:30 3 16 19 14:45 1 12 13 14:45 0 8 8 15:00 3 29 32 15:30 0 14 14 15:45 0 12 12 16:00 0 18 18 <td< td=""><td></td><td></td><td></td><td></td></td<>				
10:45 1 4 5 11:00 0 7 7 11:15 1 5 6 11:30 0 1 1 11:45 0 4 4 12:00 0 6 6 12:15 0 2 2 12:30 2 3 5 12:45 0 3 3 13:00 0 7 7 13:15 0 4 4 13:30 0 4 4 13:45 0 7 7 14:00 1 11 12 14:30 3 16 19 14:45 0 8 8 15:00 3 29 32 15:15 0 23 23 15:30 0 14 14 15:45 0 12 12 16:00 0 18 18 16:15 0 7 7 <td< td=""><td></td><td></td><td></td><td></td></td<>				
11:00 0 7 7 11:15 1 5 6 11:30 0 1 1 11:45 0 4 4 12:00 0 6 6 12:15 0 2 2 12:30 2 3 5 12:45 0 3 3 13:00 0 7 7 13:15 0 4 4 13:30 0 4 4 13:30 0 4 4 13:45 0 7 7 14:00 1 11 12 14:30 3 16 19 14:45 1 12 13 14:45 0 8 8 15:00 3 29 32 15:15 0 23 23 15:30 0 14 14 15:45 0 12 12 16:00 0 18 18 <				
11:15 1 5 6 11:30 0 1 1 11:45 0 4 4 12:00 0 6 6 12:15 0 2 2 12:30 2 3 5 12:45 0 3 3 13:00 0 7 7 13:15 0 4 4 13:30 0 4 4 13:35 0 4 4 13:45 0 7 7 14:00 1 11 12 14:15 1 12 13 14:30 3 16 19 14:45 0 8 8 15:00 3 29 32 15:30 0 14 14 15:45 0 12 12 16:00 0 18 18 16:15 0 7 7 16:30 0 3 3 <td< td=""><td></td><td></td><td></td><td></td></td<>				
11:30 0 1 1 11:45 0 4 4 12:00 0 6 6 12:15 0 2 2 12:30 2 3 5 12:45 0 3 3 13:00 0 7 7 13:15 0 4 4 13:30 0 4 4 13:30 0 4 4 13:45 0 7 7 14:00 1 11 12 14:30 3 16 19 14:45 0 8 8 15:00 3 29 32 15:15 0 23 23 15:30 0 14 14 15:45 0 12 12 16:00 0 18 18 16:30 0 3 3 16:45 0 2 2 17:00 0 4 4 <td< td=""><td></td><td></td><td></td><td></td></td<>				
11:45 0 4 4 12:00 0 6 6 12:15 0 2 2 12:30 2 3 5 12:45 0 3 3 13:00 0 7 7 13:15 0 4 4 13:30 0 4 4 13:45 0 7 7 14:00 1 11 12 13:45 0 7 7 14:00 1 11 12 13:45 0 7 7 14:30 3 16 19 14:45 0 8 8 15:00 3 29 32 15:15 0 23 23 15:30 0 14 14 15:45 0 12 12 16:30 0 3 3 16:45 0 2 2 17:00 0 4 4 <td< td=""><td></td><td></td><td></td><td></td></td<>				
12:00 0 6 6 12:15 0 2 2 12:30 2 3 5 12:45 0 3 3 13:00 0 7 7 13:15 0 4 4 13:30 0 4 4 13:45 0 7 7 14:00 1 11 12 13:45 1 12 13 14:30 3 16 19 14:45 0 8 8 15:00 3 29 32 15:15 0 23 23 15:30 0 14 14 15:45 0 12 12 16:00 0 18 18 16:30 0 3 3 16:45 0 2 2 17:00 0 4 4 17:30 0 1 1 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:45 0 3 3				
12:15 0 2 2 12:30 2 3 5 12:45 0 3 3 13:00 0 7 7 13:15 0 4 4 13:30 0 4 4 13:45 0 7 7 14:00 1 11 12 14:15 1 12 13 14:30 3 16 19 14:45 0 8 8 15:00 3 29 32 15:15 0 23 23 15:30 0 14 14 15:45 0 12 12 16:00 0 18 18 16:15 0 7 7 16:30 0 3 3 16:45 0 2 2 17:00 0 4 4 17:30 0 1 1 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:45 0 3 3				
12:30 2 3 5 12:45 0 3 3 13:00 0 7 7 13:15 0 4 4 13:30 0 4 4 13:30 0 4 4 13:45 0 7 7 14:00 1 11 12 14:15 1 12 13 14:30 3 16 19 14:45 0 8 8 15:00 3 29 32 15:15 0 23 23 15:30 0 14 14 15:45 0 12 12 16:00 0 18 18 16:15 0 7 7 16:30 0 3 3 16:45 0 2 2 17:00 0 4 4 17:30 0 1 1 17:45 0 7 7 <		0		
12:45 0 3 3 13:00 0 7 7 13:15 0 4 4 13:30 0 4 4 13:45 0 7 7 14:00 1 11 12 14:15 1 12 13 14:30 3 16 19 14:45 0 8 8 15:00 3 29 32 15:15 0 23 23 15:30 0 14 14 15:45 0 12 12 16:00 0 18 18 16:15 0 7 7 16:30 0 3 3 16:45 0 2 2 17:00 0 4 4 17:30 0 1 1 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 <	12:15	0	2	
13:00 0 7 7 13:15 0 4 4 13:30 0 4 4 13:45 0 7 7 14:00 1 11 12 14:15 1 12 13 14:30 3 16 19 14:45 0 8 8 15:00 3 29 32 15:15 0 23 23 15:30 0 14 14 15:45 0 12 12 16:00 0 18 18 16:15 0 7 7 16:30 0 3 3 16:45 0 2 2 17:00 0 4 4 17:30 0 1 1 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:30 0 0 0 <	12:30	2	3	5
13:15 0 4 4 13:30 0 4 4 13:45 0 7 7 14:00 1 11 12 14:15 1 12 13 14:30 3 16 19 14:45 0 8 8 15:00 3 29 32 15:15 0 23 23 15:30 0 14 14 15:45 0 12 12 16:00 0 18 18 16:15 0 7 7 16:30 0 3 3 16:45 0 2 2 17:00 0 4 4 17:15 0 4 4 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:45 0 3 3	12:45	0		
13:30 0 4 4 13:45 0 7 7 14:00 1 11 12 14:15 1 12 13 14:30 3 16 19 14:45 0 8 8 15:00 3 29 32 15:15 0 23 23 15:30 0 14 14 15:45 0 12 12 16:00 0 18 18 16:15 0 7 7 16:30 0 3 3 16:45 0 2 2 17:00 0 4 4 17:30 0 1 1 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:30 0 0 0 18:45 0 3 3	13:00	0	7	7
13:45 0 7 7 14:00 1 11 12 14:15 1 12 13 14:30 3 16 19 14:45 0 8 8 15:00 3 29 32 15:15 0 23 23 15:30 0 14 14 15:45 0 12 12 16:00 0 18 18 16:15 0 7 7 16:30 0 3 3 16:45 0 2 2 17:00 0 4 4 17:30 0 1 1 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:30 0 0 0 18:45 0 3 3	13:15	0	4	4
14:00 1 11 12 14:15 1 12 13 14:30 3 16 19 14:45 0 8 8 15:00 3 29 32 15:15 0 23 23 15:30 0 14 14 15:45 0 12 12 16:00 0 18 18 16:15 0 7 7 16:30 0 3 3 16:45 0 2 2 17:00 0 4 4 17:15 0 4 4 17:30 0 1 1 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:30 0 0 0 18:45 0 3 3	13:30	0	4	4
14:15 1 12 13 14:30 3 16 19 14:45 0 8 8 15:00 3 29 32 15:15 0 23 23 15:30 0 14 14 15:45 0 12 12 16:00 0 18 18 16:15 0 7 7 16:30 0 3 3 16:45 0 2 2 17:00 0 4 4 17:15 0 4 4 17:30 0 1 1 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:30 0 0 0 18:45 0 3 3	13:45	0	7	7
14:30 3 16 19 14:45 0 8 8 15:00 3 29 32 15:15 0 23 23 15:30 0 14 14 15:45 0 12 12 16:00 0 18 18 16:15 0 7 7 16:30 0 3 3 16:45 0 2 2 17:00 0 4 4 17:15 0 4 4 17:30 0 1 1 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:30 0 0 0 18:45 0 3 3	14:00	1	11	12
14:45 0 8 8 15:00 3 29 32 15:15 0 23 23 15:30 0 14 14 15:45 0 12 12 16:00 0 18 18 16:15 0 7 7 16:30 0 3 3 16:45 0 2 2 17:00 0 4 4 17:15 0 4 4 17:30 0 1 1 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:30 0 0 0 18:45 0 3 3	14:15	1	12	13
14:45 0 8 8 15:00 3 29 32 15:15 0 23 23 15:30 0 14 14 15:45 0 12 12 16:00 0 18 18 16:15 0 7 7 16:30 0 3 3 16:45 0 2 2 17:00 0 4 4 17:15 0 4 4 17:30 0 1 1 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:30 0 0 0 18:45 0 3 3		3		19
15:00 3 29 32 15:15 0 23 23 15:30 0 14 14 15:45 0 12 12 16:00 0 18 18 16:15 0 7 7 16:30 0 3 3 16:45 0 2 2 17:00 0 4 4 17:15 0 4 4 17:30 0 1 1 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:30 0 0 0 18:45 0 3 3				
15:15 0 23 23 15:30 0 14 14 15:45 0 12 12 16:00 0 18 18 16:15 0 7 7 16:30 0 3 3 16:45 0 2 2 17:00 0 4 4 17:15 0 4 4 17:30 0 1 1 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:30 0 0 0 18:45 0 3 3				
15:30 0 14 14 15:45 0 12 12 16:00 0 18 18 16:15 0 7 7 16:30 0 3 3 16:45 0 2 2 17:00 0 4 4 17:15 0 4 4 17:30 0 1 1 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:30 0 0 0 18:45 0 3 3				
15:45 0 12 12 16:00 0 18 18 16:15 0 7 7 16:30 0 3 3 16:45 0 2 2 17:00 0 4 4 17:15 0 4 4 17:30 0 1 1 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:30 0 0 0 18:45 0 3 3				
16:00 0 18 18 16:15 0 7 7 16:30 0 3 3 16:45 0 2 2 17:00 0 4 4 17:15 0 4 4 17:30 0 1 1 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:30 0 0 0 18:45 0 3 3				
16:15 0 7 7 16:30 0 3 3 16:45 0 2 2 17:00 0 4 4 17:15 0 4 4 17:30 0 1 1 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:30 0 0 0 18:45 0 3 3				
16:30 0 3 3 16:45 0 2 2 17:00 0 4 4 17:15 0 4 4 17:30 0 1 1 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:30 0 0 0 18:45 0 3 3				
16:45 0 2 2 17:00 0 4 4 17:15 0 4 4 17:30 0 1 1 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:30 0 0 0 18:45 0 3 3				
17:00 0 4 4 17:15 0 4 4 17:30 0 1 1 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:30 0 0 0 18:45 0 3 3				
17:15 0 4 4 17:30 0 1 1 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:30 0 0 0 18:45 0 3 3				
17:30 0 1 1 17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:30 0 0 0 18:45 0 3 3				
17:45 0 7 7 18:00 0 0 0 18:15 0 3 3 18:30 0 0 0 18:45 0 3 3				
18:00 0 0 0 18:15 0 3 3 18:30 0 0 0 18:45 0 3 3				
18:15 0 3 3 18:30 0 0 0 18:45 0 3 3				
18:30 0 0 0 18:45 0 3 3				
18:45 0 3 3				
TOTAL 27 221 240	TOTAL	27	3 321	348



Location: Western Driveway on Fairway Drive

Date: Tuesady 1/7/2020

Count Type: Driveway

City: Orange

Location: Central Driveway on Fairway Drive

Date: Tuesady 1/7/2020

Count Type: Driveway

ſ			ı
	Entering	Exiting	Total
6:00	0	0	0
6:15	0	1	1
6:30	1	0	1
6:45	1	0	1
7:00	1	2	3
7:15	1	0	1
7:30	0	0	0
7:45	2	0	2
8:00	0	0	0
8:15	0	1	1
8:30	2	0	2
8:45	1	0	1
9:00	1	1	2
9:15	2	0	2
9:30	0	1	1
9:45	0	0	0
10:00	0	1	1
10:15	2	0	2
10:30	0	0	0
10:45	1	0	1
11:00	0	0	0
11:15	0	0	0
11:30	1	3	4
11:45	2	1	3
12:00	1	1	2
12:15	0	0	0
12:30	0	1	1
12:45	0	0	0
13:00	0	0	0
13:15	2	1	3
13:30	1	0	1
13:45	1	2	3
14:00	0	0	0
14:15	0	0	0
14:30	0	0	0
14:45	0	1	1
15:00	2	2	4
15:15	0	1	1
15:30	0	1	1
15:45	0	0	0
	0	2	2
16:00 16:15	1	0	1
16:15	0	0	0
16:30		1	1
16:45 17:00	0	1	1
17:00			
17:15	0	1	1
17:30	0	0	0
17:45	1	0	1
18:00	0	0	0
18:15	0	0	0
18:30	0	0	0
18:45	0	0	0
TOTAL	27	26	53

6:00 6:15 6:30 6:45 7:00 7:15 7:30 7:45 8:00 8:15 8:30 8:45 9:00 9:15 9:30 9:45 10:00 10:15 10:30 10:45 11:00 11:15	ering 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Exiting 0 0 0 0 0 0 0 0 0 0 1 0 1	Total 0 0 0 0 0 0 0 0 0 0 0 0 1 0 0 0 1 0 2
6:15 6:30 6:45 7:00 7:15 7:30 7:45 8:00 8:15 8:30 8:45 9:00 9:15 9:30 9:45 10:00 10:15 10:30 10:45 11:00 11:15 11:30 11:45 12:00	0 0 0 0 0 0 1 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 1 0 0 0 0
6:30 6:45 7:00 7:15 7:30 7:45 8:00 8:15 8:30 8:45 9:00 9:15 9:30 9:45 10:00 10:15 10:30 10:45 11:00 11:15 11:30 11:45 12:00	0 0 0 0 0 1 0 0 0 0 0 0 1 0 0	0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 1 0 0 0 0
6:45 7:00 7:15 7:30 7:45 8:00 8:15 8:30 8:45 9:00 9:15 9:30 9:45 10:00 10:15 10:30 10:45 11:00 11:15 11:30 11:45 12:00	0 0 0 1 0 0 0 0 0 0 0 1 0 0	0 0 0 0 0 0 0 0 0 1	0 0 0 0 1 0 0 0 0
7:00 7:15 7:30 7:45 8:00 8:15 8:30 8:45 9:00 9:15 9:30 9:45 10:00 10:15 10:30 10:45 11:00 11:15 11:30 11:45 12:00	0 0 0 1 0 0 0 0 0 0 1 0 0	0 0 0 0 0 0 0 0 0	0 0 0 1 0 0 0 0
7:15 7:30 7:45 8:00 8:15 8:30 8:45 9:00 9:15 9:30 9:45 10:00 10:15 10:30 10:45 11:00 11:15 11:30 11:45 12:00	0 0 1 0 0 0 0 0 0 0 1 0	0 0 0 0 0 0 0 1	0 0 1 0 0 0 0 0
7:30 7:45 8:00 8:15 8:30 8:45 9:00 9:15 9:30 9:45 10:00 10:15 10:30 10:45 11:00 11:15 11:30 11:45 12:00	0 1 0 0 0 0 0 0 0 1 0 0	0 0 0 0 0 0 0 1	0 1 0 0 0 0 1
7:45 8:00 8:15 8:30 8:45 9:00 9:15 9:30 9:45 10:00 10:15 10:30 10:45 11:00 11:15 11:30 11:45 12:00	1 0 0 0 0 0 0 0 1 0 0	0 0 0 0 0 1 0	1 0 0 0 0 0 1
7:45 8:00 8:15 8:30 8:45 9:00 9:15 9:30 9:45 10:00 10:15 10:30 10:45 11:00 11:15 11:30 11:45 12:00	0 0 0 0 0 0 1 0 0	0 0 0 0 1 0	0 0 0 0 1
8:15 8:30 8:45 9:00 9:15 9:30 9:45 10:00 10:15 10:30 10:45 11:00 11:15 11:30 11:45 12:00	0 0 0 0 0 1 0 0	0 0 0 1 0	0 0 0 1 0
8:15 8:30 8:45 9:00 9:15 9:30 9:45 10:00 10:15 10:30 10:45 11:00 11:15 11:30 11:45 12:00	0 0 0 0 0 1 0 0	0 0 0 1 0	0 0 0 1 0
8:30 8:45 9:00 9:15 9:30 9:45 10:00 10:15 10:30 10:45 11:00 11:15 11:30 11:45 12:00	0 0 0 0 1 0 0	0 0 1 0	0 0 1 0
8:45 9:00 9:15 9:30 9:45 10:00 10:15 10:30 10:45 11:00 11:15 11:30 11:45 12:00	0 0 0 1 0 0 0	0 1 0 1	0 1 0
9:00 9:15 9:30 9:45 10:00 10:15 10:30 10:45 11:00 11:15 11:30 11:45 12:00	0 0 1 0 0 0	1 0 1	1 0
9:15 9:30 9:45 10:00 10:15 10:30 10:45 11:00 11:15 11:30 11:45 12:00	0 1 0 0 0	0	0
9:30 9:45 10:00 10:15 10:30 10:45 11:00 11:15 11:30 11:45 12:00	1 0 0 0	1	
9:45 10:00 10:15 10:30 10:45 11:00 11:15 11:30 11:45 12:00	0 0 0		, ,
10:00 10:15 10:30 10:45 11:00 11:15 11:30 11:45 12:00	0	0	0
10:15 10:30 10:45 11:00 11:15 11:30 11:45 12:00	0	0	0
10:30 10:45 11:00 11:15 11:30 11:45 12:00		0	0
10:45 11:00 11:15 11:30 11:45 12:00		1	2
11:00 11:15 11:30 11:45 12:00	0	0	0
11:15 11:30 11:45 12:00	1	1	2
11:30 11:45 12:00	0	0	0
11:45 12:00	1		1
12:00		0	
	0	0	3
42.45	1	2	
12:15	0	0	0
12:30	0	0	0
12:45	0	0	0
13:00	0	0	0
13:15	0	0	0
13:30	0	0	0
13:45	0	0	0
14:00	0	0	0
14:15	0	0	0
14:30	0	0	0
14:45	0	0	0
15:00	0	1	1
15:15	0	0	0
15:30	0	0	0
15:45	0	0	0
16:00	0	0	0
16:15	0	0	0
16:30	0	0	0
16:45	0	0	0
17:00	0	0	0
17:15	0	0	0
17:30	0	0	0
17:45	0	0	0
18:00	0	0	0
18:15	0	0	0
18:30	0	0	0
18:45			
TOTAL	0	0	0



Location: Eastern Driveway on Fairway Drive

Date: Tuesady 1/7/2020

Count Type: Driveway

City: Orange

Location: TOTAL DRIVEWAYS

Date: Tuesady 1/7/2020
Count Type: Driveway

	Entering Exiting		Total		
6:00		0 0			
6:15	0	0	0		
6:30	0	0	0		
6:45	0	0	0		
7:00	0	0	0		
7:15	0	0	0		
7:30	0	2	2		
7:45	0	3	3		
8:00	0	2	2		
8:15	0	2	2		
8:30	0	7	7		
8:45	0	3	3		
9:00	0	10	10		
9:15	0	3	3		
9:30	0	3	3		
9:45	0	1	1		
10:00	1	0	1		
10:15	0	2	2		
10:30	0	0	0		
10:45	0	0	0		
11:00	0	1	1		
11:15	0	0	0		
11:30	0	1	1		
11:45	0	0	0		
12:00	0	0	0		
12:15	0	0	0		
12:30	1	1	2		
12:45	0	1	1		
13:00	0	1	1		
13:15	0	1	1		
13:30	0	1	1		
13:45	0	1	1		
14:00	1	2	3		
14:15	0	3	3		
14:30	0	3	3		
14:45	0	4	4		
15:00	0	0	0		
15:15	1	1	2		
15:30	0	5	5		
15:45	0	2	2		
16:00	0	3	3		
16:15	0	0	0		
16:30	0	0	0		
16:45	0	0	0		
17:00	0	0	0		
17:15	1	0	1		
17:30	0	0	0		
17:45	0	0	0		
18:00	0	0	0		
18:15	0	0	0		
18:30	0	0	0		
18:45	0	0	0		
TOTAL	5	69	74		

6:00 6:15 6:30 6:45 7:00 7:15 7:30 7:45 8:00	Entering 0 1 4 4 13 29 20 8 17 24	Exiting 0 2 0 7 5 6 7	Total 0 3 4 4 20 34 26
6:15 6:30 6:45 7:00 7:15 7:30 7:45 8:00	0 1 4 4 13 29 20 8 17	0 2 0 0 7 5 6	0 3 4 4 20 34 26
6:15 6:30 6:45 7:00 7:15 7:30 7:45 8:00	1 4 4 13 29 20 8 17 24	2 0 0 7 5 6 7	3 4 4 20 34 26
6:30 6:45 7:00 7:15 7:30 7:45 8:00	4 4 13 29 20 8 17 24	0 0 7 5 6 7	4 4 20 34 26
6:45 7:00 7:15 7:30 7:45 8:00 8:15	4 13 29 20 8 17 24	0 7 5 6 7	4 20 34 26
7:00 7:15 7:30 7:45 8:00 8:15	13 29 20 8 17 24	7 5 6 7	20 34 26
7:15 7:30 7:45 8:00 8:15	29 20 8 17 24	5 6 7	34 26
7:30 7:45 8:00 8:15	20 8 17 24	6 7	26
7:45 8:00 8:15	8 17 24	7	
8:00 8:15	17 24		15
8:15	24		26
		9 7	31
0.20		15	40
8:30	25		28
8:45	20 17	8	
9:00		19	36
9:15	17	8	25
9:30	6	12	18
9:45	12	8	20
10:00	12	11	23
10:15	9	9	18
10:30	2	7	9
10:45	4	4	8
11:00	3	9	12
11:15	2	7	9
11:30	2	5	7
11:45	4	6	10
12:00	4	9	13
12:15	8	3	11
12:30	9	6	15
12:45	8	4	12
13:00		8	15
13:15	10	7	17
13:30	9	7	16
13:45	10	10	20
14:00	11	13	24
14:15	7	15	22
14:30	13	19	32
14:45	12	13	25
15:00	17	32	49
15:15	10	25	35
15:30	19	22	41
15:45	3	15	18
16:00	3	25	28
16:15	4	7	11
16:30	0	3	3
16:45	2	3	5
17:00	4	5	9
17:15	2	5	7
17:30	0	1	1
17:45	3	7	10
18:00	0	0	0
18:15	2	3	5
18:30	0	0	0
18:45	0	3	3
TOTAL	432	441	873



Location: Western Driveway on La Veta Avenue

Date: Wednesday 1/8/2020

Count Type: Driveway

City: Orange

Location: Eastern Driveway on La Veta Avenue

Date: Wednesday 1/8/2020

Count Type: Driveway

ſ				
	Entering	Exiting	Total	
6:00	0			
6:15	2	0	2	
6:30	2	0	2	
6:45	4	0	4	
7:00	11	0	11	
7:15	22	0	22	
7:30	15	0	15	
7:45	17	0	17	
8:00	16	0	16	
8:15	11	1	12	
8:30	22	0	22	
8:45	19	0	19	
9:00	13	1	14	
9:15	14	0	14	
9:30	11	1	12	
9:45	14	0	14	
10:00	9	0	9	
10:15	2	0	2	
10:30	4	0	4	
10:45	1	0	1	
11:00	3	2	5	
11:15	1	1	2	
11:30	5	1	6	
11:45	4	0	4	
12:00	2	1	3	
12:15	8	0	8	
12:30	10	0	10	
12:45	13	0	13	
13:00	5	0	5	
13:15	9	0	9	
13:30	6	0	6	
13:45	9	0	9	
14:00	11	2	13	
14:15	11	0	11	
14:30	7	0	7	
14:45	10	0	10	
15:00	14	0	14	
15:15	4	0	4	
15:30	11	1	12	
15:45	8	0	8	
16:00	4	1	5	
16:15	2	0	2	
16:30	1	0	1	
16:45	1	0	1	
17:00	1	0	1	
17:15	1	3	4	
17:30	0	0	0	
17:45	2	0	2	
18:00	2	2	4	
18:15	3	1	4	
18:30	0	0	0	
18:45	3	0	3	
TOTAL	380	18	398	

Entering Exiting Total				
6:15 0 1 1 1 6:30 0 0 0 0 6:45 0 1 1 1 7:00 1 3 4 7:15 2 9 11 7:30 3 7 10 7:45 0 0 0 0 8:00 1 6 7 8:15 1 5 6 8:30 2 8 10 8:45 2 4 6 9:00 1 16 17 9:15 0 5 5 9:30 0 5 5 9:45 0 5 5 10:00 0 11 11 11 10:15 0 3 3 3 10:30 0 5 5 10:45 0 4 4 11:00 0 6 6 11:15 1 5 6 11:30 1 4 5 11:45 0 2 2 12:00 0 6 6 12:15 0 5 5 12:30 1 2 3 12:45 0 5 5 13:00 0 4 4 13:15 1 2 3 13:30 0 6 6 13:45 0 13 13 14:00 0 20 14:15 0 8 8 14:30 2 13 15 14:45 1 6 7 15:00 0 21 21 15:15 0 8 8 14:30 2 13 15 14:45 1 6 7 15:00 0 21 21 15:15 0 10 10 15:45 0 14 14 16:00 0 27 27 16:15 0 1 11 16:30 0 3 3 17:15 1 1 2 15 16:30 0 3 3 17:15 1 1 1 1 17:30 1 1 1 18:45 0 2 2 2 11:15 0 5 5 5 13:30 0 10 10 15:45 0 14 14 16:00 0 27 27 16:15 0 1 1 1 16:30 0 3 3 17:15 1 1 2 2 17:30 2 2 4 17:45 0 0 2 2 2 18:15 0 0 2 2 2 18:15 0 0 1 1 1 16:30 0 3 3 3 16:45 0 0 0 0 17:00 0 3 3 3 17:15 1 1 2 2 17:30 2 2 4 17:45 0 4 4 18:00 0 2 2 2		Entering	Exiting	Total
6:30 0 0 0 0 0 6:45 0 1 1 1 1 7:00 1 3 4 7:15 2 9 11 7:30 3 7 10 7:45 0 0 0 0 8:00 1 6 7 8:15 1 5 6 8:30 2 8 10 8:45 2 4 6 9:00 1 16 17 9:15 0 5 5 9:30 0 5 5 9:45 0 4 4 11:00 0 6 6 6 11:15 1 5 6 6 11:30 1 4 5 11:45 0 1 2 1 2 1 15:30 0 1 1 3 13 13 14:00 0 20 20 14:15 0 8 8 8 14:30 2 13 15:45 0 14 14 14 16:00 0 2 2 2 18:15 0 1 1 1 1 1 1 1 10:15 0 8 8 8 14:30 2 1 1 16:30 0 0 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1				
6:45 0 1 1 7:00 1 3 4 7:15 2 9 11 7:30 3 7 10 7:45 0 0 0 8:00 1 6 7 8:15 1 5 6 8:30 2 8 10 8:45 2 4 6 9:00 1 16 17 9:15 0 5 5 9:30 0 5 5 9:30 0 5 5 9:30 0 5 5 9:30 0 5 5 9:30 0 5 5 9:30 0 5 5 9:30 0 5 5 9:30 0 5 5 10:00 0 11 11 10:10 1 1		0	1	1
7:00 1 3 4 7:15 2 9 11 7:30 3 7 10 7:45 0 0 0 8:00 1 6 7 8:15 1 5 6 8:30 2 8 10 8:45 2 4 6 9:00 1 16 17 9:15 0 5 5 9:30 0 5 5 9:30 0 5 5 9:30 0 5 5 9:30 0 5 5 9:30 0 5 5 9:30 0 5 5 9:30 0 5 5 9:30 0 5 5 9:30 0 5 5 9:45 0 5 5 10:00 0 6 <				
7:15 2 9 11 7:30 3 7 10 7:45 0 0 0 8:00 1 6 7 8:15 1 5 6 8:30 2 8 10 8:45 2 4 6 9:00 1 16 17 9:15 0 5 5 9:30 0 5 5 9:45 0 5 5 10:00 0 11 11 10:15 0 3 3 10:30 0 5 5 10:45 0 4 4 11:00 0 6 6 11:15 1 5 6 11:45 0 2 2 12:00 0 6 6 12:15 0 5 5 12:30 1 2 <td></td> <td>0</td> <td>1</td> <td>1</td>		0	1	1
7:30 3 7 10 7:45 0 0 0 8:00 1 6 7 8:15 1 5 6 8:30 2 8 10 8:45 2 4 6 9:00 1 16 17 9:15 0 5 5 9:30 0 5 5 9:45 0 5 5 10:00 0 11 11 10:15 0 3 3 10:30 0 5 5 10:45 0 4 4 11:00 0 6 6 11:15 1 5 6 11:45 0 2 2 12:00 0 6 6 12:15 0 5 5 12:30 1 2 3 12:45 0 5 <td></td> <td>1</td> <td>3</td> <td>4</td>		1	3	4
7:45 0 0 0 8:00 1 6 7 8:15 1 5 6 8:30 2 8 10 8:45 2 4 6 9:00 1 16 17 9:15 0 5 5 9:30 0 5 5 9:45 0 5 5 9:45 0 5 5 10:00 0 11 11 10:15 0 3 3 10:30 0 5 5 10:45 0 4 4 11:00 0 6 6 11:15 1 5 6 11:45 0 2 2 12:00 0 6 6 12:15 0 5 5 12:30 1 2 3 12:45 0 5	7:15	2		11
8:00 1 6 7 8:15 1 5 6 8:30 2 8 10 8:45 2 4 6 9:00 1 16 17 9:15 0 5 5 9:30 0 5 5 9:45 0 5 5 10:00 0 11 11 10:15 0 3 3 10:30 0 5 5 10:45 0 4 4 11:00 0 6 6 11:15 1 5 6 11:30 1 4 5 11:45 0 2 2 12:00 0 6 6 12:15 0 5 5 12:30 1 2 3 12:45 0 5 5 13:00 0 4 4 13:30 0 6 6 13:45	7:30	3	7	10
8:15 1 5 6 8:30 2 8 10 8:45 2 4 6 9:00 1 16 17 9:15 0 5 5 9:30 0 5 5 9:45 0 5 5 10:00 0 11 11 10:15 0 3 3 10:30 0 5 5 10:45 0 4 4 11:00 0 6 6 11:15 1 5 6 11:30 1 4 5 11:45 0 2 2 12:00 0 6 6 12:15 0 5 5 12:30 1 2 3 12:45 0 5 5 13:00 0 4 4 13:30 0 6 6 13:45 0 13 13 14:00	7:45	0	0	0
8:30 2 8 10 8:45 2 4 6 9:00 1 16 17 9:15 0 5 5 9:30 0 5 5 9:45 0 5 5 10:00 0 11 11 10:15 0 3 3 10:30 0 5 5 10:45 0 4 4 11:00 0 6 6 11:15 1 5 6 11:30 1 4 5 11:45 0 2 2 12:00 0 6 6 12:15 0 5 5 12:30 1 2 3 12:45 0 5 5 13:00 0 4 4 13:30 0 6 6 13:45 0 13 13 14:00 0 20 20 14:15	8:00	1	6	7
8:45 2 4 6 9:00 1 16 17 9:15 0 5 5 9:30 0 5 5 9:45 0 5 5 10:00 0 11 11 10:15 0 3 3 10:30 0 5 5 10:45 0 4 4 11:00 0 6 6 11:15 1 5 6 11:30 1 4 5 11:45 0 2 2 12:00 0 6 6 12:15 0 5 5 12:30 1 2 3 12:45 0 5 5 13:00 0 4 4 13:15 1 2 3 13:30 0 6 6 13:45 0 13 13 14:00 0 20 20 14:15	8:15	1	5	6
9:00 1 16 17 9:15 0 5 5 9:30 0 5 5 9:45 0 5 5 10:00 0 11 11 10:15 0 3 3 10:30 0 5 5 10:45 0 4 4 11:00 0 6 6 11:15 1 5 6 11:30 1 4 5 11:45 0 2 2 12:00 0 6 6 12:15 0 5 5 12:30 1 2 3 12:45 0 5 5 13:00 0 4 4 13:15 1 2 3 13:30 0 6 6 13:45 0 13 13 14:00 0 <td< td=""><td>8:30</td><td>2</td><td>8</td><td>10</td></td<>	8:30	2	8	10
9:15 0 5 5 9:30 0 5 5 9:45 0 5 5 10:00 0 11 11 10:15 0 3 3 10:30 0 5 5 10:45 0 4 4 11:00 0 6 6 11:15 1 5 6 11:30 1 4 5 11:45 0 2 2 12:00 0 6 6 12:15 0 5 5 12:30 1 2 3 12:45 0 5 5 13:00 0 4 4 13:15 1 2 3 13:30 0 6 6 13:45 0 13 13 14:00 0 20 20 14:15 0 <t< td=""><td>8:45</td><td>2</td><td>4</td><td>6</td></t<>	8:45	2	4	6
9:30 0 5 5 9:45 0 5 5 10:00 0 11 11 10:30 0 5 5 10:45 0 4 4 11:00 0 6 6 11:15 1 5 6 11:30 1 4 5 11:45 0 2 2 12:00 0 6 6 12:15 0 5 5 12:30 1 2 3 12:45 0 5 5 13:00 0 4 4 13:15 1 2 3 13:30 0 6 6 13:45 0 13 13 14:00 0 20 20 14:15 0 8 8 14:30 2 13 15 14:45 1	9:00	1	16	17
9:45 0 5 5 10:00 0 11 11 10:15 0 3 3 10:30 0 5 5 10:45 0 4 4 11:00 0 6 6 11:15 1 5 6 11:30 1 4 5 11:45 0 2 2 12:00 0 6 6 12:15 0 5 5 12:30 1 2 3 12:45 0 5 5 13:00 0 4 4 13:15 1 2 3 13:30 0 6 6 13:45 0 13 13 14:00 0 20 20 14:15 0 8 8 14:30 2 13 15 14:45 1	9:15	0	5	5
9:45 0 5 5 10:00 0 11 11 10:15 0 3 3 10:30 0 5 5 10:45 0 4 4 11:00 0 6 6 11:15 1 5 6 11:30 1 4 5 11:45 0 2 2 12:00 0 6 6 12:15 0 5 5 12:30 1 2 3 12:45 0 5 5 13:00 0 4 4 13:15 1 2 3 13:30 0 6 6 13:45 0 13 13 14:00 0 20 20 14:15 0 8 8 14:30 2 13 15 14:45 1		0		
10:00 0 11 11 10:15 0 3 3 10:30 0 5 5 10:45 0 4 4 11:00 0 6 6 11:15 1 5 6 11:30 1 4 5 11:45 0 2 2 12:00 0 6 6 12:15 0 5 5 12:30 1 2 3 12:30 1 2 3 12:45 0 5 5 13:00 0 4 4 13:15 1 2 3 13:30 0 6 6 13:45 0 13 13 14:00 0 20 20 14:15 0 8 8 14:30 2 13 15 14:45 1		0	5	
10:15 0 3 3 10:30 0 5 5 10:45 0 4 4 11:00 0 6 6 11:15 1 5 6 11:30 1 4 5 11:45 0 2 2 12:00 0 6 6 12:15 0 5 5 12:30 1 2 3 12:45 0 5 5 13:00 0 4 4 13:15 1 2 3 13:30 0 6 6 13:45 0 13 13 14:00 0 20 20 14:15 0 8 8 14:30 2 13 15 14:45 1 6 7 15:00 0 21 21 15:30 0 10 10 15:45 0 1 1 16:				
10:30 0 5 5 10:45 0 4 4 11:00 0 6 6 11:15 1 5 6 11:30 1 4 5 11:45 0 2 2 12:00 0 6 6 12:15 0 5 5 12:30 1 2 3 12:45 0 5 5 13:00 0 4 4 13:15 1 2 3 13:30 0 6 6 13:45 0 13 13 14:00 0 20 20 14:15 0 8 8 14:30 2 13 15 14:45 1 6 7 15:00 0 21 21 15:30 0 10 10 15:45 0 14 14 16:00 0 27 27 <td< td=""><td></td><td></td><td></td><td></td></td<>				
10:45 0 4 4 11:00 0 6 6 11:15 1 5 6 11:30 1 4 5 11:45 0 2 2 12:00 0 6 6 12:15 0 5 5 12:30 1 2 3 12:45 0 5 5 13:00 0 4 4 13:15 1 2 3 13:30 0 6 6 13:45 0 13 13 14:00 0 20 20 14:15 0 8 8 14:30 2 13 15 14:45 1 6 7 15:00 0 21 21 15:30 0 10 10 15:45 0 14 14 16:00 0 27 27 16:15 0 1 1 <td< td=""><td></td><td></td><td></td><td></td></td<>				
11:00 0 6 6 11:15 1 5 6 11:30 1 4 5 11:45 0 2 2 12:00 0 6 6 12:15 0 5 5 12:30 1 2 3 12:45 0 5 5 13:00 0 4 4 13:15 1 2 3 13:30 0 6 6 13:45 0 13 13 14:00 0 20 20 14:15 0 8 8 14:30 2 13 15 14:45 1 6 7 15:00 0 21 21 15:30 0 10 10 15:45 0 14 14 16:00 0 27 27 16:15 0 1 1 16:30 0 3 3 <td< td=""><td></td><td></td><td></td><td></td></td<>				
11:15 1 5 6 11:30 1 4 5 11:45 0 2 2 12:00 0 6 6 12:15 0 5 5 12:30 1 2 3 12:45 0 5 5 13:00 0 4 4 13:15 1 2 3 13:30 0 6 6 13:45 0 13 13 14:00 0 20 20 14:15 0 8 8 14:30 2 13 15 14:45 1 6 7 15:00 0 21 21 15:15 0 21 21 15:30 0 10 10 15:45 0 14 14 16:00 0 27 27 16:15 0 1 1 16:30 0 3 3 <				
11:30 1 4 5 11:45 0 2 2 12:00 0 6 6 12:15 0 5 5 12:30 1 2 3 12:45 0 5 5 13:00 0 4 4 13:15 1 2 3 13:30 0 6 6 13:45 0 13 13 14:00 0 20 20 14:15 0 8 8 14:30 2 13 15 14:45 1 6 7 15:00 0 21 21 15:30 0 10 10 15:30 0 10 10 15:45 0 14 14 16:00 0 27 27 16:15 0 1 1 16:30 0 3 3 17:00 0 3 3 <				
11:45 0 2 2 12:00 0 6 6 12:15 0 5 5 12:30 1 2 3 12:45 0 5 5 13:00 0 4 4 13:15 1 2 3 13:30 0 6 6 13:45 0 13 13 14:00 0 20 20 14:15 0 8 8 14:30 2 13 15 14:45 1 6 7 15:00 0 21 21 15:15 0 21 21 15:30 0 10 10 15:45 0 14 14 16:00 0 27 27 16:15 0 1 1 16:30 0 3 3 17:00 0 3 3 17:15 1 1 2 <				
12:00 0 6 6 12:15 0 5 5 12:30 1 2 3 12:45 0 5 5 13:00 0 4 4 13:15 1 2 3 13:30 0 6 6 13:45 0 13 13 14:00 0 20 20 14:15 0 8 8 14:30 2 13 15 14:45 1 6 7 15:00 0 21 21 15:15 0 21 21 15:30 0 10 10 15:45 0 14 14 16:00 0 27 27 16:15 0 1 1 16:30 0 3 3 16:45 0 0 0 17:00 0 3 3 17:45 0 4 4 <				
12:15 0 5 5 12:30 1 2 3 12:45 0 5 5 13:00 0 4 4 13:15 1 2 3 13:30 0 6 6 13:45 0 13 13 14:00 0 20 20 14:15 0 8 8 14:30 2 13 15 14:45 1 6 7 15:00 0 21 21 15:15 0 21 21 15:30 0 10 10 15:45 0 14 14 16:00 0 27 27 16:15 0 1 1 16:30 0 3 3 16:45 0 0 0 17:00 0 3 3 17:45 0 4 4 18:00 0 2 2 <				
12:30 1 2 3 12:45 0 5 5 13:00 0 4 4 13:15 1 2 3 13:30 0 6 6 13:45 0 13 13 14:00 0 20 20 14:15 0 8 8 14:30 2 13 15 14:45 1 6 7 15:00 0 21 21 15:15 0 21 21 15:30 0 10 10 15:45 0 14 14 16:00 0 27 27 16:15 0 1 1 16:30 0 3 3 16:45 0 0 0 17:00 0 3 3 17:45 0 4 4 18:00 0 2 2 18:15 0 3 3 <				
12:45 0 5 5 13:00 0 4 4 13:15 1 2 3 13:30 0 6 6 13:45 0 13 13 14:00 0 20 20 14:15 0 8 8 14:15 0 8 8 14:30 2 13 15 14:45 1 6 7 15:00 0 21 21 15:15 0 21 21 15:30 0 10 10 15:45 0 14 14 16:00 0 27 27 16:15 0 1 1 16:30 0 3 3 17:00 0 3 3 17:45 0 4 4 18:00 0 2 2 18:15 0 3 3 18:30 0 1 1 <				
13:00 0 4 4 13:15 1 2 3 13:30 0 6 6 13:45 0 13 13 14:00 0 20 20 14:15 0 8 8 14:15 0 8 8 14:30 2 13 15 14:45 1 6 7 15:00 0 21 21 15:15 0 21 21 15:30 0 10 10 15:30 0 10 10 15:45 0 14 14 16:00 0 27 27 16:15 0 1 1 16:30 0 3 3 17:00 0 3 3 17:15 1 1 2 17:45 0 4 4 18:00 0 2 2 18:15 0 3 3				
13:15 1 2 3 13:30 0 6 6 13:45 0 13 13 14:00 0 20 20 14:15 0 8 8 14:30 2 13 15 14:45 1 6 7 15:00 0 21 21 15:15 0 21 21 15:30 0 10 10 15:45 0 14 14 16:00 0 27 27 16:15 0 1 1 16:30 0 3 3 16:45 0 0 0 17:00 0 3 3 17:45 0 4 4 18:00 0 2 2 18:15 0 3 3 18:30 0 1 1 18:45 0 2 2				
13:30 0 6 6 13:45 0 13 13 14:00 0 20 20 14:15 0 8 8 14:30 2 13 15 14:45 1 6 7 15:00 0 21 21 15:15 0 21 21 15:30 0 10 10 15:45 0 14 14 16:00 0 27 27 16:15 0 1 1 16:30 0 3 3 16:45 0 0 0 17:00 0 3 3 17:15 1 1 2 17:45 0 4 4 18:00 0 2 2 18:15 0 3 3 18:45 0 2 2				
13:45 0 13 13 14:00 0 20 20 14:15 0 8 8 14:30 2 13 15 14:45 1 6 7 15:00 0 21 21 15:15 0 21 21 15:30 0 10 10 15:45 0 14 14 16:00 0 27 27 16:15 0 1 1 16:30 0 3 3 16:45 0 0 0 17:00 0 3 3 17:15 1 1 2 17:45 0 4 4 18:00 0 2 2 18:15 0 3 3 18:30 0 1 1 18:45 0 2 2				
14:00 0 20 20 14:15 0 8 8 14:30 2 13 15 14:45 1 6 7 15:00 0 21 21 15:15 0 21 21 15:30 0 10 10 15:45 0 14 14 16:00 0 27 27 16:15 0 1 1 16:30 0 3 3 16:45 0 0 0 17:00 0 3 3 17:15 1 1 2 17:45 0 4 4 18:00 0 2 2 18:15 0 3 3 18:30 0 1 1 18:45 0 2 2				
14:15 0 8 8 14:30 2 13 15 14:45 1 6 7 15:00 0 21 21 15:15 0 21 21 15:30 0 10 10 15:45 0 14 14 16:00 0 27 27 16:15 0 1 1 16:30 0 3 3 16:45 0 0 0 17:00 0 3 3 17:15 1 1 2 17:45 0 4 4 18:00 0 2 2 18:15 0 3 3 18:30 0 1 1 18:45 0 2 2				
14:30 2 13 15 14:45 1 6 7 15:00 0 21 21 15:15 0 21 21 15:30 0 10 10 15:45 0 14 14 16:00 0 27 27 16:15 0 1 1 16:30 0 3 3 16:45 0 0 0 17:00 0 3 3 17:15 1 1 2 17:45 0 4 4 18:00 0 2 2 18:15 0 3 3 18:30 0 1 1 18:45 0 2 2				
14:45 1 6 7 15:00 0 21 21 15:15 0 21 21 15:30 0 10 10 15:45 0 14 14 16:00 0 27 27 16:15 0 1 1 16:30 0 3 3 16:45 0 0 0 17:00 0 3 3 17:15 1 1 2 17:30 2 2 4 18:00 0 2 2 18:15 0 3 3 18:30 0 1 1 18:45 0 2 2				
15:00 0 21 21 15:15 0 21 21 15:30 0 10 10 15:45 0 14 14 16:00 0 27 27 16:15 0 1 1 16:30 0 3 3 16:45 0 0 0 17:00 0 3 3 17:15 1 1 2 17:30 2 2 4 18:00 0 2 2 18:15 0 3 3 18:30 0 1 1 18:45 0 2 2				
15:15 0 21 21 15:30 0 10 10 15:45 0 14 14 16:00 0 27 27 16:15 0 1 1 16:30 0 3 3 16:45 0 0 0 17:00 0 3 3 17:15 1 1 2 17:30 2 2 4 17:45 0 4 4 18:00 0 2 2 18:15 0 3 3 18:30 0 1 1 18:45 0 2 2				
15:30 0 10 10 15:45 0 14 14 16:00 0 27 27 16:15 0 1 1 16:30 0 3 3 16:45 0 0 0 17:00 0 3 3 17:15 1 1 2 17:30 2 2 4 17:45 0 4 4 18:00 0 2 2 18:15 0 3 3 18:30 0 1 1 18:45 0 2 2				
15:45 0 14 14 16:00 0 27 27 16:15 0 1 1 16:30 0 3 3 16:45 0 0 0 17:00 0 3 3 17:15 1 1 2 17:30 2 2 4 17:45 0 4 4 18:00 0 2 2 18:15 0 3 3 18:30 0 1 1 18:45 0 2 2				
16:00 0 27 27 16:15 0 1 1 16:30 0 3 3 16:45 0 0 0 17:00 0 3 3 17:15 1 1 2 17:30 2 2 4 17:45 0 4 4 18:00 0 2 2 18:15 0 3 3 18:30 0 1 1 18:45 0 2 2				
16:15 0 1 1 16:30 0 3 3 16:45 0 0 0 17:00 0 3 3 17:15 1 1 2 17:30 2 2 4 17:45 0 4 4 18:00 0 2 2 18:15 0 3 3 18:30 0 1 1 18:45 0 2 2				
16:30 0 3 3 16:45 0 0 0 17:00 0 3 3 17:15 1 1 2 17:30 2 2 4 17:45 0 4 4 18:00 0 2 2 18:15 0 3 3 18:30 0 1 1 18:45 0 2 2				
16:45 0 0 0 17:00 0 3 3 17:15 1 1 2 17:30 2 2 4 17:45 0 4 4 18:00 0 2 2 18:15 0 3 3 18:30 0 1 1 18:45 0 2 2				
17:00 0 3 3 17:15 1 1 2 17:30 2 2 4 17:45 0 4 4 18:00 0 2 2 18:15 0 3 3 18:30 0 1 1 18:45 0 2 2				
17:15 1 1 2 17:30 2 2 4 17:45 0 4 4 18:00 0 2 2 18:15 0 3 3 18:30 0 1 1 18:45 0 2 2				
17:30 2 2 4 17:45 0 4 4 18:00 0 2 2 18:15 0 3 3 18:30 0 1 1 18:45 0 2 2				
17:45 0 4 4 18:00 0 2 2 18:15 0 3 3 18:30 0 1 1 18:45 0 2 2				
18:00 0 2 2 18:15 0 3 3 18:30 0 1 1 18:45 0 2 2				
18:15 0 3 3 18:30 0 1 1 18:45 0 2 2		0	4	4
18:30 0 1 1 18:45 0 2 2	18:00	0	2	2
18:45 0 2 2	18:15	0	3	3
	18:30	0	1	1
TOTAL 23 320 343	18:45	0	2	2
	TOTAL	23	320	343



Location: Western Driveway on Fairway Drive

Date: Wednesday 1/8/2020

Count Type: Driveway

City: Orange

Location: Central Driveway on Fairway Drive

Date: Wednesday 1/8/2020

Count Type: Driveway

	Entering	Eviting	Total
6:00	Entering Exiting 0 1		Total 1
6:15	1	1	
			2
6:30	0	0	0
6:45	1	1	2
7:00	1	1	2
7:15	2	1	3
7:30	0	1	1
7:45	2	0	2
8:00	1	0	1
8:15	2	0	2
8:30	0	1	1
8:45	1	0	1
9:00	0	0	0
9:15	1	1	2
9:30	1	1	2
9:45	0	0	0
10:00	0	0	0
10:15	1	0	1
10:30	0	2	2
10:45	1	1	2
11:00	0	0	0
11:15	0	0	0
11:30	0	0	0
11:45	1	2	3
12:00	0	0	0
12:15	0	0	0
12:30	1	1	2
12:45	0	0	0
13:00	2	0	2
13:15	1	0	1
13:30	0	0	0
13:45	1	1	2
14:00	1	1	2
14:15	0	1	1
14:30	0	0	0
14:45	0	0	0
15:00	0	1	1
15:15	0	1	1
15:30	0	1	1
15:45	0	2	2
16:00	0	1	1
16:15	0	2	2
16:30			2
	16:45 1		1
17:00	0	0	0
17:15	0	0	0
17:30	0	0	0
17:45	0	0	0
18:00	0	0	0
18:15	0	0	0
18:30	0	0	0
18:45	0	0	0
TOTAL	24	27	51

	Entering	Exiting	Total
6:00	0	0	0
6:15	0	0	0
6:30	0	0	0
6:45	0	0	0
7:00	0	0	0
7:15	0	0	0
7:30	0	0	0
7:45	0	0	0
8:00	0	0	0
8:15	0	0	0
8:30	0	0	0
8:45	0	0	0
9:00	0	0	0
9:15	1	0	1
9:30	0	1	1
9:45	1	1	2
10:00	2	0	2
10:15	1	2	3
10:30	0	1	1
10:45	0	0	0
11:00	0	0	0
11:15	0	0	0
11:30	0	0	0
11:45	0	0	0
12:00	0	0	0
12:15	1	1	2
12:30	0	0	0
12:45	0	0	0
13:00	0	0	0
13:15	1	1	2
13:30	0	0	0
13:45	0	0	0
14:00	0	0	0
14:15	0	0	0
14:30	0	0	0
14:45	0	0	0
15:00	0	0	0
15:15	0	0	0
15:30	0	0	0
15:45	0	0	0
16:00	0	0	0
16:15	0	0	0
16:30	0	0	0
16:45	0	0	0
17:00	0	0	0
17:15	0	0	0
17:30	0	0	0
17:45	0	0	0
18:00	0	0	0
18:15	0	0	0
18:30	0	0	0
18:45	0	0	0
TOTAL	7	7	14



Location: Eastern Driveway on Fairway Drive

Date: Wednesday 1/8/2020

Count Type: Driveway

City: Orange

Location: TOTAL DRIVEWAYS
Date: Wednesday 1/8/2020

Date: Wednesda Count Type: Driveway

	Entering	Exiting	Total
6:00	0	0	0
6:15	0	0	0
6:30	0	0	0
6:45	0	0	0
7:00	1	0	1
7:15	0	1	1
7:30	0	4	4
7:45	0	2	2
8:00	0	2	2
8:15	1	2	3
8:30	0	7	7
8:45	0	9	9
9:00	1	3	4
9:15	0	2	2
9:30	0	4	4
9:45	0	1	1
10:00	0	1	1
10:00	1	2	3
10:13	0	0	0
10:30	0	0	0
11:00	0	0	0
11:15	0	0	0
11:30	0	1	1
11:45	0	0	0
12:00			
	0	0	0
12:15 12:30	0	0	0
	0		
12:45	0	0	0
13:00	0	2	2
13:15	0	2	2
13:30	0	1	1
13:45	0	0	0
14:00	0	1	1
14:15	0	3	3
14:30	0	2	2
14:45	0	5	5
15:00	0	4	4
15:15	0	1	1
15:30	0	1	1
15:45	0	1	1
16:00	0	1	1
16:15	0	1	1
16:30	1	0	1
16:45	0	0	0
17:00	0	0	0
17:15	0	0	0
17:30	0	0	0
17:45	0	0	0
18:00	0	0	0
18:15	0	0	0
18:30	0	0	0
18:45	0	0	0
TOTAL	5	66	71

	Entering	Exiting	Total	
6:00	0 1		1	
6:15		3 2		
6:30	2	0	5 2	
6:45	5	2	7	
7:00	14	4	18	
7:15	26	11	37	
7:30	18	12	30	
7:45	19	2	21	
	18	8	26	
8:00				
8:15	15	8	23	
8:30	24	16	40	
8:45	22	13	35	
9:00	15	20	35	
9:15	16	8	24	
9:30	12	12	24	
9:45	15	7	22	
10:00	11	12	23	
10:15	5	7	12	
10:30	4	8	12	
10:45	2	5	7	
11:00	3	8	11	
11:15	2	6	8	
11:30	6	6	12	
11:45	5	4	9	
12:00	2	7	9	
12:15	9	6	15	
12:30	12	3	15	
12:45	13	5	18	
13:00	7	6	13	
13:15	12	5	17	
13:30	6	7	13	
13:45	10	14	24	
14:00	12	24	36	
14:15	11	12	23	
14:30	9	15	24	
14:45	11	11	22	
15:00	14	26	40	
15:15	4	23	27	
15:30	11	13	24	
15:45	8	17	25	
16:00	4	30	34	
16:15	2	4	6	
16:30	3	4	7	
16:45	2	0	2	
17:00	1	3	4	
17:15	2	4	6	
17:30	2	2	4	
17:45	2	4	6	
18:00	2	4	6	
18:15	3	4	7	
18:30	0	1	1	
18:45	3	2	5	
TOTAL	439	438	877	
.0.71			J.,	

ATTACHMENT B REHABILITATION INSTITUTE OF SOUTHERN CALIFORNIA TWO-DAY AVERAGE HOURLY TRIP GENERATION


	Hour Beginning At	Inbound	Outbound	Total	
	6:00	10	4	14	
	6:15	23	9	32	
	6:30	49	15	64	
	6:45	65	24	89	
	7:00	74	27	101	
¥ο	7:15	78		108	
AM PEAK PERIOD	7:30	70	30	100	
PEF	7:45	75	36	111	
4	8:00	83	42		← AM Peak Hour
	8:15	81	53		← Hour of Highest Trip Generation
	8:30	78		132	Constitution of the grant of th
	8:45	63	50	113	
	9:00	55	47	102	
	9:15	51	39	90	
	9:30	41	39	80	
	9:45	35		70	
	10:00	25	32	57	
	10:15	16	29	45	
	10:30	11	27	38	
	10:45	12	25	37	
	11:00	14	26	40	
	11:15	14	25	39	
	11:30	20		43	
	11:45	27	22	49	
	12:00	33	22	55	
	12:15	37	21	58	
	12:30	39	22	61	
	12:45	36	25	61	
	13:00	36	32	68	
	13:15	40		84	
	13:30	38	51	89	
	13:45	42	61	103	
	14:00	43	61	104	
	14:15	47	72	119	
	14:30	45	82	127	
	14:45	49	83	132	
	15:00	43	87	130	
	15:15	31	85	116	
	15:30	27	67	94	
-	15:45	14	53	67	
	16:00	10	38	48	← PM Peak Hour
PM PEAK PERIOD	16:15	9	15	24	
PM PEAK PERIOD	16:30	8	14	22	
≥ 4 34	16:45	8	12	20	
	17:00	8		24	
	17:15	7	14	21	
	17:30	7	13	20	
	17:45	6	12	18	
	18:00	5	9	14	
	18:15	4	7	11	
	18:30	2	3	5 5	
	18:45	2	3	5	

DAILY TOTALS 436 440

876




ATTACHMENT C PROJECT TRIP DISTRIBUTION PERCENTAGES



FN: LaVeta(1800 E)RehabOrange\PROJ-DIST



Attachment 20. CalFIRE Fire Hazard Severity Zones Map



Attachment 21. Climate Mapping for Resilience and Adaptation

